

## 1049-2017ADDENDUM 3

### PROVISION OF FIBRE OPTIC CABLE FROM WEST END SEWAGE TREATMENT PLANT (WEWPCC) TO PERIMETER ROAD PUMPING STATION (PRPS)

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: February 23, 2018  
BY: Amanda Wolfe  
TELEPHONE NO. 204 986-2808

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20160708

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART B – BIDDING PROCEDURES**

Revise: B2.1 The Submission Deadline is 4:00 p.m. Winnipeg time, March 6, 2018.

#### **PART D – SUPPLEMENTAL CONDITIONS**

Add: D23 PROPOSED ROUTE

D23.1 As part of the Submissions section, the Contractor shall provide the Contract Administrator with a preliminary fibre cable route within ten (10) Calendar Days of notification of the award of Contract by Purchase Order. The preliminary route must be approved by the Contract Administrator in writing a minimum of fifteen (15) Calendar Days prior to the installation.

D23.2 The fibre cable route is subject to the following restriction:

(a) The fibre cable shall not be installed underneath the snow dump area at WEWPCC. The snow dump area is outlined in revised Drawing 1-0103A-E0021-R1.

Add: D24 HOURS OF WORK

D24.1 As part of the Control of Work section, the hours of Work on City property, including WEWPCC and PRPS, are 7:30 am to 3:30 pm on weekdays. No Work will be permitted on City property on evenings after 3:30 pm, weekends, Statutory Holidays or Civic Holidays unless approved by the Contract Administrator in writing.

#### **PART E – SPECIFICATIONS**

Replace 1049-2017\_NMS\_Format\_Specifications with 1049-2017\_NMS\_Addendum 3\_Format\_Specifications\_R1. The following is a summary of changes incorporated in the replacement specifications:

Section 26 05 34

3.1.7.1 Maintain the following minimum clearances for underground conduit runs:

Add: .4 Fibre conduit installed concurrently: 50 mm

Section 40 95 80

### 1.3.3.7 Proposed Route

Revise: .2 Submit the **detailed fibre cable** route, location of handholes, and location of underground services within one metre of the proposed route for review by the Contract Administrator at least 30 days prior to the planned initiation of the work. The **detailed** route must be approved **by the Contract Administrator in writing** a minimum of 15 days prior to the installation.

## **DRAWINGS**

Replace: 1049-2017\_Drawing\_1-0103A-E0021-R0 with 1049-2017\_Addendum\_3\_Drawing\_1-0103A-E0021-R1

## **QUESTIONS AND ANSWERS**

- Q1 Can a dwg file of the site be provided?
- A1 Not at this time. The AutoCAD file can be provided to the Contractor after award of Contract.
- Q2 Is "fiber blowing" an acceptable installation method?
- A2 As per Specification 40 95 80, the cable must be installed in accordance with manufacturer's requirements.
- Q3 Once the contract is awarded, if changes to the conduit route are required, for example, because of permit requirements, how will the changes be managed?
- A3 Changes in Work will be managed according to Section C7 of the General Conditions for Construction.
- Q4 Could we submit a map showing the proposed route with the bid?
- A4 Bidders may submit a map showing the proposed fibre cable route with the bid. This is optional; it is not a mandatory requirement. Bids will be evaluated in accordance with section B16 Evaluation of Bids of the Bid Opportunity document.