

9-2018 ADDENDUM 3

SHOAL LAKE AQUEDUCT CROSSING AND ASSOCIATED ROADWORKS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: January 25, 2018
BY: Graeme Loeppky
TELEPHONE NO. (204) 453-2353 Ext . 4066

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20130301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Revise: E15.2.2 (a) to read: Install drainage pipes behind and on the sides of the abutments as directed by the Contract Administrator;
- Revise: E15.2.4 (a) to read: Install subdrains completed with all necessary connections, penetrations through wing walls, and terminations as per directed by the Contract Administrator;
- Delete: E16.4.12 (c)
- Revise: E16.5.4 (a) to read: Concrete shall be placed so that the aggregates will not separate or segregate. The concrete shall be vibrated throughout the upper three (3) meters of the steel pipe pile.
- Add: E30.2.3 Information on the train operation may be inquired from Ed Clarkson, the Aqueduct and Railway Supervisor, at (204) 986-4121.