



**THE CITY OF WINNIPEG**

# **BID OPPORTUNITY**

**BID OPPORTUNITY NO. 187-2004**

**SAND AND SALT STORAGE FACILITY AT 1539 WAVERLEY, YARD WORKS**

**PREPARED FOR: The City of Winnipeg**

**PREPARED BY:**  **UMA Engineering Ltd.**  
Engineers & Planners

UMA JOB NO. 41 09 0265 366 00

## TABLE OF CONTENTS

### PART A - BID SUBMISSION

Form A: Bid	1
FORM B: PRICES	4
Form G1: Bid Bond and Agreement to Bond	8
Form G2: Irrevocable Standby Letter of Credit and Undertaking	10

### PART B - BIDDING PROCEDURES

B1. Project Title	1
B2. Submission Deadline	1
B3. Site Investigation	1
B4. Enquiries	1
B5. Addenda	1
B6. Substitutes	2
B7. Bid Submission	3
B8. Bid	3
B9. Prices	4
B10. Qualification	4
B11. Bid Security	5
B12. Opening of Bids and Release of Information	5
B13. Irrevocable Bid	6
B14. Withdrawal of Bids	6
B15. Evaluation of Bids	6
B16. Award of Contract	7

### PART C - GENERAL CONDITIONS

C1. General Conditions	1
------------------------	---

### PART D - SUPPLEMENTAL CONDITIONS

#### General

D1. General Conditions	1
D2. Scope of Work	1
D3. Contract Administrator	1
D4. Contractor's Supervisor	1
D5. Notices	2
D6. Furnishing of Documents	2

#### Submissions

D7. Performance Security	2
D8. Insurance	3
D9. Subcontractor List	3
D10. Detailed Work Schedule	3

#### Schedule of Work

D11. Commencement	4
D12. Working Days	4
D13. Restricted Work Hours	4
D14. Work By Others	5
D15. Substantial Performance	5
D16. Total Performance	5
D17. Liquidated Damages	6
D18. Scheduled Maintenance	6

#### Control of Work

D19. Job Meetings	6
-------------------	---

D20. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	6
<b>Warranty</b>	
D21. Warranty	7
Form H1: Performance Bond	8
Form H2: Irrevocable Standby Letter of Credit	10
Form J: Subcontractor List	12
Form L: Detailed Work Schedule	13

## **PART E - SPECIFICATIONS**

### **General**

E1. Applicable Specifications, Standard Details and Drawings	1
E2. Codes and Standards	1
E3. Site Investigation Report	1
E4. Verification of Weights	2
E5. Truck Weight Limits	2
E6. Protection of Existing Trees	2
E7. Water Used by Contractor	3
E8. Surface Restorations	3
E9. Provisional Items	3
E10. Removal and Salvaging Existing Chain Link Fence	3
E11. Watermains	4
E12. Wastewater Sewers	6
E13. Land Drainage Sewers	8
E14. Sewer Manholes	9
E15. Deflection Testing	10
E16. Preparation of Existing Site	11
E17. Installation of Drainage Inlets	11
E18. Portland Cement Concrete Pavement Works	12
E19. Topsoil and Finish Grading	14
E20. Trees and Shrubs	15
E21. Cast-In-Place Concrete Piles	20
E22. Wood Fencing	21
E23. Bollards	22
E24. Electrical General Requirements	23
E25. Installation of Cables in Trenches and in Ducts	27
E26. Grounding – Secondary	28
E27. Fastenings and Supports	30
E28. Wires and Cables (0-1000 V)	30
E29. Splitters, Junction, Pull Boxes and Cabinets	31
E30. Outlet Boxes, Conduit Boxes and Fittings	32
E31. Conduits, Conduit Fastenings and Conduit Fittings	33
E32. Wiring Devices	34
E33. Wire and Box Connectors 0-1000 V	35
E34. Outdoor Equipment Enclosures	36
E35. Moulded Case Circuit Breakers	37
E36. Contactors	37
E37. Panelboards Breaker Type	38
E38. Lighting Equipment	39
E39. Floodlighting-Exterior	41
E40. Street Lighting Poles and Luminaires	42
E41. Lighting Control Equipment Photoelectric	43

Appendix A – Test Hole Logs