



ADDENDUM NO. 1 BID OPPORTUNITY NO. 188-2004

SUPPLY AND INSTALL TRAFFIC WAYFINDER SIGN SYSTEM

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: September 15, 2004
BY: Coleen Groening /c
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20040901

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid Submission non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

Revise D11.1 to read:

D11.1 The Contractor shall achieve Substantial Performance by July 31, 2005.

Revise D12.1 to read:

D12.1 The Contractor shall achieve Total Performance by August 31, 2005.

Revise D13. LIQUIDATED DAMAGES to read:

D13. LIQUIDATED DAMAGES

D13.1 If the Contractor fails to achieve critical stages, Substantial Performance or Total Performance in accordance with the Contract by the days fixed herein for same, the Contractor shall pay the City the following amounts per Calendar Day for each and every Calendar Day following the days fixed herein for same during which such failure continues:

- (a) Stage 1 Work – One Hundred and Fifty dollars (\$150.00);
- (b) Stage II Work – One Hundred and Fifty dollars (\$150.00);
- (c) Substantial Performance – One Hundred and Fifty dollars (\$150.00);

D13.2 The amounts specified for liquidated damages in D13.1 are based on a genuine pre-estimate of the City's losses in the event that the Contractor does not achieve critical stages or Substantial Performance by the days fixed herein for same.

D13.3 The City may reduce any payment to the Contractor by the amount of any liquidated damages assessed.

Add D18. CRITICAL STAGES:

D18. CRITICAL STAGES

D18.1 The Contractor shall achieve critical stages of the Work in accordance with the following requirements:

- (a) Stage I Work Completion Date shall be **December 31, 2004**.
- (b) Stage II Work Completion Date shall be **July 31, 2005**.

D18.2 Stage I Work shall include the supply and installation of the following 47 sign structures, complete with sign boxes/plates and sign message information, applicable to all six Alternatives by the stipulated date.

Item No.	Structure No.	Location Code
1	WF013	BE5
2	WF039	MN2
3	WF041	MN4
4	WF044	MN7
5	WF047	MN9-F1
6	WF048	MN9-F2
7	WF049	MN9-F3
8	WF052	MS1-F
9	WF054	MS2-F1
10	WF055	MS2-F2
11	WF056	MS3
12	WF060	MS7
13	WF061	MS8
14	WF062	MS9
15	WF069	PE5
16	WF070	PE5-F1
17	WF071	PE5-F2
18	WF073	PE6-F
19	WF074	PE7
20	WF075	PE7-F1
21	WF076	PE7-F2
22	WF078	PE8-F
23	WF080	PE9-F1
24	WF081	PE9-F2
25	WF089	PiW5
26	WF090	PiW6
27	WF095	PW3-F1
28	WF096	PW3-F2
29	WF097	PW4
30	WF098	PW5
31	WF099	PW5-F1
32	WF100	PW5-F2
33	WF109	Sm1
34	WF112	Sm4
35	WF113	Sm4-F1
36	WF114	Sm4-F2
37	WF115	Sm5
38	WF116	Sm5-F
39	WF118	Sm6-F
40	WF119	St1
41	WF120	St2
42	WF121	St3
43	WF122	St4
44	WF123	St5
45	WF124	St5-F
46	WF129	St8
47	WF130	St8-F

D18.3 Stage II Work shall include the supply and installation of the remaining structures in each Alternative as well as final site restoration at all locations by the stipulated dates.

PART E – SPECIFICATIONS

Revise E3.2.9 to read:

E3.2.9 Paint

The paint system for hot-dip galvanized posts shall consist of a high-build epoxy primer and two coats of urethane topcoat. Approved paint products are Davoe Coatings Devron 201 Universal Epoxy Primer and Devthane 369 Aliphatic Urethane Gloss Enamel for topcoat. The finish colour shall be Pantone Matching System PMS 2738, dark blue. However, the Contract Administrator will supply a swatch sample to the Contractor to match the colour prior to painting.

Revise E3.4.6 to read:

E3.4.6 Painting

All painting shall be carried out in the shop.

For the previously hot-dip galvanized steel items, including posts, base plates, brackets, shrouds, and reaction plates, the paint system for Alternatives 1, 2, and 3 shall be applied as follows:

- a) Surface preparation involving sweep blasting to SSPC-SP7.
- b) One coat of high build epoxy primer with 3 to 4 mils dry film thickness.
- c) Two coats of urethane top coat with each coat 2 to 3 mils dry film thickness. Colour to match Pantone Colour Matching System 2738.

For Alternatives 4, 5, and 6, the posts and breakaway bases are not to be painted.

Revise E5.2.10 to read:

E5.2.10 Paint

The paint system for sign boxes of Alternatives 1, 2, and 3 shall consist of an epoxy primer and two coats of urethane topcoat. Approved paint products are Davoe Coatings Devron 201 Universal Epoxy Primer and Devthane 369 Aliphatic Urethane Gloss Enamel for topcoat. The paint finish colour shall be dark blue to match Pantone Matching System PMS 2738.

Revise E5.3.1 f) to read:

E5.3.1 f) The sign box extrusion, including screw heads, shall be painted dark blue to match Pantone Matching System 2738, being the colour of the posts for Alternatives 1, 2, and 3. The paint system shall be applied as follows:

- i) Totally wipe clean with solvent both the outside and inside surfaces. Do light sanding and rub surface down with tack cloth.
- ii) Apply one coat of epoxy primer on both the outside and inside surfaces with 3 to 4 mils dry film thickness.
- iii) Apply two coats of urethane topcoat on both the outside and inside surfaces, each coat to be 2 to 3 mils dry film thickness.

Replace Drawing WF-04-08-R0 with Drawing WF-04-08-R1

Add: Appendix A-Inventory List ALT 2

Add: Appendix A- Inventory List ALT 3

Replace Appendix A – Installations with:

- Appendix A – Installations ALT 1-a thru g
- Appendix A – Installations ALT 2-a thru f
- Appendix A – Installations ALT 3-a thru e

Note:

The document listed under Appendix A – Installations was too large to open so we are re-issuing them broken down into several smaller files.

Revise: Table in E5 as follows:

TABLE E1

Item No./Folder	PDF Files		
1. Inventory List	Inventory List – Sep 3-04 Inventory List ALT 2 – Sept 10-04 Inventory List ALT 3 – Sept 10-04		
2. Site Maps	Sign Plans_Maps_ALT 1 Sign Plans_Maps_ALT 2 Sign Plans_Maps_ALT 3		
3. Installations	Installations_ALT 1-a Installations_ALT 1-b Installations_ALT 1-c Installations_ALT 1-d Installations_ALT 1-e Installations_ALT 1-f Installations_ALT 1-g	Installations_ALT 2-a Installations_ALT 2-b Installations_ALT 2-c Installations_ALT 2-d Installations_ALT 2-e Installations_ALT 2-f	Installations_ALT 3-a Installations_ALT 3-b Installations_ALT 3-c Installations_ALT 3-d Installations_ALT 3-e
4. Sign Art	Sign Art_ALT 1 Sign Art_ALT 2 Sign Art_ALT 3		
5. Kit of Parts	Kit of Parts		
6. Box Sign Back Logo	Box Sign Back Logo		