

PART E
SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. GENERAL

E1.1 These Specifications shall apply to the Work.

E1.2 The following Drawings are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing</u>
Figure 2	Concrete Reinforced Pad

E2. GOODS

E2.1 The Contractor shall supply and deliver concrete reinforced pads in accordance with the requirements hereinafter specified.

E2.2 Item No. 1 - concrete reinforced pads shall be 2' (ft) x 3' (ft) x 2" (in) .

- (a) reinforced with 3/8" (in) rebar, running diagonally from corner to corner;
- (b) minimum strength to 40 MPA; and
- (c) non-slip surface (diamond shaped).

E3. DELIVERY

E3.1 Goods shall be delivered within thirty (30) Calendar Days of the award of Contract, f.o.b. destination, freight prepaid to:

Winnipeg Transit
421 Osborne Street
Winnipeg, MB

E3.2 Goods shall be delivered between 7:30 a.m. and 2:00 p.m. on Business Days.

E3.3 The Contractor shall off-load goods as directed at the delivery location.

E3.4 The Contractor shall contact Brian Newton @ (204) 986-5812 prior to delivery.