



THE CITY OF WINNIPEG

BID OPPORTUNITY

BID OPPORTUNITY NO. 389-2004

SECONDARY DIKE 265, 271, 275 SCOTIA STREET

**PREPARED FOR: The City of Winnipeg
Water and Waste Department**

PREPARED BY:  **UMA Engineering Ltd.
Engineers & Planners**

UMA JOB NO. 41 01 0265 361 01

TABLE OF CONTENTS

PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	3

PART B - BIDDING PROCEDURES

B1. Project Title	1
B2. Submission Deadline	1
B3. Site Meeting	1
B4. Enquiries	1
B5. Addenda	1
B6. Substitutes	2
B7. Bid Submission	3
B8. Bid	3
B9. Prices	4
B10. Qualification	4
B11. Opening of Bids and Release of Information	5
B12. Irrevocable Bid	5
B13. Withdrawal of Bids	5
B14. Evaluation of Bids	6
B15. Award of Contract	6

PART C - GENERAL CONDITIONS

C1. General Conditions	1
------------------------	---

PART D - SUPPLEMENTAL CONDITIONS

General

D1. General Conditions	1
D2. Definitions	1
D3. Scope of Work	1
D4. Contract Administrator	2
D5. Contractor's Supervisor	2
D6. Notices	2

Submissions

D7. Performance Security	3
D8. Insurance	3
D9. Subcontractor List	3

Schedule of Work

D10. Commencement	4
D11. Substantial Performance	4
D12. Total Performance	4
D13. Liquidated Damages	5
D14. Scheduled Maintenance	5

Control of Work

D15. Job Meetings	5
D16. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	5

Warranty

D17. Warranty	6
D18. Site Access and Traffic Control	6
D19. Hours of Work	6
D20. Protection and Replacement of Trees	7
D21. Encroachment on Private Property	7

Template Version: C320040618

D22. Damage to Existing Structures and Property	7
D23. Protection of River Channel	8
D24. Site Restoration	8
D25. Environmental Protection	8
D26. Private Property Inspections	10
Form H1: Performance Bond	11
Form H2: Irrevocable Standby Letter of Credit	13
Form J: Subcontractor List	15

PART E - SPECIFICATIONS

General

E1. Applicable Specifications, Standard Details and Drawings	1
E2. Soils Investigation Report	1
E3. Truck Weight Limits	1
E4. Site Access And Restoration Of Gravel Surfaces	1
E5. Sediment Control Measures	2
E6. Site Preparation and Associated Works	3
E7. Stockpiling And Storage Of Materials	4
E8. Earth Works	5
E9. Segmental Block Retaining Wall	7
E10. Lot Drain	10
E11. Residential Sewer Isolation valves	12
E12. Sodding	13