

PART E

SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. GENERAL

- E1.1 These Specifications shall apply to the Work.
- E1.2 Where the word “**Owner**” is found on the Drawings replace with City of Winnipeg.
- E1.3 Where the word “**Consultant**” is found on the Drawings replace with Contract Administrator.
- E1.4 The following Drawings are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Detail Sheets</u>
WF-1	Pedestrian Wayfinder System (October 20, 2004)
WF-2	Pedestrian Wayfinder System (October 20, 2004)
WF-3	Pedestrian Wayfinder System (October 20, 2004)
WF-4	Pedestrian Wayfinder System (October 20, 2004)
WF-5	Pedestrian Wayfinder System (October 20, 2004)
WF-6	Pedestrian Wayfinder System (October 20, 2004)
A6a	Graham Skywalk (October 21, 2004)
A6b	Graham Skywalk (October 21, 2004)
A6c – side 1	Graham Skywalk (October 21, 2004)
A6c – side 2	Graham Skywalk (October 21, 2004)
A6d – side 1	Graham Skywalk (October 21, 2004)
A6d – side 2	Graham Skywalk (October 21, 2004)
A7 – side 1	Graham Skywalk (October 21, 2004)
A7 – side 2	Graham Skywalk (October 21, 2004)
A8 – side 1	Graham Skywalk (October 21, 2004)
A8 – side 2	Graham Skywalk (October 21, 2004)
A9a	Graham Skywalk (October 21, 2004)
A9b	Graham Skywalk (October 21, 2004)
A9c	Graham Skywalk (October 21, 2004)
A12	Portage Skywalk (October 21, 2004)
A13	Graham Skywalk (October 21, 2004)
A14a	Portage Skywalk (October 21, 2004)
A14b	Portage Skywalk (October 21, 2004)
A14c	Portage Skywalk (October 21, 2004)
A14d	Portage Skywalk (October 21, 2004)
A15	Portage Skywalk (October 21, 2004)
A16	Portage Skywalk (October 21, 2004)

E2. GOODS

- E2.1 The Contractor shall supply and deliver acrylic interior directional signs in accordance with the requirements hereinafter specified.
- E2.2 The Winnipeg (interior) walkway system in Downtown has been named the “W”, and will be marked by a directional sign system. Many of the signs will feature a three (3) dimensional “W” logo, to be made of painted MDF material.
- E2.3 Acrylic sheets are to be painted (except for white sub-panels), with 3-D logo and cut vinyl letters applied as indicated on the attached detail sheets. Many of the panels will feature “sub-panels” to be attached to the main panel using 3M **VHB** tape, as per the manufacturer’s specifications.

NOTE:

- (a) Four (4) of the signs are double sided, thus there are 21 sign sides to be prepared,
- (b) Nine (9) of the sign sides do NOT have a 3-D logo, thus only 12 3-D logo are required.

E2.4 For the Contractor reference only, signs suspended from ceiling will be attached using Mustang System stainless steel units which attach to the sign with friction screws, no holes required. The signs that will be attached to walls will be attached using 3M **VHB** tape.

E3. DELIVERY

E3.1 Goods shall be delivered by November 09, 2004, f.o.b. destination, freight prepaid to 65 Garry Street. The Contractor shall confirm the delivery date to the Contract Administrator, if **the location changes**, the Contract Administrator will update the delivery address to the Contractor.

E3.2 Goods shall be delivered between 8:30 a.m. and 4:30 p.m. on Business Days.