



THE CITY OF WINNIPEG

BID OPPORTUNITY

BID OPPORTUNITY NO. 536-2004

**MARYLAND TWIN BRIDGES REHABILITATION PROJECT
WEST BRIDGE REHABILITATION**

TABLE OF CONTENTS

PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	4
Form G1: Bid Bond and Agreement to Bond	9
Form G2: Irrevocable Standby Letter of Credit and Undertaking	11

PART B - BIDDING PROCEDURES

B1. Project Title	1
B2. Submission Deadline	1
B3. Enquiries	1
B4. Addenda	1
B5. Substitutes	2
B6. Bid Submission	3
B7. Bid	3
B8. Prices	4
B9. Qualification	4
B10. Bid Security	5
B11. Opening of Bids and Release of Information	6
B12. Irrevocable Bid	6
B13. Withdrawal of Bids	6
B14. Evaluation of Bids	7
B15. Award of Contract	7

PART C - GENERAL CONDITIONS

C1. General Conditions	1
------------------------	---

PART D - SUPPLEMENTAL CONDITIONS

General

D1. General Conditions	1
D2. Scope of Work	1
D3. Contract Administrator	1
D4. Contractor's Supervisor	2
D5. Notices	2
D6. Furnishing of Documents	2

Submissions

D7. Safe Work Plan	2
D8. Performance Security	3
D9. Insurance	3
D10. Subcontractor List	4
D11. Detailed Work Schedule	4

Schedule of Work

D12. Commencement	4
D13. Substantial Performance	5
D14. Total Performance	5
D15. Liquidated Damages	5
D16. Scheduled Maintenance	5

Control of Work

D17. Job Meetings	6
D18. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	6
D19. Layout of the Work	6

Warranty

D20. Warranty	6
D21. Environmental Protection Plan	7
Form H1: Performance Bond	14
Form H2: Irrevocable Standby Letter of Credit	16
Form J: Subcontractor List	18

PART E - SPECIFICATIONS

E1. Applicable Specifications, Standard Details and Drawings	1
E2. Office Facilities	2
E3. Night Work and Noise Limitations	2
E4. Mobilization and Demobilization	3
E5. Traffic and Pedestrian Control and Detour Diversion Works	4
E6. Excavation	6
E7. Structural Concrete and Other Removals	7
E8. Electrical Conduit and Reinforced Concrete Encasement	9
E9. Supplying and Placing Reinforcing Steel	12
E10. Expansion Joints	14
E11. Structural Concrete	20
E12. Backfill	48
E13. Precast Concrete Girder Corrosion Protection Works	49
E14. Supply and Installation of Aluminum Pedestrian Handrail and Life Preserver Enclosure	51
E15. Transition Curb installation	55
E16. Navigation Lights	55
E17. Roadway Lighting	57
E18. Installation of Aluminum Balanced Barrier and Aluminum Bridge Barrier	57
E19. St. James Bridge Southbound Median Bull-Nose Works	59