



## 385-2005 ADDENDUM No. 1

### 2005 COMBINED SEWER RENEWALS BY CIPP – CONTRACT 13

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: July 12, 2005  
BY: T. Whiteside  
TELEPHONE NO. (204) 986-4451^

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20050506

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART E – SPECIFICATIONS**

Add: **E5 SUSPENSION OF WORK ACTIVITIES WHEN SEWER CONTROL GATES ARE ACTIVATED DURING PERIODS OF HIGH RIVER LEVELS**

- E5.1 The Contractor is advised that as the elevation of the Red and Assiniboine Rivers rise from the normal winter or summer levels due to spring runoff or periods of heavy rainfall the City is required to close various control gates located on sewer system outfalls. Similarly, as the elevation of the rivers drop to normal levels, the City is required to open the control gates that have been closed. Control gates begin to be closed when river levels reach elevation 224.51 (James Avenue 9.0). As well, higher river levels can cause the level of flow in sewers can be higher than normal.
- E5.2 In the event the Red and Assiniboine Rivers rise to an elevation where the City has to begin closing control gates, the Contract Administrator will direct that work activities in any sewers affected by the gate closure be suspended and the risk of runoff causing flooding in the sewer evaluated. Work will continue to be suspended as long as there is a risk of the sewer being flooded while the control gate is closed unless the Contractor provides flow control measures approved jointly by the Contract Administrator, City of Winnipeg Collection System and Flood Control Branch and Local Services Branch.
- E5.3 Similarly, as river elevations drop and the City has to open control gates that have been closed, the Contract Administrator will direct that work activities in any sewers affected by the control gate opening be suspended due to the risk of the river flooding the sewer once the gate is opened. Work will continue to be suspended as long as the sewer is being flooded from the river unless the Contractor provides flow control measures approved jointly by the Contract Administrator, City of Winnipeg Collection System and Flood Control Branch and Local Services Branch.
- E5.4 The Contractor will have no claim for extra work or compensation as a result of suspension of work due to the City closing and opening control gates during periods of rising and dropping river levels. If in the opinion of the Contract Administrator the suspension will cause the completion of the Work to occur after the specified date for Critical Stages or Substantial Performance and the Contractor's schedule would have reasonably permitted completion of the Work before the required date, the date for Critical Stages or Substantial Performance will be adjusted accordingly.