

CP-H11A	Generator Communication Panel		Jumper or Internal Cable	Conductor #	Cable	Cable Information
Comments						
			Switch 1			
Primary Generator PLC	RJ-45 To Switch 3: 01	01				
Standby Generator PLC		02		RJ-45	C-CP-H11-C01	4-Pair #24 AWG - Cat 5E TO CP-H11
Spare		03		RJ-45	C-CP-H11-C02	4-Pair #24 AWG - Cat 5E TO CP-H11
Spare		04				
Spare		05				
Spare		06				
Plant Control Network Receive	PP1: 01	07-Rx				
Plant Control Network Transmit	PP1: 02	07-Tx				
Plant Control Network Receive	PP1: 14	08-Rx				
Plant Control Network Transmit	PP1: 13	08-Tx				
			Switch 2			
Spare		01		RJ-45	C-WTPWSH11 01-C01	4-Pair #24 AWG - Cat 5E TO WTPWSH11 01
Spare		02				
Spare		03				
Spare		04				
Spare		05				
Spare		06				
Plant Monitoring Network Receive	PP1: 05	07-Rx				
Plant Monitoring Network Transmit	PP1: 06	07-Tx				
Plant Monitoring Network Receive	PP1: 18	08-Rx				
Plant Monitoring Network Transmit	PP1: 17	08-Tx				

<b>NOTES:</b> 1. Panel and Cabling are not in Contract 742-2005. Drawing Issued for Information Only.	B.M. ELEV.			 		<b>ENGINEER'S SEAL</b>  ORIGINAL SIGNED BY S.W. TORMEY 2006/03/29  CONSULTANT DRAWING NO. WH-A0507	<b>THE CITY OF WINNIPEG</b> <b>WATER AND WASTE DEPARTMENT</b> <b>ENGINEERING DIVISION</b>			
				DESIGNED BY	SWT		CHECKED BY	SWT	WATER TREATMENT PLANT PLANT UTILITIES MECHANICAL AND ELECTRICAL	CITY FILE NUMBER
				DRAWN BY	SWT		APPROVED BY	AHL		SHEET 7 OF 63
				SCALE: NTS			RELEASED FOR CONSTRUCTION BY: R. SOROKOWSKI			CITY DRAWING NUMBER
		0	ISSUED FOR TENDER	06/03/29	SWT					1-0601H-J-A0507-001-00B
		NO. REVISIONS	DATE	BY	DATE	2006/03/29	DATE	2006/03/29		



Certificate of Authorization  
 Earth Tech Canada Inc.  
 No. 730 Expiry: April 30, 2006.

Monday, April 03, 2006