CP-O30A Ozone Communication Panel

Comments	Jumper or Internal Cable	Switch 3	Conductor #	Cable	Cable Information
	RJ-45 To Switch 1: 01	01			
Power Meter: Ozone Generator 1		02	RJ-45	C-PSU-O310A-C01	4-Pair #24 AWG - Cat 5E TO PSU-O310A
Power Meter: Ozone Generator 2		03	RJ-45	C-PSU-O320A-C01	4-Pair #24 AWG - Cat 5E TO PSU-O320A
Power Meter: Ozone Generator 3		04	RJ-45	C-PSU-O330A-C01	4-Pair #24 AWG - Cat 5E TO PSU-O330A
Spare		05			
Spare		06			
Spare		07			
Spare		08			

NOTES:

APEGM
Certificate of Authorization
Earth Tech Canada Inc.
No. 730 Expiry: April 30, 2006.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
0	ISSUED FOR TENDER	06/03/29	SWT

CH2MHILL
Frederickson Cooper ARCHITECTS
EarthTech A Tyco International Ltd. Company

DESIGNED BY	SWT	CHECKED BY	SWT
DRAWN BY	SWT	APPROVED BY	AHL
SCALE:	NTS	RELEASED FOR CONSTRUCTION BY:	R. SOROKOWSKI
DATE	2006/03/29	DATE	2006/03/29

ENGINEER'S SEAL

ORIGINAL SIGNED BY
S.W. TORMEY
2006/03/29

CONSULTANT DRAWING NO.
WH-A0524

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

WATER TREATMENT PLANT
PLANT UTILITIES
MECHANICAL AND ELECTRICAL

CITY FILE NUMBER

SHEET 24 OF 63

AUTOMATION / I AND C
PLANT COMMUNICATION CABLE
TERMINATION DIAGRAMS

CITY DRAWING NUMBER
1-0601H-J-A0524-001-00B

Monday, April 03, 2006