



299-2006 ADDENDUM 1

Province of Manitoba/City of Winnipeg/Local Improvements, 2006 Residential Street Renewal Program – Part 1: Pacific Avenue, Part 2: Burrows Avenue Westbound, Part 3: Helmsdale/Kimberly Alley, Part 4: Underground Works

ISSUED: June 13, 2006
BY: James Kennedy
TELEPHONE NO. (204) 284-0580

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20050301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 299-2006 Bid Submission with 299-2006 Addendum 1- Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Prices: Item A.7 – updated
- Items B.41 and B.42 – added

PART B – BIDDING PROCEDURES

Change B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, June 28, 2006.

PART D – SUPPLEMENTAL CONDITIONS

Change D13.3 to read: The Contractor shall not commence the Work on the Site before July 17, 2006, and shall commence the Work on Site no later than July 21, 2006, as directed by the Contract Administrator and weather permitting.

Change D13.4 to read: The City intends to award this Contract by July 12, 2006.

PART E – SPECIFICATIONS

Add: E12.3: The Contractor shall not be permitted to use pneumatic breakers within 5 metres of the centre of the Branch 1 Aqueduct on Pacific Avenue.

Add:

E26. STREET LIGHTING TRENCHES

E26.1 Description

E26.1.1 This specification covers the excavation and backfill of trenches or the pushing of pipe required for the installation of Manitoba Hydro street lighting cable on Burrows Avenue.

E26.2 Construction Methods

E26.2.1 Street Lighting Trenches

- (a) Excavate trenches exclusively for Manitoba Hydro's use at locations staked by Manitoba Hydro or the Contract Administrator.
- (b) The trench shall be a minimum of 0.6 metres deep, measured from final grade or as determined by the Contract Administrator.
- (c) Install all pipe pushes at road crossing locations staked by Manitoba Hydro or the Contract Administrator. Pipe will be supplied by Manitoba Hydro.
- (d) The Contractor shall have equipment and staff on site when Manitoba Hydro installs the underground cable, and follow Manitoba Hydro's directions.
- (e) Backfill the trenches with clean fill to the satisfaction of Manitoba Hydro and the Contract Administrator.
- (f) Where required for protection, as determined by Manitoba Hydro, the Contractor shall supply and install sand backfill.
- (g) The Contractor shall contact Manitoba Hydro two (2) weeks prior to curb completion to schedule the work.
- (h) Manitoba Hydro's normal hours of work are 08:00 – 16:30, Monday through Friday.

E26.3 Measurement and Payment

E26.3.1 The excavation and backfill of trenches required for the installation of Manitoba Hydro street lighting cable will be measured on a length basis and paid for at the Contract Unit Price per linear metre for "Trenching and Backfilling for Street Lighting Cable". The length to be paid for will be the total number of metres of trench excavated and backfilled in accordance with this Specification, accepted and measured by the Contract Administrator.

E26.3.2 The pushing of pipe required for the installation of Manitoba Hydro street lighting cable will be measured on a length basis and paid for at the Contract Unit Price per linear metre for "Pipe Pushing for Street Lighting Cable". The length to be paid for will be the total number of metres of pipe pushed in accordance with this Specification, accepted and measured horizontally at-grade by the Contract Administrator.

DRAWINGS

Replace: Drawing LD-2661-R0 with Drawing LD-2661-RA

Add: Drawing 2006-B-935094