


1988 EXPANSION JOINT DESIGN GAP		
SETTING TEMP.	'W'	'W'
	NORTH ABUT.	SOUTH ABUT.
−5°	234	235
0°	225	227
5°	217	220
10°	208	212
15°	200	204
20°	191	196
25°	183	188
30°	175	180
MIN.	150	150
MAX.	300	300


	MAY 2006 EXPANSION JOINT GAP		
TEMP. DURING READINGS	12°C		
, W, 4	210		
'X' _{4-S}	65		
,X,4-N	73		




REMOVE CONCRETE. DO NOT DAMAGE EXISTING ANCHORS.

REMOVE DAMAGED EXTRUSION AND TOP PLATE.

3. CLEAN REPAIR AREA FREE OF DUST






N.T.S.

1. ORIGINAL STEEL EXTRUSION: GLACIER WSF-160.

- 2. ORIGINAL SEAL: GSH 141W. NEW SEALS SHALL FIT EXISTING EXTRUSION.
- 3. EACH EXPANSION JOINT STRIP SEAL SHALL BE INSTALLED AS ONE CONTINUOUS PIECE, TO THE SATISFACTION OF THE CONTRACT ADMINISTRATOR.
- 4. PROTECT EXISTING STRIP SEALS THAT ARE TO REMAIN FROM DAMAGE DURING EXTRUSION REPAIR OPERATIONS.
- 5. REMOVE AND SALVAGE THE EXISTING SOUTHBOUND, SOUTH ABUTMENT, NORTH SEAL.
- 6. AREAS OF SHALLOW GOUGED STEEL AS DETERMINED WITH THE CONTRACT ADMINISTRATOR TO BE REPAIRED BY FILLING WITH WELD MATERIAL AND GRINDING SMOOTH.
- 7. WELDING SHALL BE DONE IN ACCORDANCE WITH CSA W59, "WELDED STEEL CONSTRUCTION." COAT ALL WELDS AFTER INSTALLATION WITH FIELD-APPLIED GALVANIZING.



06/05/19 MRD

DATE

0 ISSUED FOR CITY REVIEW

NO. REVISIONS

ENGINEER'S SEAL ORIGINAL R. A. **WIEBE** DILLON JUNE 15/06 CONSULTING

ORIGINAL SIGNED BY B. NEIRINCK, P.Eng.

CONSULTANT PROJECT NO.

06-5919-100°

THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT Winnipeg

2006 BRIDGE MAINTENANCE ST. VITAL BRIDGE EXPANSION JOINT REPAIRS

DETAILS 2 OF 2

B116-06-03B SHEET BID OPP NO.

353-2006

CITY DRAWING NUMBER

40DILLON ACAD FILE: G:\CAD\065919\ST. VITAL BRIDGE\CURRENT\STVITAL_40F4.DWG 06/09/06