



## 356-2006 ADDENDUM 1

### 2006 WATERMAIN RENEWALS – CONTRACT NO. 7

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: 2006-06-15  
BY: Coleen Groening  
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20050506

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART A – BID SUBMISSION**

Replace: 356-2006 Bid Submission with 356-2006 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B (R1):

B. Lennox Avenue

Revise item B.7 (a) (i) to have a quantity of 2

C. Chevrier Boulevard

Add item C.9 - Connecting to Existing Watermains and Large Diameter Water Services

Add item C.10 – Connecting Existing Copper Water Services to New Watermains

Revise item C.11 to have a quantity of 4

Renumber the remainder of items following item C.10

D. River Road

Revise Item D.7 (a) (i) to have a quantity of 4

E. Waverley Street

Add item F.1 (c) (iii)

Revise Item F.13 (a) and (b) to have a quantity of 21.0

G. St. Anne's Road / Kingswood Avenue

Delete Item G.7 (b)

Add Item G.12 – Remove Existing 150mm Tee and Reconnect Existing 150mm Watermain

Renumber the remainder of items following item G.12

## **PART E – SPECIFICATIONS**

Add:

E 11.2 Remove Existing 150 Tee and Reconnect Existing 150mm Watermain on Inman Avenue

E11.2.1 This Specification covers the removal of the existing 150mmx150mmx150mm tee and the reconnection of the existing 150mm watermain as shown on Drawing D-9034 and all associated work involved.

E11.2.2 All materials are to be in accordance with CW 2110.

E11.2.3 Method of measurement and basis of payment

- (a) Removal of existing 150 tee and reconnect existing 150mm watermain will be measured on a unit basis and paid for at the contract unit price for “Remove Existing 150 Tee and Reconnect Existing 150mm Watermain” as accepted and measured by the Contract Administrator.
- (b) Excavation, removal, hauling and disposal of excess material are to be included with the price for “Remove Existing 150 Tee and Reconnect Existing 150mm Watermain.”
- (c) Plugging the abandoned watermain and reconnecting existing watermain and all materials and labour are to be included in the price.

## **DRAWINGS**

Replace Drawing D-9030 with Drawing D-9030 Revision 1

Replace Drawing D-9031 with Drawing D-9031 Revision 1