



379-2006 ADDENDUM No. 1

CONSTRUCTION OF WEST TRANSCONA FIRE PARAMEDIC STATION NO. 21 AT 1446 REGENT AVENUE W.

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: August 11, 2006
BY: Ruby Li
TELEPHONE NO. (204) 986-3984

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20050301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D.19.1 to read:

If the Contractor fails to achieve Total Performance in accordance with the Contract by the day fixed herein for Total Performance, the Contractor shall pay the City two-hundred & fifty dollars (\$250.00) per Working Day for each and every Working Day following the day fixed herein for Total Performance during which such failure continues.

PART E – SPECIFICATIONS

Revise: Section 04 05 12 Masonry Mortar Part 1 General 1.3.3 to read:

Submit test reports under provisions of Section 01 45 00.

Revise: Section 08 12 13 Steel Doors and Frames Part 2 Products 2.6.8.1 to read:

Provide removable stainless steel glazing beads for dry glazing of snap on type. Stainless steel glazing beads may be replaced with steel glazing beads.

Add Section 09 30 11 Ceramic Wall Tiling Part 1 General 1.1.3

3" x 3" ceramic tile installation are as shown on drawing A-18 Millwork Elevations.

Add Section 09 91 10 Painting Part 2 Products 1.11.2.2

Glidden Lifemaster Pro HB Acrylic Coating No. 5440 Series.

Add Section 09 91 10 Painting Part 3 Execution 1.15.12

Ceilings and walls of Apparatus Room 129 and Storage Room 130 shall be covered with block filler 1-GP-188M and a 100% acrylic resin coating (no latex will be allowed).

Add Section 10 28 14 Toilet and Bath Accessories Part 2 Products 2.1.5

Toilet partitions, urinal screens shall be floor mounted, overhead braced with non corrosive panels, doors and pilaster. Acceptable product – Shannahan's SML DB overhead braced model.

Delete Section 10 51 13 Part 2 Products 2.3.2

Revise: Section 10 51 13 Metal Lockers 2.4.13 to read:

Gearmasters – Air Flow Lockers: standard construction with pedestal base (legs) for air circulation.
Lockable – no equals allowed.

Revise: Section 23 35 16 Vehicle Exhaust 1.1.5 to read:

Contractor shall install a complete automatic disconnect Diesel Exhaust Removal System for all three bays, that addresses the problem of diesel fumes in the fire department station house that will not interfere with normal day-to day operations. The system shall be a Sliding Balancer Track type system as manufactured by Plymovent Ltd. Canada, and to the following performance criteria. The authorized vendor / installer is:

BPL Sales Ltd.
Unit A5 – 1692 Dublin Avenue
Phone 694-9790
Attention: Bernie Loiselle