

ALTERATION NOTE:

- (A) LADDER NICHE:REMOVE STAIR TREADS(4LOCATIONS), 10M@10" O.C. E.W. (DOWEL 6"MIN.)AND FILL W/20MPa CONC.
- (B) UNDERWATER LIGHT NICHE:REMOVE ALL EXISTING LIGHTS, 10M@10" O.C. E.W. (DOWEL 6"MIN.) AND FILL W/20MPa CONC.
- © REPLACE EXISTING ANCHORE CUPS WITH THE NEW ONES
- (E) REPLACE EXISTING MAIN DRAINS WITH 18"X18"EPS MAIN DRAINS.
- (E) REPAIR CONCRETE SLAB/WALLS, DEMOLISH LOOSE CONRETE AND OLD CONCRETE PATCHES.
- F SANDBLAST OFF ALL WALL PAINT AS REQUIRED
- (©) REPLACE ALL EXISTING RETURN FITTINGS WITH NEW ONES, CORE DRILL NEW LOCATIONS FOR ADDITIONAL RETURN FITTINGS.
- (H) REPLACE ALL EXISTING VACUUM FITTINGS WITH NEW ONES.
- FILL ALL MANHOLE OPENINGS W/20MPa CONCRETE.
- (L) FILL EXISTING GUTTERS W/20MPg CONCRETE AND INSTALL 3"ALUMINIUM COPING AT THE EDGE OF POOL.
- EXISTING DIVING BOARDS REMAIN AS THEY ARE.
- REMOVE ALL ELECTRICAL CONDUITS, WIRES, JUNCTION BOXES AND FILL ALL THE HOLES.
- (P) REPLACE ALL EXISTING POOL PLUMBING WITH NEW, NO VALVE SHALL BE INSTALLED IN CRAWL SPACE.
- (a) INSTALL NEW SKIMMERS(SEE A-4 FOR DETAILS)
- (R) INSTALL 4 NEW LADDERS AT SAME LOCATIONS AS EXISTING ONES.
- (8) DEPTH MARKING & RACING LANES(IN BLACK)
- NEW POOL UPPER DECK,25MPa CONCRETE, SLOPING AWAY FROM POOL 2.0% SLOPE MIN.
- 4 NEW FLOOR DRAINS BETWEEN POOL& BUILDING, DRAIN TO SEWER
- $(\hat{\mathbf{V}})$ sodding 4'wide on 3 sides of Pool upper deck.
- (W) INSTALLATION OF 12 NEW WATERPROOF 2X4FLOURSCENT FIXTURES,2 AT EACH END OF POOL, 4 AT EACH SIDE OF POOL IN THE CRAWL SPACE, PLUS A SWITCH IN MFCH.ROOM.
- (Y) SODDING 4'WIDE ON 3 SIDES OF POOL UPPER DECK.
- (2) PLACE 2 SUMP PIT IN CRAWL SPACE AND ONE 9"Ø HAYWARD SECONDARY RELIEF AT POOL BOTTOM NEAR MAIN DRAIN.



Certificate of Authorization GC Engineering Ltd. No. 3208 Expiry: April 30, 2007

GC ENGINEERING LTD. 675 ELM STREET

675 ELM STREET WINNIPEG, MB R3M 3N8 PH 793-3948 FAX 487-4616 EMAIL CALGRAY@MTS.NET

FORT GARY LION'S CLUB SWIMMING POOL

969 Dowker Avenue Winnipeg, MB

A-

POOL& CRAWL SPACE

JUNE 1 / 06