- READ THE STRUCTURAL DRAWINGS IN CONJUNCTION WITH ALL OTHER PERTINENT CONTRACT DOCUMENTS. IN THE EVENT OF A CONFLICT, GENERAL CONTRACTOR SPECIFIES ORDER OF PRECEDENCE.
- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE. THE CONTRACTOR SHALL VERIFY DIMENSIONS BEFORE BEGINNING CONSTRUCTION AND REPORT DISCREPANCIES TO THE CONTRACT ADMINISTRATOR BEFORE PROCEEDING WITH THE WORK.
- THE DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE NATIONAL BUILDING CODE OF CANADA 2005, ITS SUPPLEMENTS AND THE LATEST EDITIONS (UNLESS OTHERWISE NOTED) OF REFERENCED CODES AND STANDARDS THEREIN.
- REFER TO THE ARCHITECTURAL, PROCESS, MECHANICAL AND ELECTRICAL DRAWINGS FOR LOCATIONS AND DIMENSIONS OF OPENINGS, SLEEVES AND OTHER BUILDING COMPONENTS NOT SHOWN ON THE STRUCTURAL DRAWINGS. REPORT DISCREPANCIES TO THE CONTRACT ADMINISTRATOR BEFORE PROCEEDING WITH CONSTRUCTION

### DESIGN LOADS

- LOADS SHALL CONFORM TO THE NATIONAL BUILDING CODE OF CANADA 2005 AND SUPPLEMENTS.
- DEAD LOADS: AS INDICATED ON CORRESPONDING DRAWINGS.
- 3. LIVE LOADS: AS INDICATED ON CORRESPONDING DRAWINGS
- 4. WIND LOADS: q(1/50)=0.45 KPa
- ADDITIONAL DESIGN LOADS FOR EQUIPMENT ARE INDICATED ON CORRESPONDING DRAWINGS.
- CONTRACTOR TO VERIFY FINAL EQUIPMENT WITH CONTRACT AND REPORT DISCREPANCIES AND OBTAIN APPROVAL FROM THE ADMINISTRATOR PRIOR TO PROCEEDING WITH CONSTRUCTION.

#### **FOUNDATION NOTES:**

- ALL FOUNDATION CONSTRUCTION SHALL BE PERFORMED WITH REFERENCE TO THE RECOMMENDATIONS GIVEN IN THE GEOTECHNICAL INFORMATION AVAILABLE FOR THE SITE.
- 2. FOUNDATIONS ARE DESIGNED IN COMBINATION WITH CAST IN PLACE REINFORCED CONCRETE PILES.

#### EXCAVATION, BACKFILLING AND COMPACTION NOTES

- AN EXCAVATION PLAN SHALL BE PREPARED. SEALED AND SIGNED BY A QUALIFIED PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA. SUBMIT EXCAVATION PLAN FOR REVIEW. VERIFY LOCATION OF ALL UNDERGROUND SERVICES PRIOR TO COMMENCING EXCAVATION AND BE RESPONSIBLE FOR DISRUPTIONS.
- 2. EXCAVATE TO LINES AND LEVELS INDICATED IN THE CONSTRUCTION SEQUENCE AND DRAWINGS NECESSARY TO PROPERLY COMPLETE THE WORK. (IF INDICATED)
- CONSTRUCTION METHODS REQUIRING TEMPORARY SHORING OR BRACING. SHALL BE DESIGNED, SEALED AND SIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA. SUBMIT SHORING PLAN AND DETAILS FOR REVIEW.
- 4. CAST IN PLACE CONCRETE PILES
- .1) DESIGN SKIN FRICTION OF 15.2kN/m2 IS IN ACCORDANCE WITH THE GEOTECHNICAL REPORT.
- .2) TOLERANCES: OUT OF POSITION
- ± 50 2% OF PILE LENGTH
- OUT OF PLUMB CUT-OFF ELEVATION +0 TO - 75
- .3) UNLESS SHOWN OTHERWISE, CENTER PILES UNDER COLUMNS, GRADE BEAMS OR WALLS.

  4) ALL PILES TO BE REINFORCED AS SHOWN ON PLAN. REINFORCING STEEL TO CSA 630.18 GRADE 300 FOR TIES. GRADE 400 FOR 15M AND LARGER BARS. LAP SPLICES 36 BAR DIAMETERS OR 460,
- WHICHEVER IS GREATER. 5) ENSURE ALL LOOSE MATERIAL AND WATER IS THOROUGHLY REMOVED FROM PILE EXCAVATIONS PRIOR TO PLACING REINFORCEMENT AND CONCRETE. CONCRETING OPERATIONS TO PROCEED WITHIN 3 HOURS OF EXCAVATION OR IMMEDIATELY IF GROUNDWATER EXISTS. CASTING OF ALL PILES SHALL BE CONTINUOUS; CONSTRUCTION JOINTS IN PILE SHAFTS SHALL NOT BE ALLOWED. VIBRATE CONCRETE IN UPPER 15' OF SHAFT OR UPPER 50% OF THE REINFORCING LENGTH, WHICH EVER IS GREATER.
- 6) PROVIDE REMOVABLE CASING IF REQUIRED DUE TO WATER OR SLOUGHING SOILS. .7) PILING CONTRACTOR SHALL KEEP AN ACCURATE RECORD. OF DEPTHS OF PILES. EXCAVATED SOILS PENETRATED. WATER SEEPAGE AND OTHER PERTINENT CONDITIONS. REPORT ANY ABNORMAL CONDITIONS TO THE ENGINEER
- .8) DO NOT DRILL ADJACENT PILES LESS THAN 48 HOURS AFTER PILES HAVE BEEN FORMED UNLESS PILES ARE MORE THAN 6 PILE DIAMETERS APART.
- .9) SEE CONCRETE SPECIFICATION SECTIONS FOR CONCRETE PERFORMANCE REQUIREMENTS. .10) CONC. STRENGTH SHALL BE 35 MPa SULPHATE RESISTANT CONCRETE.

# **CONCRETE NOTES**

- 1. PROVIDE CONCRETE AND PERFORM WORK TO CSA A23.1-04, TEST CONCRETE TO CSA A23.2-04. THE CONTRACTOR SHALL HAVE COPIES OF THESE STANDARD ON SITE AT ALL TIMES.
- 2. SPECIFIED SLUMPS ARE PRIOR TO THE ADDITION OF ANY ACCEPTED PLASTICIZING ADMIXTURE. WHEN CONCRETE IS PLACED BY PUMPING, THE LISTED SLUMPS SHALL BE AT DISCHARGE.
- 3. ALL CONCRETE SHALL BE NORMAL WEIGHT 2400 KG/CUBIC METER UNLESS NOTED.
- 4. GROUT: NON-SHRINK, NON-METALLIC WITH MINIMUM STRENGTH 35MPa AT 28 DAYS.
- VOID FORMS: PROVIDE VOID FORMS UNDER SLABS, GRADE BEAMS, WALLS AND PILE CAPS AS SHOWN ON DRAWINGS TO ACCOMODATE FOR 200mm SOIL SWELLING AS PER GEOTECHNICAL INFORMATION.

  ACCEPTABLE PRODUCT: BIO DEGRADABLE MOISTURE RESISTANT TREATED PAPER OF
- FORMWORK AND FALSEWORK DESIGN SHALL BE COMPLETED BY A PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA. SUBMIT TO CONTRACT ADMINISTRATOR FOR REVIEW.
- 7. PROVIDE 20mm CHAMFER ON ALL EXPOSED CONCRETE CORNERS.

# REINFORCING STEEL NOTES

- 1. DEFORMED BARS CONFORMING TO CSA-G30.18 GRADE 400 PLAIN FINISH.
- 2. REINFORCING WORK SHALL BE IN ACCORDANCE WITH CSA-A23,1-04 AND CSA-A23.3
- REINFORCING SHALL BE DETAILED IN ACCORDANCE WITH THE LATEST REINFORCING STEEL INSTITUTE OF CANADA DETAILING MANUAL OF STANDARD PRACTICE.

# STEEL FABRICATIONS

- 1. FABRICATE AND ERECT STRUCTURAL STEEL TO CSA-S16.1.
- 2. STRUCTURAL STEEL WIDE FLANGE SECTIONS: CONFORMING TO CSA G40.21, TYPE W WITH MINIMUM YIELD STRENGTH OF 350 MPa.
- 3. MISCELLANEOUS STEEL: TO CAN/CSA G40.21; TYPE W WITH A MINIMUM YIELD STRENGTH OF 300
- 4. HOLLOW STRUCTURAL SECTIONS: CONFORMING TO CSA G40.21, TYPE W, MINIMUM YIELD STRENGTH OF 350 MPa, CLASS C.
- WELDING MATERIALS: CONFORMING TO CSA W59. BY FABRICATORS CERTIFIED BY THE CANADIAN WELDING BUREAU TO THE REQUIRMENTS OF CSA-W47.1, DIVISION 2.
- 6. GALVANIZING CONFORMING TO CSA G164.
- CLEAN ALL STEEL PRIOR TO PRIMING TO SSPC SURFACE PREPARATION SPECIFICATION NO. 7 "BRUSH-OFF BLAST CLEANING".
- 8. PRIME STEEL SURFACES WITH ONE COAT OF PRIMER TO CISC/CPMA 2-75.

## <u> MISCELLANEOUS METALS - STEEL</u>

- 1. STEEL PLATES AND SECTIONS: CONFORMING TO CSA G40.21) TYPE W WITH A MINIMUM YIELD STRENGTH OF 300 MPa.
- HOLLOW STRUCTURAL SECTIONS: CONFORMING TO CSA G40.21) TYPE W WITH A MINIMUM YIELD STRENGTH OF 350 MPa.
- ANCHOR BOLTS: CONFORMING TO ASTM A307.
- WELDING MATERIALS: CONFORMING TO CSA W59.
- PRIMER: TO CISC/CPMA 2-75. WELDING OF ALL LOAD CARRYING ASSEMBLIES IS TO BE PERFORMED BY A FIRM CERTIFIED BY THE CANADIAN WELDING BUREAU TO THE REQUIREMENTS OF CSA
- $\sqrt{01}$   $\sqrt{W47.1}$  IN DIVISION 2.
- GROUT: NON-SHRINK, NON-METALLIC, 50 MPa AT 28 DAYS. VERIFY ALL DIMENSIONS ON SITE PRIOR TO FABRICATION.
- FABRICATE ITEMS OF SIZES AND PROFILES DETAILED ON DRAWINGS, WITH JOINTS NEATLY FITTED AND PROPERLY SECURED.
- SUPPLY ALL COMPONENTS REQUIRED FOR PROPER ANCHORAGE OF MISCELLANEOUS METALS. FABRICATE ANCHORAGE AND RELATED COMPONENTS OF SAME MATERIAL AND FINISH AS METAL FABRICATIONS, UNLESS OTHERWISE
- SPECIFIED OR SHOWN. WELD CONNECTIONS WHERE POSSIBLE, OTHERWISE BOLT CONNECTIONS.
- COUNTERSINK ALL EXPOSED FASTENINGS. CUT OFF BOLTS FLUSH WITH NUTS. ACCURATELY FORM ALL CONNECTIONS AND JOINTS WITH EXPOSED FACES FLUSH,
- MITRES AND JOINTS TIGHT. GRIND OR FILE EXPOSED ROUGH WELDS AND METALS SECTIONS SMOOTH AND FLUSH.
- 14. GALVANIZING CONFORMING TO CSA G164. OT
- CLEAN ALL STEEL PRIOR TO PRIMING TO SSPC SURFACE PREPARATION SPECIFICATION No. 7 "BRUSH-OFF BLAST CLEANING".
- 16. PRIME STEEL SURFACES WITH ONE COAT OF PRIMER TO CISC/CPMA 2-75. FINISH COAT(S) TO OWNER REQUIREMENTS.

## WOOD CONSTRUCTION

- TIMBER CONSTRUCTION SHALL CONFORM TO CSA 086 NBC 2005.
- ROOF AND WALL SHEATHING TO BE PRESSURE TREATED CONSTRUCTION. USE H-CLIPS AS REQUIRED.
- JOIST HANGERS AND FRAMING ANCHORS CAPABLE TO SUPPORT LOADS INDICATED WITH A MINIMUM CAPACITY OF 3.5 kN (750 lb.) AND TO BE MINIMUM 1.21mm (18 GAUGE) GALVANIZED SHEET METAL MATERIAL. NAI TO MANUFACTURER'S INSTRUCTIONS. USE COATED SPIRAL NAILS TO CSA \$111
- WOOD FRAMING MATERIAL (UNLESS OTHERWISE SPECIFIED):
  - LINTELS, BUILT-UP BEAMS - KILN DRIED:
- D. FIR-L NO. 1/NO. 2 OR HEM-FIR NO. 1/NO. 2 (S-DRY) S-P-F NO. 1/NO. 2 (S-DRY
- EXTERIOR WALL STUDS -KILN DRIED
  - S-P-F NO. 1/NO. 2 (S-DRY)
- INTERIOR PARTITION WALL STUDS
- -KILN DRIED S-P-F NO. 1/NO. 2 (S-DRY)
- PLYWOOD SUBFLOOR (TONGUE AND GROOVE): D. FIR

#### RAFTER, JOISTS – KILN DRIED:

- MINIMUM S-P-F NO. 1/NO. 2 (S-DRY)
- BELOW GRADE PLYWOOD - P.T. PLYWOOD WITH CSA 0322 CERTIFIED STAMP, PRESERVATIVE TO CSA 088. GALVANIZED NAILS TO CAN/CSA G164.
- STANDARDS SET FORTH IN THE NATIONAL EVALUATION SERVICE INC. (NES) REPORT NO. NER-481 OR CCMC REPORT NO. 11161-R. -EACH OF THE BEAMS SHALL BE IDENTIFIED BY A STAMP INDICATING THE

-USE PARALLAM PSL PRODUCTS DESIGNED AND MANUFACTURED TO THE

- PRODUCT TYPE AND GRADE, NEC OR CCMC REPORT NO., MANUFACTURER'S NAME, PLANT NO. AND THE INDEPENDENT INSPECTION AGENCY'S LOGO.
- MANUFACTURER'S ENGINEERING SHALL NOT BE PERMITTED. CONNECT ALL NON-LOAD BEARING PARTITIONS TO THE STRUCTURE ABOVE. CONNECTION TO

-HOLES, CUTS OR NOTCHES NOT PREVIOUSLY AUTHORIZED BY

ALLOW FOR VERTICAL DEFLECTION OF THE STRUCTURE.

ALL TRUSSES, JOISTS, FRAMING, AND DECKING DELIVERED TO THE SITE SHALL BE KEPT DRY. NO WARPED MATERIAL SHALL BE USED.

# STANDARD ABBREVIATIONS:

FACE TO FACE

FOUNDATION

FOOTING

GALVANIZE

**GUARD RAIL** 

FACE OF CONCRETE

FULL TENSION SPLICE

F.O.C.


FDN

F.T.S.

**GALV** 

G.R.

DDITIONAL	ADDL	GRANULAR	GRAN.	PAINT
I NCHOR BOLT	@ A. BOLT	GRAVEL	GRL.	PERIMETER
NCHOR BOLT		HANGER	HGR HORIZ	PERPENDICULAR
LUMINUM	ALUM	HORIZONTAL		PLATE
PPROXIMATE	APPROX	HOLLOW STRUCTURAL STEEL	HSS	PRECAST
RCHITECTURAL	ARCH	HEIGHT	HT	PRELIMINARY
VERAGE	AVG.	INSIDE FACE	I.F.	RADIUS
OTTOM	ВОТ	INSIDE DIAMETER	I.D.	REINFORCE WITH
OTTOM LOWER LAYER	BLL	INSULATION	INSUL	REINFORCING
OTTOM UPPER LAYER	BUL	INTERIOR	INT	REQUIRED
ETWEEN	BETW	JUNCTION	JCT	REVISION
JILDING	BLDG	KILONEWTON	kN	RETAINING WALL
EARING	BRG	LOCATION	LOC'N	SECTION
LEAR COVER	CL.	LONG	LG	SHEET
ENTERLINE	<b>Q</b>	LONG LEG HORIZONTAL	LLH	SIMILAR
ENTER TO CENTER	c̄/c	LONG LEG VERTICAL	LLV	SPECIFICATION
AST IN PLACE	C.I.P.	LIVE LOAD	L.L.	STAINLESS STEEL
ONSTRUCTION JOINT	C.J.	LONGITUDE	LONG	STANDARD
OMPLETE WITH	C/W	MAXIMUM	MAX	STIFFENER
RCULAR	CÍRC	MECHANICAL	MECH	STIRRUP
ONCRETE	CONC	MINIMUM	MIN	STRUCTURAL
ONSTRUCTION	CONSTR	MISCELLANEOUS	MISC	TOP LOWER LAYER
ONTINUOUS	CONT	MILLIMETER	mm	TOP OF
MENSION	DIM	METER	M	TOP UPPER LAYER
EAD LOAD	D.L.	NELSON STUD	N.STUD	TYPICAL
NWC	DN.	NUMBER	No.	UNLESS NOTED
RAWING	DWG	NOT TO SCALE	N.T.S.	UNDERSIDE
OWEL	DWL	ON CENTER	o/c (lower case)	VERTICAL
AMETER	DIA	OUTSIDE FACE	0.F.	WIND LOAD
EGREE	•	OUT TO OUT	0/0	WORK POINT
ACH FACE	E.F.	OUTSIDE DIAMETER	0.D.	
ACH END	E.E.	OPENING	OPNG	
ACH SIDE	E.S.	ORIGINAL	ORIG	
(PANSION JOINT	E.J.	ONGINAL	ONIG	
ACH WAY	E.W.		B.M.	
	ELECT		ELEV.	
LECTRICAL				
EVATION	EL.			
QUAL	EQ			
KISTING	EXIST			
KPANSION	EXP.			
KTERIOR	EXT	Certificate of Authorization		
AR SIDE	F.S.	11		



CAST-IN PLACE CONCRETE PILE SCHEDULE								
MARK	DIAMETER	LENGTH	REINFORCING	REMARKS				
P-1 & P-8	400	7.6m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 233.858m				
P2 T0 P7	400	7.6m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 233.558m				
P-9	400	11.0m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 233.756m				
P-10	400	11.0m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 233.736m				
P-11	400	11.0m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 233.506m				
P-12	400	11.0m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 233.486m				
P-13	400	7.6m	4-15M VERT. FULL HEIGHT, 2-10M TIES TOP REMAINDER 10M TIES @ 250 o/c	C.I.P. PILE, SET T.O. PILE @ 234.200m (CONFIRM WITH EQUIPMENT SUPPLIER)				

	CONCRETE PILECAP SCHEDULE								
144	MARK SIZE		DEDTIL		R	EINFORCIN	G	DEMARKS	
MA	ΛN.	SIZE	DEPTH	TOP	MIDDLE	воттом	STIRRUPS	ADDITIONAL	REMARKS
PC	-1	600x1828	600	6-20M	1-15M E.F.	6-20M	10M @ 250 o/c		
PC-	-2	SEE PLAN	600	6-20M	1-15M E.F.	6-20M	10M @ 250 o/c		SEE PLAN FOR EXACT DIMENSIONS
PC-	-3	600×4000	600	6-20M	1-15M E.F.	6-20M	10M @ 250 o/c		
PC-	-4	600ø	±1200				10M TIES @ 200	7-15M VERT.	SITE VERIFY T.O. CAP WITH EQUIPMENT SHOP DWGS.
PC-	-5	600ø	±1200				10M TIES @ 200	7-15M VERT.	SITE VERIFY T.O. CAP WITH EQUIPMENT SHOP DWGS.
PC-	-6	600ø	±1200				10M TIES @ 200	7-15M VERT.	SITE VERIFY T.O. CAP WITH EQUIPMENT SHOP DWGS.
PC-	-7	600ø	±1200				10M TIES @ 200	7-15M VERT.	SITE VERIFY T.O. CAP WITH EQUIPMENT SHOP DWGS.
	CONCRETE GRADE BEAM SCHEDULE								

MARK WIDTH DEPTH		DEDTU		RE	EINFORCIN	G	REMARKS		
WARK	MARK   WIDTH   DEF		TOP	MIDDLE	BOTTOM STIRRUPS ADDIT			ADDITIONAL	
GB-1	250	1200	3-25M	15M@300 o/c E.F.	3-25M	10M @ 400 o/c			
GB-2	250	1500	3-25M	15M <b>@</b> 300 o/c E.F.	3-25M	10M @ 400 o/c			
	CONCRETE TIE BEAM SCHEDULE								
MARK WIDTH DEPTH REINFORCING							REMARKS		
WARK	MARK   WIDTH	DIR DEFIN	TOP	MIDDLE	ВОТТОМ	STIRRUPS	ADDITIONAL	REMARKS	
TB-1	300	600	2-25M	15M MID. E.F.	2-25M	10M @ 300 o/c			
	WOOD LINTEL SCHEDULE								

MARK	WIDTH	DEPTH	GRADE / SPECIES	REMARKS				
WL-1	38	235	No. 2 SPF OR BETTER	3 PLY c/w 2 PLY 38x140 BEARING STUDS				
WL-2	89	235	PARALLAM PSL	1 PLY PARALLAM c/w 3 PLY 38x140 BEARING STUDS				
WL-3	38	184	No. 2 SPF OR BETTER	3 PLY c/w 2 PLY 38x140 BEARING STUDS				

ENGINEER'S SEAL THE CITY OF WINNIPEG **EarthTech** Frederickson Cooper WATER AND WASTE DEPARTMENT ARCHITECT 8 ORIGINAL A Tyco International Ltd. Company Winnipeg SOLID WASTE SERVICES DIVISION SIGNED BY M. KLASSEN CHECKED DESIGNED CITY FILE NUMBER BRADY RD. LANDFILL LLR/GGP NEW ENTRANCE AND 2007/07/20 DRAWN APPROVED Earth Tech Canada Inc. SCALE FACILITY No. 730 RELEASED FOR CONSTRUCTION BY: AS SHOWN CITY DRAWING NUMBER SCALE: STRUCTURAL 01 357-2007 ADDENDUM 1 07/07/31 CMF CONSULTANT DRAWING NO. GENERAL NOTES V. JEANCART 0 ISSUED FOR TENDER 07/07/20 KK SWD-D-379S1.01 SCHEDULES NO. REVISIONS DATE | BY | DATE 2006/07/24 DATE 2007/07/20

**PERIM** 

PERP

PŘELIM.

R/W

RÉINF

REQD REV.

R.W.

SECT

SHT

S.S.

STD STIFF **STIRR** 

TUL

U/S

W.P.

VERT W.L.

STRUC1

R or RAD