

REMOVE NATURAL GAS PIPING (+/- 150'-0", APPROX. 20'-0" AFF) FROM NORTH WALL OF SHOP AND STORE FOR REINSTALLATION AFTER O/H DOOR AND SLAB REPLACEMENT, DISCONNECT CONNECTIONS AND ENSURE SUPPLY IS CORRECTLY CUT-OFF, RE-CONNECT @ TIME OF REINSTALLATION.

REMOVE EXISTING RADIANT HEATERS (3 UNITS @ 20'-0" EACH, APPROX. 13'-0" AFF) FROM NORTH WALL OF SHOP AND STORE FOR REINSTALLATION AFTER O/H DOOR AND SLAB REPLACEMENT. DISCONNECT ANY GAS/ELECTRICAL CONNECTIONS AND ENSURE SUPPLY IS CORRECTLY CUT-OFF. RE-CONNECT @ TIME OF REINSTALLATION.

REMOVE EXISTING HORIZONTAL (1 - 48"x12"x80'-0" LONG HORIZONTAL DUCT @ +/-20'-0" AFF) AND VERTICAL AIR SUPPLY DUCTING (1 @ +/-10'-0", APPROX. 5'-0" TO 20'-0" AFF) FROM NORTH WALL OF SHOP AND STORE FOR REINSTALLATION AFTER O/H DOOR AND SLAB REPLACEMENT.

REMOVE EXISTING HORIZONTAL 6"/8" SPIRAL EXHAUST DUCTING (+/- 60'-0", APPROX. 11'-0" AFF) AND VERTICAL DROPS (4 @ +/- 10'-0") FROM NORTH WALL OF SHOP AND STORE FOR REINSTALLATION AFTER O/H DOOR AND SLAB REPLACEMENT. SLIGHT MODIFICATIONS TO DUCT MOUNTING AND LOCATIONS MAY NEED TO OCCUR FOR RE-MOUNTING, COORDINATION TO HAPPEN ON-SITE.


REMOVE SURFACE ELECTRICAL OUTLETS AND CONNECTIONS INCLUDING CONDUIT, APPROXIMATELY 200' TOTAL CONDUIT INCLUDING ELECTRICAL WIRE (APPROX. 4'-0" AFF) TO BE DISCONNECTED AND REMOVED. REMOVE 48" FLUORESCENT SUSPENDED LIGHTING UNITS (8) AND STORE FOR RE-INSTALLATION.

REMOVE PARTS WASHER FROM NORTH WALL AND STORE FOR RE-INSTALLATION, CAP WATER SUPPLY FOR RELOCATION +/- 5'-0" TO THE EAST, REMOVE AIR HOSE REELS (2) AND CONNECTIONS FROM NORTH WALL AND STORE FOR RE-INSTALLATION.

VIEW OF EXISTING NORTH WALL



			_
0	ADDENDUM 2	JUN 11, 2007	LK
REV	DESCRIPTION	DATE	BY
=			



INTERIOR ELEVATION PHOTO

195 TECUMSEH O/H DOOR & CONCRETE SLAB REPLACEMENT

WINNIPEG, MANITOBA

Neil Cooper Architect Inc. 10-395 Berry Street, Winnipeg, Manitoba R3J 1N6

D6069/Contract Doc/Contract Dwgs/Arch Dwgs/A2.4RO.dwg