



**KILDARE LAND DRAINAGE FLOOD PUMPING STATION
MECHANICAL AND ELECTRICAL WORKS**

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: September 11, 2007
BY: Rudy Derksen, P.Eng.
TELEPHONE NO. (204) 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20060821

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, September 14, 2007.

PART E – SPECIFICATIONS

Replace: Section 11000, Item 1.7.6 with the following:

".6 Equipment Performance Test: The equipment will be restarted and run continuously for four (4) hours. During this period, as practicable, conditions will be simulated which represent maximum, average, and minimum conditions."

Replace: Section 15100, Item 3.2.2.2 with the following:

"A temporary closure panel at the station outlet will not be required for pump testing. The City will be responsible for providing sufficient water flow for testing and will arrange to raise the water level in the station and upstream piping as required by using the existing positive gate valve in the valve chamber. The City will operate the positive gate valve. With the station positive gate valve closed, the City will introduce and regulate water to the drainage piping. The station pumps will then pump this water directly to the floodway."