

FOR CONTINUATION OF 150mm STORM LINE REFER TO CIVIL DRAWINGS. MECHANICAL SUBCONTRACTORS'S CONTRACT

FOR CONTINUATION OF 150mm SANITARY LINES REFER TO CIVIL DRAWINGS. MECHANICAL SUBCONTRACTORS'S CONTRACT SHALL END AT THIS POINT.

MAIN BUILDING CLEAN-OUT. COORDINATE EXACT LOCATION

4 CAPPED FOR CONNECTION TO FUTURE DISHWASHER.

RAINWATER LEADER TO DROP DOWN FROM HIGH LEVEL. COORDINATE EXACT LOCATION WITH ARCHITECTURAL.

RAINWATER LEADER TO DROP DOWN, FROM HIGH LEVEL, INSIDE WALL. COORDINATE EXACT LOCATION WITH

7 REFER TO MEZZANINE FLOOR PLAN FOR CONTINUATION.

SANITARY LINE TO DROP DOWN, FROM HIGH LEVEL INSIDE WALL. COORDINATE EXACT LOCATION WITH ARCHITECTURAL.

STORM WATER LINE INVERT ELEVATION AT BUILDING LINE IS ABOUT ±1200mm (4'-2") BELOW THE TOP OF THE FINISHED MAIN FLOOR ELEVATION. BÉFORE CONSTRUCTION CONFIRM INVERT ELEVATION AND COORDINATE WITH THE SITE SERVICES

SANITARY LINE INVERT ELEVATION AT BUILDING LINE IS ABOUT ±1397mm (4'-7") BELOW THE TOP OF THE FINISHED MAIN FLOOR ELEVATION. BÉFORE CONSTURCTION CONFIRM INVERT ELEVATION AND COORDINATE WITH THE SITE SERVICES SUBCONTRACTOR.

## **GENERAL NOTES:**

NOTES :

THIS DRAWING MUST NOT BE SCALED.

1. EXAMINE THE COMPLETE SET OF CONTRACT DOCUMENTS TO ENSURE THAT THE WORK CAN BE CARRIED OUT WITHOUT SIGNIFICANT CHANGES TO THE INTENT OF THE DOCUMENTS. NO FUTURE ALLOWANCE WILL BE MADE FOR CHANGES UNLESS THE CONTRACT ADMINISTRATOR HAS BEEN NOTIFIED IN WRITING OF ANY DISCREPANCIES OR INTERFERENCES, PRIOR TO THE CLOSE OF BID OPPORTUNITYS. NO ALLOWANCE WILL BE MADE FOR ITEMS THAT SHOULD HAVE BEEN NOTED DURING A PRE-BID OPPORTUNITY SITE INSPECTION.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, DATUMS, AND LEVELS PRIOR TO COMMENCEMENT OF WORK. ALL ERRORS AND OMISSIONS TO BE REPORTED TO THE CONTRACT ADMINSTRATOR BEFORE PROCEEDING.

THIS DRAWING IS THE EXCLUSIVE PROPERTY OF NUMBER TEN ARCHITECTURAL GROUP AND THE COPYRIGHT IN THE SAME BEING RESERVED TO THEM. IT MAY BE REPRODUCED ONLY WITH THE PERMISSION OF THE CITY OF WINNIPEG.

2. MECHANICAL SUBCONTRACTOR SHALL VERIFY EXACT LOCATIONS, CONNECTIONS, SIZES, INVERTS, ETC. PRIOR TO BID OPPORTUNITY CLOSE AND COMMENCEMENT OF

3. FOR SANITARY PIPE 100mmø (4"ø) AND UP THE PIPE IS TO SLOPE 1% UNLESS OTHERWISE NOTED.

4. MECHANICAL SUBCONTRACTOR TO ENSURE THAT CLEANOUTS ARE LOCATED IN ACCESSIBLE LOCATIONS.

5. MECHANICAL SUBCONTRACTOR SHALL REFER TO ARCHITECTURAL, STRUCTURAL, ELECTRICAL DRAWINGS, THE CITY'S EQUIPMENT SUPPLIER SHOP DRAWINGS, ETC

FOR EXACT LOCATIONS, OF ALL FIXTURES, EQUIPMENT,

6. MECHANICAL CONTRACTOR TO PROVIDE ALL ROUGH-IN FOR THE CITY SUPPLIED EQUIPMENT. FINAL CONNECTION TO BE BY THE MECHANICAL SUBCONTRACTOR, UNLESS NOTED OTHERWISE.

7. ALL PLUMBING INSTALLATIONS ETC. SHALL BE PERFORMED IN ACCORDANCE WITH ALL CODES, REGULATIONS & AUTHORITIES HAVING JURISDICTION.

8. ALL VENT PIPING TO BE INSTALLED AS PER CODE.

9. SHUTOFF VALVES (S.O.V.) TO BE INSTALLED ON ALL LINES SERVING FIXTURES & EQUIPMENT.

10.DOMESTIC WATER RUN OUTS SHALL BE 13mm (1/2")UNLESS NOTED OTHERWISE.

11.COORDINATE PLUMBING WITH DUCT RUNS, SPRINKLER PIPING, & ALL OTHER TRADES.

12.PROVIDE ISOLATION VALVES AT BASE OF EACH RISER & AT EACH FIXTURE.





numberTEN architectural group


architecture = interior design = graphic design

No.	REVISED/ ISSUED/ PLOTTED	DATE	l
$\sqrt{1}$	DESIGN DEVELOPMENT SUBMISSION	31/AUG./07	ı
2	ISSUED FOR 40% REVIEW	26/OCT./07	
$\frac{\sqrt{3}}{2}$	ISSUED FOR 80% REVIEW	07/DEC./07	
4	ISSUED FOR 100% REVIEW	11/JAN./08	
<u>5</u>	ISSUED FOR TENDER	18/JAN./08	
6			
	I.	. 1 1	

REVISION/DESCRIPTION







BRONX PARK COMMUNITY CENTRE GOOD NEIGHBOURS SENIOR CENTRE

MAIN FLOOR PLAN

DRAIN, WASTE, AND VENTING LAYOUT

PP&D 2006-065 DRAWING SHEET SIZE: ARCH E1 (42" x 30") PLOT 1:1