



**THE CITY OF WINNIPEG**

# **BID OPPORTUNITY**

**BID OPPORTUNITY NO. 876-2007**

**FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK  
STABILITY IMPROVEMENT**

## TABLE OF CONTENTS

### PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	4
Form G1: Bid Bond and Agreement to Bond	6
Form G2: Irrevocable Standby Letter of Credit and Undertaking	8

### PART B - BIDDING PROCEDURES

B1. Contract Title	1
B2. Submission Deadline	1
B3. Site Investigation	1
B4. Enquiries	1
B5. Addenda	1
B6. Substitutes	2
B7. Bid Components	3
B8. Bid	3
B9. Prices	4
B10. Qualification	4
B11. Bid Security	5
B12. Opening of Bids and Release of Information	6
B13. Irrevocable Bid	6
B14. Withdrawal of Bids	6
B15. Evaluation of Bids	7
B16. Award of Contract	7

### PART C - GENERAL CONDITIONS

C0. General Conditions	1
------------------------	---

### PART D - SUPPLEMENTAL CONDITIONS

#### General

D1. General Conditions	1
D2. Scope of Work	1
D3. Contract Administrator	1
D4. Contractor's Supervisor	1
D5. Notices	1
D6. Furnishing of Documents	2

#### Submissions

D7. Authority to Carry on Business	2
D8. Safe Work Plan	2
D9. Insurance	2
D10. Performance Security	3
D11. Subcontractor List	3
D12. Equipment List	3
D13. Detailed Work Schedule	4
D14. Security Clearance	4

#### Schedule of Work

D15. Commencement	5
D16. Critical Stages	5
D17. Substantial Performance	5
D18. Total Performance	6
D19. Liquidated Damages	6

#### Control of Work

D20. Job Meetings	6
D21. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	6

**Measurement and Payment**

D22. Payment	6
Form H1: Performance Bond	7
Form H2: Irrevocable Standby Letter of Credit	9
Form J: Subcontractor List	11
Form K: Equipment	12

**PART E - SPECIFICATIONS**

**General**

E1. Applicable Specifications and Drawings	1
--	---

**Reference Drawings**

E2. Geotechnical Information	1
------------------------------	---

**General Requirements**

E3. Office Facilities	2
E4. Dangerous Work Conditions	2
E5. Mobilization and Demobilization	3
E6. Protection of Existing Trees	3
E7. Waterway By-Law and Permits	3
E8. Shop Drawings	4
E9. Flow Control	5
E10. Site Development and Restoration	6
E11. Authorized Work on Private Property	8
E12. Outfall Sewer Repairs	8
E13. Geotextile	12
E14. Rockfill Riprap	13
E15. Rockfill Shear Key	15
E16. Channel Protection	17
E17. Topsoil and Sodding	17
E18. Silt Fence	17
E19. Tree Removal	19
E20. Riverbank Regrading	20
E21. Straw Mulch	21
E22. DFO Project Review	22
E23. Environmental Protection Plan	22
E24. Lean Mix Concrete	27
E25. Construction Of Concrete Weir Structure	27
E26. Excavation And Shoring	29
E27. Cold Weather Requirements	30
E28. Metal Fabrications	31
E29. Cleaning Existing Concrete Storm Pipe	33
E30. Access Road Construction	33
E31. Site Instrumentation	34

## **PART B - BIDDING PROCEDURES**

### **B1. CONTRACT TITLE**

B1.1 FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK STABILITY IMPROVEMENT

### **B2. SUBMISSION DEADLINE**

B2.1 The Submission Deadline is 12:00 noon Winnipeg time, December 18, 2007.

B2.2 Bids determined by the Manager of Materials to have been received later than the Submission Deadline will not be accepted and will be returned upon request.

B2.3 The Contract Administrator or the Manager of Materials may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

### **B3. SITE INVESTIGATION**

B3.1 Further to C3.1, the Bidder may view the Site without making an appointment.

B3.2 The Bidder is advised that the Site should be viewed to identify any Site restrictions that could impede the Work progress.

### **B4. ENQUIRIES**

B4.1 All enquiries shall be directed to the Contract Administrator identified in D3.1.

B4.2 If the Bidder finds errors, discrepancies or omissions in the Bid Opportunity, or is unsure of the meaning or intent of any provision therein, the Bidder shall notify the Contract Administrator of the error, discrepancy or omission, or request a clarification as to the meaning or intent of the provision at least five (5) Business Days prior to the Submission Deadline.

B4.3 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator to all Bidders by issuing an addendum.

B4.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator only to the Bidder who made the enquiry.

B4.5 The Bidder shall not be entitled to rely on any response or interpretation received pursuant to B4 unless that response or interpretation is provided by the Contract Administrator in writing.

### **B5. ADDENDA**

B5.1 The Contract Administrator may, at any time prior to the Submission Deadline, issue addenda correcting errors, discrepancies or omissions in the Bid Opportunity, or clarifying the meaning or intent of any provision therein.

B5.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.

B5.2.1 Addenda will be available on the Bid Opportunities page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

B5.2.2 The Bidder is responsible for ensuring that he has received all addenda and is advised to check the Materials Management Branch internet site for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.

B5.3 The Bidder shall acknowledge receipt of each addendum in Paragraph 10 of Form A: Bid. Failure to acknowledge receipt of an addendum may render a Bid non-responsive.

## **B6. SUBSTITUTES**

B6.1 The Work is based on the Plant, Materials and methods specified in the Bid Opportunity.

B6.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.

B6.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.

B6.4 The Bidder shall ensure that any and all requests for approval of a substitute:

- (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative;
- (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
- (c) identify any anticipated cost or time savings that may be associated with the substitute;
- (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance;
- (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance.

B6.5 The Contract Administrator, after assessing the request for approval of a substitute, may in his sole discretion grant approval for the use of a substitute as an "approved equal" or as an "approved alternative", or may refuse to grant approval of the substitute.

B6.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, only to the Bidder who requested approval of the substitute.

B6.6.1 The Bidder requesting and obtaining the approval of a substitute shall be entirely responsible for disseminating information regarding the approval to any person or persons he wishes to inform.

B6.7 If the Contract Administrator approves a substitute as an "approved equal", any Bidder may use the approved equal in place of the specified item.

B6.8 If the Contract Administrator approves a substitute as an "approved alternative", any Bidder bidding that approved alternative may base his Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B15.

B6.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.

## **B7. BID COMPONENTS**

B7.1 The Bid shall consist of the following components:

- (a) Form A: Bid;
- (b) Form B: Prices;
- (c) Form G1: Bid Bond and Agreement to Bond, or  
Form G2: Irrevocable Standby Letter of Credit and Undertaking, or  
a certified cheque or draft;

B7.2 Further to B7.1, the Bidder should include the written correspondence from the Contract Administrator approving a substitute in accordance with B6.

B7.3 All components of the Bid shall be fully completed or provided, and submitted by the Bidder no later than the Submission Deadline, with all required entries made clearly and completely, to constitute a responsive Bid.

B7.4 The Bid shall be submitted enclosed and sealed in an envelope clearly marked with the Bid Opportunity number and the Bidder's name and address.

B7.4.1 Samples or other components of the Bid which cannot reasonably be enclosed in the envelope may be packaged separately, but shall be clearly marked with the Bid Opportunity number, the Bidder's name and address, and an indication that the contents are part of the Bidder's Bid.

B7.5 Bidders are advised not to include any information/literature except as requested in accordance with B7.1.

B7.6 Bidders are advised that inclusion of terms and conditions inconsistent with the Bid Opportunity document, including the General Conditions, may result in the Bid being determined to be non-responsive.

B7.7 Bids submitted by facsimile transmission (fax) or internet electronic mail (e-mail) will not be accepted.

B7.8 Bids shall be submitted to:

The City of Winnipeg  
Corporate Finance Department  
Materials Management Branch  
185 King Street, Main Floor  
Winnipeg MB R3B 1J1

## **B8. BID**

B8.1 The Bidder shall complete Form A: Bid, making all required entries.

B8.2 Paragraph 2 of Form A: Bid shall be completed in accordance with the following requirements:

- (a) if the Bidder is a sole proprietor carrying on business in his own name, his name shall be inserted;
- (b) if the Bidder is a partnership, the full name of the partnership shall be inserted;
- (c) if the Bidder is a corporation, the full name of the corporation shall be inserted;
- (d) if the Bidder is carrying on business under a name other than his own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.

- B8.2.1 If a Bid is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B8.2.
- B8.3 In Paragraph 3 of Form A: Bid, the Bidder shall identify a contact person who is authorized to represent the Bidder for purposes of the Bid.
- B8.4 Paragraph 12 of Form A: Bid shall be signed in accordance with the following requirements:
- (a) if the Bidder is a sole proprietor carrying on business in his own name, it shall be signed by the Bidder;
  - (b) if the Bidder is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
  - (c) if the Bidder is a corporation, it shall be signed by its duly authorized officer or officers and the corporate seal, if the corporation has one, should be affixed;
  - (d) if the Bidder is carrying on business under a name other than his own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.
- B8.4.1 The name and official capacity of all individuals signing Form A: Bid shall be printed below such signatures.
- B8.4.2 All signatures should be witnessed, except where a corporate seal has been affixed.
- B8.5 If a Bid is submitted jointly by two or more persons, the word "Bidder" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Bidders in the Bid and the Contract, when awarded, shall be both joint and several.

## **B9. PRICES**

- B9.1 The Bidder shall state a price in Canadian funds for each item of the Work identified on Form B: Prices.
- B9.2 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Bids.
- B9.3 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.

## **B10. QUALIFICATION**

- B10.1 The Bidder shall:
- (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba; and
  - (b) be financially capable of carrying out the terms of the Contract; and
  - (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.
- B10.2 The Bidder and any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
- (a) be responsible and not be suspended, debarred or in default of any obligations to the City (a list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>).
- B10.3 The Bidder and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:

- (a) have successfully carried out work similar in nature, scope and value to the Work; and
- (b) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract; and
- (c) have a written workplace safety and health program if required pursuant to The Workplace Safety and Health Act (Manitoba);

B10.4 Further to B10.3(c), the Bidder shall, within three (3) Business Days of a request by the Contract Administrator, provide proof satisfactory to the Contract Administrator that the Bidder/Subcontractor has a workplace safety and health program meeting the requirements of The Workplace Safety and Health Act (Manitoba), by providing:

- (a) a valid COR certification number under the Certificate of Recognition (COR) Program administered by the Manitoba Construction Safety Association or by the Manitoba Heavy Construction Association's Safety, Health and Environment Program; or
- (b) a report or letter to that effect from an independent reviewer acceptable to the City. (A list of acceptable reviewers and the review template are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt.>)

B10.5 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.

B10.6 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

## **B11. BID SECURITY**

B11.1 The Bidder shall provide bid security in the form of:

- (a) a bid bond, in the amount of at least ten percent (10%) of the Total Bid Price, and agreement to bond of a company registered to conduct the business of a surety in Manitoba, in the form included in the Bid Submission (Form G1: Bid Bond and Agreement to Bond); or
- (b) an irrevocable standby letter of credit, in the amount of at least ten percent (10%) of the Total Bid Price, and undertaking issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form included in the Bid Submission (Form G2: Irrevocable Standby Letter of Credit and Undertaking); or
- (c) a certified cheque or draft payable to "The City of Winnipeg", in the amount of at least fifty percent (50%) of the Total Bid Price, drawn on a bank or other financial institution registered to conduct business in Manitoba.

B11.1.1 If the Bidder submits alternative bids, the bid security shall be in the amount of the specified percentage of the highest Total Bid Price submitted.

B11.1.2 All signatures on bid securities shall be original, and shall be witnessed or sealed as required.

B11.2 The bid security of the successful Bidder and the next two lowest evaluated responsive and responsible Bidders will be released by the City when a Contract for the Work has been duly executed by the successful Bidder and the performance security furnished as provided herein. The bid securities of all other Bidders will be released when a Contract is awarded.

B11.2.1 Where the bid security provided by the successful Bidder is in the form of a certified cheque or draft pursuant to B11.1(c), it will be deposited and retained by the City as the performance security and no further submission is required.

B11.2.2 The City will not pay any interest on certified cheques or drafts furnished as bid security or subsequently retained as performance security.

B11.3 The bid securities of all Bidders will be released by the City as soon as practicable following notification by the Contract Administrator to the Bidders that no award of Contract will be made pursuant to the Bid Opportunity.

## **B12. OPENING OF BIDS AND RELEASE OF INFORMATION**

B12.1 Bids will be opened publicly, after the Submission Deadline has elapsed, in the office of the Corporate Finance Department, Materials Management Branch, or in such other office as may be designated by the Manager of Materials.

B12.1.1 Bidders or their representatives may attend.

B12.1.2 Bids determined by the Manager of Materials, or his designate, to not include the bid security specified in B11 will not be read out.

B12.2 Following the submission deadline, the names of the Bidders and their Total Bid Prices (unevaluated, and pending review and verification of conformance with requirements) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

B12.3 After award of Contract, the name(s) of the successful Bidder(s) and the Contract Amount(s) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

B12.4 The Bidder is advised that any information contained in any Bid may be released if required by City policy or procedures, by The Freedom of Information and Protection of Privacy Act (Manitoba), by other authorities having jurisdiction, or by law.

## **B13. IRREVOCABLE BID**

B13.1 The Bid(s) submitted by the Bidder shall be irrevocable for the time period specified in Paragraph 11 of Form A: Bid.

B13.2 The acceptance by the City of any Bid shall not release the Bids of the next two lowest evaluated responsive Bidders and these Bidders shall be bound by their Bids on such Work until a Contract for the Work has been duly executed and the performance security furnished as herein provided, but any Bid shall be deemed to have lapsed unless accepted within the time period specified in Paragraph 11 of Form A: Bid.

## **B14. WITHDRAWAL OF BIDS**

B14.1 A Bidder may withdraw his Bid without penalty by giving written notice to the Manager of Materials at any time prior to the Submission Deadline.

B14.1.1 Notwithstanding C23.3, the time and date of receipt of any notice withdrawing a Bid shall be the time and date of receipt as determined by the Manager of Materials.

B14.1.2 The City will assume that any one of the contact persons named in Paragraph 3 of Form A: Bid or the Bidder's authorized representatives named in Paragraph 12 of Form A: Bid, and only such person, has authority to give notice of withdrawal.

B14.1.3 If a Bidder gives notice of withdrawal prior to the Submission Deadline, the Manager of Materials will:

- (a) retain the Bid until after the Submission Deadline has elapsed;

- (b) open the Bid to identify the contact person named in Paragraph 3 of Form A: Bid and the Bidder's authorized representatives named in Paragraph 12 of Form A: Bid; and
- (c) if the notice has been given by any one of the persons specified in B14.1.3(b), declare the Bid withdrawn.

B14.2 A Bidder who withdraws his Bid after the Submission Deadline but before his Bid has been released or has lapsed as provided for in B13.2 shall be liable for such damages as are imposed upon the Bidder by law and subject to such sanctions as the Chief Administrative Officer considers appropriate in the circumstances. The City, in such event, shall be entitled to all rights and remedies available to it at law, including the right to retain the Bidder's bid security.

## **B15. EVALUATION OF BIDS**

B15.1 Award of the Contract shall be based on the following bid evaluation criteria:

- (a) compliance by the Bidder with the requirements of the Bid Opportunity (pass/fail);
- (b) qualifications of the Bidder and the Subcontractors, if any, pursuant to B10 (pass/fail);
- (c) Total Bid Price;
- (d) economic analysis of any approved alternative pursuant to B6.

B15.2 Further to B15.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities, if the interests of the City so require.

B15.3 Further to B15.1(b), the Award Authority shall reject any Bid submitted by a Bidder who does not demonstrate, in his Bid or in other information required to be submitted, that he is responsible and qualified.

B15.4 Further to B15.1(c), the Total Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.

B15.4.1 If there is any discrepancy between the Total Bid Price written in figures, the Total Bid Price written in words and the sum of the quantities multiplied by the unit prices for each item, the sum of the quantities multiplied by the unit prices for each item shall take precedence.

## **B16. AWARD OF CONTRACT**

B16.1 The City will give notice of the award of the Contract or will give notice that no award will be made.

B16.2 The City will have no obligation to award a Contract to a Bidder, even though one or all of the Bidders are determined to be responsible and qualified, and the Bids are determined to be responsive.

B16.2.1 Without limiting the generality of B16.2, the City will have no obligation to award a Contract where:

- (a) the prices exceed the available City funds for the Work;
- (b) the prices are materially in excess of the prices received for similar work in the past;
- (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with its own forces;
- (d) only one Bid is received; or
- (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.

**B16.3** Subject to B16.2, where an award of Contract is made by the City, the award shall be made to the responsible and qualified Bidder submitting the lowest evaluated responsive Bid.

**B16.3.1** Following the award of contract, a Bidder will be provided with information related to the evaluation of his Bid upon written request to the Contract Administrator.

## **PART C - GENERAL CONDITIONS**

### **C0. GENERAL CONDITIONS**

- C0.1 The *General Conditions for Construction* (Revision 2006 12 15) are applicable to the Work of the Contract.
- C0.1.1 The *General Conditions for Construction* are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.
- C0.2 A reference in the Bid Opportunity to a section, clause or subclause with the prefix "**C**" designates a section, clause or subclause in the *General Conditions for Construction*.

## **PART D - SUPPLEMENTAL CONDITIONS**

### **GENERAL**

#### **D1. GENERAL CONDITIONS**

D1.1 In addition to the *General Conditions for Construction*, these Supplemental Conditions are applicable to the Work of the Contract.

#### **D2. SCOPE OF WORK**

The Work to be done under the Contract shall consist of:

- Construction of riverbank stability improvement works consisting of shear key installation, and riprap erosion protection measures for the riverbank related activities
- Replacement of approximately 40 metres of existing 2400 mm diameter CSP outfall pipe at the river outlet.
- Regrading of sloughed-in riverbank outside limits of riprap placement.
- Installation of shoring along walls of trench for CSP pipe replacement.
- Installation of concrete weir structure at upstream end of CSP outfall pipe.
- Removal of debris and silt in existing 2400 mm diameter concrete storm relief sewer.
- Site restoration

#### **D3. CONTRACT ADMINISTRATOR**

D3.1 The Contract Administrator is KGS Group, represented by:

Roy Houston, P.Eng.  
Manager Civil/Municipal Services  
3<sup>rd</sup> Floor – 865 Waverley Street, Winnipeg, Manitoba, R3T 5P4  
Telephone No. (204) 896-1206  
Facsimile No. (204) 896-0754

D3.2 At the pre-construction meeting, Mr. Houston will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

#### **D4. CONTRACTOR'S SUPERVISOR**

D4.1 At the pre-construction meeting, the Contractor shall identify his designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.

#### **D5. NOTICES**

D5.1 Except as provided for in C23.2.2, all notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the Contractor shall be sent to the address or facsimile number identified by the Contractor in Paragraph 2 of Form A: Bid.

D5.2 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the City, except as expressly otherwise required in D5.3, D5.4 or elsewhere in the Contract, shall be sent to the attention of the Contract Administrator at the address or facsimile number identified in D3.1.

- D5.3 All notices of appeal to the Chief Administrative Officer shall be sent to the following address or facsimile number:

The City of Winnipeg  
Chief Administrative Officer Secretariat  
Attn: Chief Administrative Officer  
Administration Building, 3rd Floor  
510 Main Street  
Winnipeg MB R3B 1B9  
Facsimile No.: (204) 949-1174

- D5.4 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications required to be submitted or returned to the City Solicitor shall be sent to the following address or facsimile number:

The City of Winnipeg  
Corporate Services Department  
Legal Services Division  
Attn: City Solicitor  
185 King Street, 3rd Floor  
Winnipeg MB R3B 1J1  
Facsimile No.: (204) 947-9155

#### **D6. FURNISHING OF DOCUMENTS**

- D6.1 Upon award of the Contract, the Contractor will be provided with five (5) complete sets of the Bid Opportunity. If the Contractor requires additional sets of the Bid Opportunity, they will be supplied to him at cost.

#### **SUBMISSIONS**

#### **D7. AUTHORITY TO CARRY ON BUSINESS**

- D7.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

#### **D8. SAFE WORK PLAN**

- D8.1 The Contractor shall provide the Contract Administrator with a Safe Work Plan at least five (5) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.
- D8.2 The Safe Work Plan should be prepared and submitted in the format shown in the City's template which is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

#### **D9. INSURANCE**

- D9.1 The Contractor shall provide and maintain the following insurance coverage:
- (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg added as an additional insured, with a cross-liability clause, such liability policy to also contain contractual liability, unlicensed motor vehicle liability, non-owned automobile liability and products and completed

operations, to remain in place at all times during the performance of the Work and throughout the warranty period;

- (b) automobile liability insurance for owned automobiles used for or in connection with the Work in the amount of at least two million dollars (\$2,000,000.00) at all times during the performance of the Work and until the date of Total Performance;
- (c) all risks course of construction insurance in the amount of one hundred percent (100%) of the total Contract Price, written in the name of the Contractor and The City of Winnipeg, at all times during the performance of the Work and until the date of Total Performance.

D9.2 Deductibles shall be borne by the Contractor.

D9.3 The Contractor shall provide the City Solicitor with a certificate(s) of insurance, in a form satisfactory to the City Solicitor, at least two (2) Business Days prior to the commencement of any Work but in no event later than the date specified in C4.1 for the return of the executed Contract.

D9.4 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least fifteen (15) Calendar Days prior written notice to the Contract Administrator.

## **D10. PERFORMANCE SECURITY**

D10.1 The Contractor shall provide and maintain performance security until the expiration of the warranty period in the form of:

- (a) a performance bond of a company registered to conduct the business of a surety in Manitoba, in the form attached to these Supplemental Conditions (Form H1: Performance Bond), in the amount of fifty percent (50%) of the Contract Price; or
- (b) an irrevocable standby letter of credit issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form attached to these Supplemental Conditions (Form H2: Irrevocable Standby Letter of Credit), in the amount of fifty percent (50%) of the Contract Price; or
- (c) a certified cheque or draft payable to "The City of Winnipeg", drawn on a bank or other financial institution registered to conduct business in Manitoba, in the amount of fifty percent (50%) of the Contract Price.

D10.1.1 Where the performance security is in the form of a certified cheque or draft, it will be deposited by the City. The City will not pay any interest on certified cheques or drafts furnished as performance security.

D10.2 If the bid security provided in his Bid was not a certified cheque or draft pursuant to B11.1(c), the Contractor shall provide the City Solicitor with the required performance security within seven (7) Calendar Days of notification of the award of the Contract by way of letter of intent and prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.

## **D11. SUBCONTRACTOR LIST**

D11.1 The Contractor shall provide the Contract Administrator with a complete list of the Subcontractors whom the Contractor proposes to engage (Form J: Subcontractor List) at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.

## **D12. EQUIPMENT LIST**

D12.1 The Contractor shall provide the Contract Administrator with a complete list of the equipment which the Contractor proposes to utilize (Form K: Equipment List) at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.

### **D13. DETAILED WORK SCHEDULE**

- D13.1 The Contractor shall provide the Contract Administrator with a detailed work schedule at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.
- D13.2 The detailed work schedule shall consist of the following:
- (a) a critical path method (C.P.M.) schedule for the Work;
  - (b) a Gantt chart for the Work based on the C.P.M. schedule;
  - (c) a daily manpower schedule for the Work;
- all acceptable to the Contract Administrator.
- D13.3 Further to D13.2(a), the C.P.M. schedule shall clearly identify the start and completion dates of all of the following activities/tasks making up the Work as well as showing those activities/tasks on the critical path:
- (a) Geotechnical/Riverbank Stability Works (to be completed prior to other activities)
  - (b) Installation of Trench Shoring
  - (c) Cleaning Existing Concrete Storm Pipe
  - (d) Construction of Concrete Weir Structure
  - (e) Installation of CSP Outfall Pipe
  - (f) Placement of Riprap
  - (g) Restoration of Site
- D13.4 Further to D13.2(b), the Gantt chart shall show the time on a weekly basis, required to carry out the Work of each trade, or specification division. The time shall be on the horizontal axis, and the type of trade shall be on the vertical axis.
- D13.5 Further to D13.2(c), the daily manpower schedule shall list the daily number of individuals on the Site for each trade.

### **D14. SECURITY CLEARANCE**

- D14.1 Each individual proposed to perform the following portions of the Work:
- (a) any Work on private property;
- shall be required to obtain a Criminal Record Search Certificate from the police service having jurisdiction at his place of residence.
- D14.2 Prior to the commencement of any Work specified in D14.1, and during the term of the Contract if additional or replacement individuals are proposed to perform Work, the Contractor shall supply the Contract Administrator with a Criminal Record Search Certificate obtained not earlier than one (1) year prior to the Submission Deadline, or a certified true copy thereof, for each individual proposed to perform such Work.
- D14.3 Any individual for whom a Criminal Record Search Certificate is not provided, or for whom a Criminal Record Search Certificate indicates any convictions or pending charges related to property offences or crimes against another person, will not be permitted to perform any Work specified in D14.1.
- D14.4 Any Criminal Record Search Certificate obtained thereby will be deemed valid for the duration of the Contract subject to a repeated records search as hereinafter specified.
- D14.5 Notwithstanding the foregoing, at any time during the term of the Contract, the City may, at its sole discretion and acting reasonably, require an updated criminal records search. Any individual who fails to provide a satisfactory Criminal Record Search Certificate as a result of a

repeated criminal records search will not be permitted to continue to perform any Work specified in D14.1.

## **SCHEDULE OF WORK**

### **D15. COMMENCEMENT**

- D15.1 The Contractor shall not commence any Work until he is in receipt of a letter of intent from the Award Authority authorizing the commencement of the Work.
- D15.2 The Contractor shall not commence any Work on the Site until:
- (a) the Contract Administrator has confirmed receipt and approval of:
    - (i) evidence of authority to carry on business specified in D7;
    - (ii) evidence of the workers compensation coverage specified in C6.15;
    - (iii) the Safe Work Plan specified in D8;
    - (iv) evidence of the insurance specified in D9;
    - (v) the performance security specified in D10;
    - (vi) the Subcontractor list specified in D11;
    - (vii) the equipment list specified in D12;
    - (viii) the detailed work schedule specified in D13; and
    - (ix) the security clearances specified in D14.
  - (b) the Contractor has attended a pre-construction meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a pre-construction meeting.
- D15.3 The Contractor shall commence the Work on the Site within seven (7) Working Days of receipt of the letter of intent.
- D15.4 The City intends to award this Contract by January 15, 2008.
- D15.4.1 If the actual date of award is later than the intended date, the dates specified for Commencement, Critical Stages, Substantial Performance, and Total Performance will be adjusted by the difference between the aforementioned intended and actual dates.

### **D16. CRITICAL STAGES**

- D16.1 The Contractor shall achieve critical stages of the Work in accordance with the following requirements:
- (a) Riverbank Stabilization Work (installation of Rockfill Shear Key) must be completed first prior to any other work required in this contract.

### **D17. SUBSTANTIAL PERFORMANCE**

- D17.1 The Contractor shall achieve Substantial Performance by March 31, 2008.
- D17.2 When the Contractor considers the Work to be substantially performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Substantial Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be reinspected.
- D17.3 The date on which the Work has been certified by the Contract Administrator as being substantially performed to the requirements of the Contract through the issue of a certificate of Substantial Performance is the date on which Substantial Performance has been achieved.

## **D18. TOTAL PERFORMANCE**

- D18.1 The Contractor shall achieve Total Performance by June 15, 2008..
- D18.2 When the Contractor or the Contract Administrator considers the Work to be totally performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Total Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be reinspected.
- D18.3 The date on which the Work has been certified by the Contract Administrator as being totally performed to the requirements of the Contract through the issue of a certificate of Total Performance is the date on which Total Performance has been achieved.

## **D19. LIQUIDATED DAMAGES**

- D19.1 If the Contractor fails to achieve critical stages, Substantial Performance or Total Performance in accordance with the Contract by the days fixed herein for same, the Contractor shall pay the City the following amounts per Business Day for each and every Business Day following the days fixed herein for same during which such failure continues:
- (a) Substantial Performance – One thousand dollars (\$1,000.00);
  - (b) Total Performance – Five hundred dollars (\$500.00).
- D19.2 The amounts specified for liquidated damages in D19.1 are based on a genuine pre-estimate of the City's losses in the event that the Contractor does not achieve critical stages, Substantial Performance or Total Performance by the days fixed herein for same.
- D19.3 The City may reduce any payment to the Contractor by the amount of any liquidated damages assessed.

## **CONTROL OF WORK**

### **D20. JOB MEETINGS**

- D20.1 Regular weekly job meetings will be held at the Site. These meetings shall be attended by a minimum of one representative of the Contract Administrator, one representative of the City and one representative of the Contractor. Each representative shall be a responsible person capable of expressing the position of the Contract Administrator, the City and the Contractor respectively on any matter discussed at the meeting including the Work schedule and the need to make any revisions to the Work schedule. The progress of the Work will be reviewed at each of these meetings.
- D20.2 The Contract Administrator reserves the right to cancel any job meeting or call additional job meetings whenever he deems it necessary.

### **D21. PRIME CONTRACTOR – THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA)**

- D21.1 Further to C6.24, the Contractor shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

## **MEASUREMENT AND PAYMENT**

### **D22. PAYMENT**

- D22.1 Further to C12, effective January 1, 2007 the City may at its option pay the Contractor by direct deposit to the Contractor's banking institution.

**FORM H1: PERFORMANCE BOND**  
(See D10)

KNOW ALL MEN BY THESE PRESENTS THAT

\_\_\_\_\_ ,  
(hereinafter called the "Principal"), and

\_\_\_\_\_ ,  
(hereinafter called the "Surety"), are held and firmly bound unto **THE CITY OF WINNIPEG** (hereinafter called the "Obligee"), in the sum of

\_\_\_\_\_ dollars (\$\_\_\_\_\_)

of lawful money of Canada to be paid to the Obligee, or its successors or assigns, for the payment of which sum the Principal and the Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS the Principal has entered into a written contract with the Obligee dated the

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, for:

BID OPPORTUNITY NO. 876-2007

FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK STABILITY IMPROVEMENT

which is by reference made part hereof and is hereinafter referred to as the "Contract".

NOW THEREFORE the condition of the above obligation is such that if the Principal shall:

- (a) carry out and perform the Contract and every part thereof in the manner and within the times set forth in the Contract and in accordance with the terms and conditions specified in the Contract;
- (b) perform the Work in a good, proper, workmanlike manner;
- (c) make all the payments whether to the Obligee or to others as therein provided;
- (d) in every other respect comply with the conditions and perform the covenants contained in the Contract; and
- (e) indemnify and save harmless the Obligee against and from all loss, costs, damages, claims, and demands of every description as set forth in the Contract, and from all penalties, assessments, claims, actions for loss, damages or compensation whether arising under "The Workers Compensation Act", or any other Act or otherwise arising out of or in any way connected with the performance or non-performance of the Contract or any part thereof during the term of the Contract and the warranty period provided for therein;

THEN THIS OBLIGATION SHALL BE VOID, but otherwise shall remain in full force and effect. The Surety shall not, however, be liable for a greater sum than the sum specified above.

AND IT IS HEREBY DECLARED AND AGREED that the Surety shall be liable as Principal, and that nothing of any kind or matter whatsoever that will not discharge the Principal shall operate as a discharge or release of liability of the Surety, any law or usage relating to the liability of Sureties to the contrary notwithstanding.

IN WITNESS WHEREOF the Principal and Surety have signed and sealed this bond the

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

SIGNED AND SEALED  
in the presence of:

\_\_\_\_\_  
(Witness)

\_\_\_\_\_  
(Name of Principal)

Per: \_\_\_\_\_ (Seal)

Per: \_\_\_\_\_

\_\_\_\_\_  
(Name of Surety)

By: \_\_\_\_\_ (Seal)  
(Attorney-in-Fact)

**FORM H2: IRREVOCABLE STANDBY LETTER OF CREDIT  
(PERFORMANCE SECURITY)**  
(See D10)

\_\_\_\_\_  
(Date)

The City of Winnipeg  
Corporate Services Department  
Legal Services Division  
185 King Street, 3rd Floor  
Winnipeg MB R3B 1J1

RE: PERFORMANCE SECURITY - BID OPPORTUNITY NO. 876-2007

FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK STABILITY  
IMPROVEMENT

Pursuant to the request of and for the account of our customer,

\_\_\_\_\_  
(Name of Contractor)

\_\_\_\_\_  
(Address of Contractor)

WE HEREBY ESTABLISH in your favour our irrevocable Standby Letter of Credit for a sum not exceeding  
in the aggregate

\_\_\_\_\_ Canadian dollars.

This Standby Letter of Credit may be drawn on by you at any time and from time to time upon written demand for payment made upon us by you. It is understood that we are obligated under this Standby Letter of Credit for the payment of monies only and we hereby agree that we shall honour your demand for payment without inquiring whether you have a right as between yourself and our customer to make such demand and without recognizing any claim of our customer or objection by the customer to payment by us.

The amount of this Standby Letter of Credit may be reduced from time to time only by amounts drawn upon it by you or by formal notice in writing given to us by you if you desire such reduction or are willing that it be made.

Partial drawings are permitted.

We engage with you that all demands for payment made within the terms and currency of this Standby Letter of Credit will be duly honoured if presented to us at:

\_\_\_\_\_  
(Address)

and we confirm and hereby undertake to ensure that all demands for payment will be duly honoured by us.

All demands for payment shall specifically state that they are drawn under this Standby Letter of Credit.

Subject to the condition hereinafter set forth, this Standby Letter of Credit will expire on

\_\_\_\_\_  
(Date)

It is a condition of this Standby Letter of Credit that it shall be deemed to be automatically extended from year to year without amendment from the present or any future expiry date, unless at least 30 days prior to the present or any future expiry date, we notify you in writing that we elect not to consider this Standby Letter of Credit to be renewable for any additional period.

This Standby Letter of Credit may not be revoked or amended without your prior written approval.

This credit is subject to the Uniform Customs and Practice for Documentary Credit (1993 Revision), International Chamber of Commerce Publication Number 500.

\_\_\_\_\_  
(Name of bank or financial institution)

Per: \_\_\_\_\_  
(Authorized Signing Officer)

Per: \_\_\_\_\_  
(Authorized Signing Officer)



**FORM K: EQUIPMENT**  
(See D12)

**FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK STABILITY IMPROVEMENT**

<p><b>1. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>
<p><b>2. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>
<p><b>3. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>

**FORM K: EQUIPMENT**  
(See D12)

**FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK STABILITY IMPROVEMENT**

<p><b>4. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>
<p><b>5. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>
<p><b>6. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>

## PART E - SPECIFICATIONS

### GENERAL

#### E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

- E1.1 These Specifications shall apply to the Work.
- E1.2 *The City of Winnipeg Standard Construction Specifications* in its entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.
- E1.2.1 *The City of Winnipeg Standard Construction Specifications* is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.
- E1.2.2 The version in effect three (3) Business Days before the Submission Deadline shall apply.
- E1.2.3 Further to C2.4(d), Specifications included in the Bid Opportunity shall govern over *The City of Winnipeg Standard Construction Specifications*.
- E1.3 The following Drawings are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
	Cover Sheet
876-2007-Drawing_LD-3774-R0	Fort Rouge Park Outfall (AS-92)
876-2007-Drawing_LD-3824-R0	Existing 2400 Conc SRS Pipe Inspection Details
876-2007-Drawing_LD-3775-R0	Miscellaneous Details
876-2007-Drawing_LD-3776-R0	Existing Site Conditions (June 2007)
876-2007-Drawing_LD-3777-R0	Trench Shear Key and Riprap Plan
876-2007-Drawing_LD-3778-R0	Sections and Details
876-2007-Drawing_LD-3779-R0	Concrete Weir Structure Location Plan and Profile
876-2007-Drawing_LD-3780-R0	Concrete Weir Structure Concrete Details
876-2007-Drawing_LD-3781-R0	Concrete Weir Structure Reinforcing Details
876-2007-Drawing_LD-3782-R0	Concrete Weir Structure - Miscellaneous Metal Details

#### Reference Drawings

876-2007-Drawing_SC-15745-R0	Site Details - Existing Gate Chamber - Part 1 of 2
876-2007-Drawing_SC-15745-R0	Site Details - Existing Gate Chamber - Part 2 of 2
876-2007-Drawing_SC-15753-R0	Details of River Avenue Storm Relief Gate Chamber

#### E2. GEOTECHNICAL INFORMATION

- E2.1 Further to C3.1, of the General Conditions, geotechnical test holes have been drilled in the vicinity of the proposed Works to determine the character of the subsurface soil to facilitate the design of the Work. The information is considered accurate at the locations indicated and at the time of the investigation. However, considerable variations in the soil conditions may exist between test holes and fluctuations in ground water levels can be expected seasonally. Test hole logs are included.
- E2.2 Bidders are responsible for any interpretation they place on the supplied information and are expected to make such additional investigation of the soil as they feel necessary to satisfy themselves.
- E2.3 Any test borings made by the Bidder shall be done in accordance with the requirements of the appropriate authority of the City of Winnipeg. Bidders shall notify the Contract Administrator prior to starting any soil boring operation.

## GENERAL REQUIREMENTS

### E3. OFFICE FACILITIES

- E3.1 The Contractor shall supply office facilities meeting the following requirements:
- (a) The field office shall be for the exclusive use of the Contract Administrator.
  - (b) The building shall be conveniently located near the Site of the Work.
  - (c) The building shall have a minimum floor area of 25 square metres, two windows for cross ventilation and a door entrance with a suitable lock.
  - (d) The building shall be suitable for all weather use. It shall be equipped with an electric heater and air conditioner so that the room temperature can be maintained between either 16-18°C or 24-25 °C.
  - (e) The building shall be adequately lighted with fluorescent fixtures and have a minimum of three wall outlets.
  - (f) The building shall be furnished with two desks, two drafting tables, table 3m X 1.2m, one stool, one four drawer legal size filing cabinet, and a minimum of 12 chairs.
  - (g) The building shall have a working landline telephone service connection.
  - (h) A portable toilet shall be located near the field office building. The toilet shall have a locking door and be for the exclusive use of the Contract Administrator and other personnel from the City.
  - (i) The field office building and the portable toilet shall be cleaned on a weekly basis immediately prior to each Site meeting. The Contract Administrator may request additional cleaning when he deems it necessary.
- E3.2 The Contractor shall be responsible for all installation and removal costs, all operating costs, and the general maintenance of the office facilities.
- E3.3 The office facilities will be provided from the date of the Commencement of the Work until Total Performance.

### E4. DANGEROUS WORK CONDITIONS

- E4.1 Further to clause C 6.24 of the General Conditions, the Contractor shall be aware that underground chambers, manholes, and sewers are considered a confined space and shall follow the "Guidelines for confined Entry Work" as published by the Manitoba Workplace Safety and Health Division.
- E4.2 The Contractor shall be aware of the potential hazards that can be encountered in gate chambers, manholes and sewers such as explosive gases, toxic gases and oxygen deficiency.
- E4.3 The air in a confined space must be tested before entry and continuously during the time that personnel are inside the space. Equipment for continuous monitoring of gases must be explosion-proof and equipped with a visible and audible alarm. The principal tests are for oxygen deficiency, explosion range and toxic gases. Testing equipment must be calibrated in accordance with manufacturer's specifications.
- E4.4 The Contractor shall ventilate all confined spaces including underground chambers, tunnels, pipes and shafts as required and approved by the Manitoba Workplace Safety and Health Act (the "Act"). If no ventilation is supplied, a Worker must wear a respirator or supplied air to enter the confined space.
- E4.5 Workers must wear a respirator or supplied air at all times when entering a chamber, manhole or sewer where live sewage is present.
- E4.6 The Contractor shall provide a photoionization detector (PID) on Site at all times to monitor potential hydrocarbon vapours in the confined spaces. The gas detector and safety equipment

conforming to the Act shall be made available to the Contract Administrator for his use during inspections. In addition, the Contract Administrator shall collect discrete air samples for laboratory analysis.

- E4.7 The Contract Administrator may issue a Stop Work order to the Contractor if the above guidelines are not being followed. The Contractor shall not resume his operations until the Contract Administrator is satisfied the Contractor is following the appropriate procedures. The Contractor shall have no claim for extra time or costs due to the Stop Work order for not following these safety guidelines.

## **E5. MOBILIZATION AND DEMOBILIZATION**

- E5.1 Mobilization and demobilization will include but not be limited to start-up costs, equipment setup and removal, field office and storage facilities set-up and removal and Site cleanup.
- E5.2 Mobilization and demobilization will be measured on a unit basis and paid for at the Contract Unit Price for "Mobilization and Demobilization" in accordance with this specification, accepted and measured by the Contract Administrator.
- E5.3 50% of the Mobilization and Demobilization unit price will be paid on the first progress payment.
- E5.4 The remaining 50% of the Mobilization and Demobilization unit price will be paid subsequent to the completion of the Work and restoration and clean up of the Site.

## **E6. PROTECTION OF EXISTING TREES**

- E6.1 Work in this contract will include removal of existing trees within the limits of construction. There are some large trees located near the project limits that will need to be preserved. Prior to construction, the Contract Administrator will identify specifically which trees are to be kept. Where a tree needs to be preserved, the Contractor shall take the following precautionary steps to avoid damage from construction activities to existing trees within the limits of the construction area.
- E6.1.1 Do not stockpile materials and soil or park vehicles and equipment within 2 metres of trees.
- E6.1.2 Strap mature tree trunks with 25 x 150 x 2400 wood planks. Smaller trees shall be similarly protected using appropriately sized wood planks.
- E6.1.3 Excavations shall be carried out in a manner to minimize damage to existing root systems. Where roots must be cut to facilitate an excavation they shall be neatly pruned at the face of the excavation.
- E6.1.4 Work on Site shall be carried out in a manner to minimize damage to existing tree branches. Where damage to tree branches does occur, the Contractor shall neatly prune the damaged branch.
- E6.1.5 American elm trees shall not be pruned between April 1st and August 1st and Siberian elm trees between April 1st and July 1st of any year under provisions of The Dutch Elm Disease Act.
- E6.2 All damage to existing trees due to construction activities shall be repaired to the requirements and satisfaction of the City of Winnipeg, Public Works Department, Forestry Branch at the Contractor's expense.
- E6.3 Costs for protection of trees shall be considered incidental to the tree removal costs.

## **E7. WATERWAY BY-LAW AND PERMITS**

- E7.1 The Contractor shall note that all Works fall within 107 metres (350 feet) of the regulated summer water level of the Red River and are therefore within the jurisdiction of the Waterway

By-law. The Contract Administrator will apply and pay for the required Waterway Permits for the permanent Work. The Contractor shall adhere to restrictions imposed by the permit.

E7.2 The Contractor shall be responsible to apply and pay for a Waterway Permit for all temporary Works including construction access ramps as outlined in E10.3.

E7.3 Under no circumstances will stockpiling of any material be permitted within 107 metres of the regulated summer water level of the Red River.

## **E8. SHOP DRAWINGS**

E8.1 Description

(a) This Specification shall revise, amend and supplement the requirements of CW 1100.

- (i) The term 'shop drawings' means drawings, diagrams, illustrations, schedules, performance charts, brochures, and other data, including Site erection drawings which are to be provided by the Contractor to illustrate details of a portion of the Work.
- (ii) The Contractor shall submit specified shop drawings to the Contract Administrator for review. All submissions must be in metric units. Where data is in imperial units, the correct metric equivalent shall also be show on all submissions for Engineering review.

(b) Shop Drawings

- (i) Original drawings are to be prepared by Contractor, Subcontractor, Supplier, Distributor, or Manufacturer, which illustrate appropriate portion of Work; showing fabrication, layout, setting or erection details as specified in appropriate sections.
- (ii) Shop drawings for the following structural components shall bear the seal of a registered Contract Administrator of Manitoba.
  - (a) Shoring.
  - (b) Reinforcing steel.
  - (c) Metal Fabrications.

(c) Contractor's Responsibilities

- (i) Review shop drawings, product data and samples prior to submission and stamp and sign drawings indicating conformance to the Contract requirements.
- (ii) Verify:
  - (a) Field Measurements
  - (b) Field Construction Criteria
  - (c) Catalogue numbers and similar data
- (iii) Coordinate each submission with requirements of Work and Contract Documents. Individual shop drawings will not be reviewed until all related drawings are available.
- (iv) Notify Contract Administrator, in writing at time of submission, of deviations from requirements of Contract Documents.
- (v) Responsibility for deviations in submission from requirements of Contract Documents is not relieved by Contract Administrator's review of submission, unless Contract Administrator gives written acceptance of specified deviations.
- (vi) Responsibility for errors and omissions in submission is not relieved by Contract Administrator's review of submittals.
- (vii) The Contractor shall make any corrections required by the Contract Administrator and shall resubmit the required number of corrected copies of Shop Drawings. The Contractor shall direct specific attention in writing or on resubmitted Shop Drawings to revisions other than the corrections requested by the Contract Administrator on previous submission.
- (viii) After Contract Administrator's review and return of copies, distribute copies to subtrades as appropriate.

- (ix) Maintain one (1) complete set of reviewed shop drawings, filed by Specification Section Number, at the Site of the Work for use and reference of the Contract Administrator and Subcontractors.
- (d) Submission Requirements
  - (i) Schedule submissions at least 14 Calendar Days before dates reviewed submissions will be needed, and allow for a 14 Calendar Day period for review by the Contract Administrator of each individual submission and re-submission, unless noted otherwise in the Contract Documents.
  - (ii) Submit five (5) paper prints of shop drawings. The Contractor is advised that the Contract Administrator will retain three (3) copies of all submittals and return two (2) copies to the Contractor.
  - (iii) Accompany submissions with transmittal letter, containing:
    - (a) Date
    - (b) Project title and Bid Opportunity number
    - (c) Contractor's name and address
    - (d) Number of each shop drawing, product data and sample submitted
    - (e) Specification Section, Title, Number and Clause
    - (f) Drawing Number and Detail/Section Number
    - (g) Other pertinent data
  - (iv) Submissions shall include:
    - (a) Date and revision dates.
    - (b) Project title and Bid Opportunity number.
    - (c) Name of:
      - (a) Contractor
      - (b) Subcontractor
      - (c) Supplier
      - (d) Manufacturer
      - (e) Separate detailer when pertinent
    - (d) Identification of product of material.
    - (e) Relation to adjacent structure or materials.
    - (f) Field dimensions, clearly identified as such.
    - (g) Specification section name, number and clause number or drawing number and detail/section number.
    - (h) Applicable standards, such as CSA or CGSB numbers.
    - (i) Contractor's stamp, initialed or signed, certifying review of submission, verification of field measurements and compliance with Contract Documents.
- (e) Other Considerations
  - (i) Fabrication, erection, installation or commissioning may require modifications to equipment or systems to conform to the design intent. Revise pertinent shop drawings and resubmit.
  - (ii) Material and equipment delivered to the Site of the Works will not be paid for at least until pertinent shop drawings have been submitted and reviewed.
  - (iii) Incomplete shop drawing information will be considered as stipulated deductions for the purposes of progress payment certificates.
  - (iv) No delay or cost claims will be allowed that arise because of delays in submissions, re-submissions and review of shop drawings.

## **E9. FLOW CONTROL**

- E9.1 During winter months land drainage and storm relief sewers can receive flow of an undetermined amount from groundwater infiltration, watermain breaks, snow melt and other unforeseen sources.
- E9.2 Provide flow control measures to contend with and maintain flow in the storm relief sewer directed to the outfall pipe being replaced. Flow control measures shall include but not be limited to diversions, flumes and by-pass pumping.

- E9.3 Discharge hoses for by-pass pumping shall not be laid across vehicle or pedestrian traffic areas and must be protected from freezing during winter months. Pumping equipment if used, shall be set-up in a location and in such a way to not be a noise problem for nearby residences
- E9.4 Provide a flow control plan to the Contract Administrator for review before removing any existing sewer pipe.
- E9.5 Costs for flow control shall be considered incidental to the installation of CSP outfall pipe, under the item "Removal and Installation of CSP".
- E9.6 In the event the flow in the sewer system is expected to exceed the sewer capacity due to spring runoff, the Contract Administrator may suspend Work activities that require temporary by-pass pumping and temporary shutdown of the Site. Suspension of these activities will continue until the high flow diminishes in the sewer.
- E9.7 If in the opinion of the Contract Administrator suspension of Work activities that require temporary by-pass pumping and temporary shutdown of the Site may cause a delay in completion of the Work through no fault of the Contractor, the completion date of the Work will be adjusted accordingly.

## **E10. SITE DEVELOPMENT AND RESTORATION**

### **E10.1 Description**

This Specification shall cover all aspects of the Site Development and restoration Work, including erection, maintenance and removal of safety fencing, sediment control Works, snow clearing, general access development, access maintenance and removal, and Site restoration.

### **E10.2 Materials**

#### **E10.2.1 Equipment**

All equipment, implements, tools and facilities used shall be of a size and type as required to complete the Work in a reasonable time, approved by the Contract Administrator. The Contractor shall keep all equipment in good Working order, and have sufficient standby equipment available at all times, as required.

### **E10.3 Construction Methods**

#### **E10.3.1 Site and Construction Access**

The Contractor shall be responsible to develop suitable Site access. This includes but is not limited to, temporary bridging over structures, temporary removal and reinstallation of safety fencing, any landscaping and grading repairs, restoration of vegetation, etc. necessary to restore any Site and construction access areas to their pre-existing condition. Prior to commencing construction the Contractor shall submit their site access plan to the Contract Administrator for approval.

All construction access ramps from the top bank area down to the edge of the river shall be constructed by excavating to the necessary ramp grade and disposing of the material off Site. Under no circumstances will the excavated material or any additional materials be placed as fill in the ramp area. Detailed construction access ramp drawings are to be submitted to the Contract Administrator for approval a minimum seven (7) days prior to any construction activity on Site.

The Contractor is responsible for obtaining and paying for all required permits and permissions that are necessary for Site access, including a Waterways Permit, if required by the City of Winnipeg. Contact Don Kingerski, P.Eng., Riverbank Management Contract Administrator at 986-5159 for information regarding Waterways Permits.

The locations of the Contractor's construction access ramps shall be restored to the same condition or better than it was prior to the initiation of any Work.

E10.3.2 Existing Chain Link Fence

The existing chain link fence along the right-of-way may be removed and replaced, if necessary, to permit installation of temporary shoring. New fence materials including wire mesh, posts, rails, fasteners, and any other required items shall be used for the reconstruction and shall be consistent with the existing fence.

E10.3.3 Frozen Waterways Permit

The Contractor is responsible for obtaining a Frozen Water Permit for permission to Work on the river ice. Contact the City of Winnipeg Police Service.

E10.3.4 Vegetation Removal

Some vegetation (small trees and sod) removal will be permitted in order to facilitate Site access. Existing vegetation shall not be removed without prior approval from the Contract Administrator. The Contractor shall load and haul any removed vegetation, and dispose of the material off Site immediately upon collection. Stockpiling shall not be permitted unless written approval has been obtained from the Contract Administrator.

E10.3.5 Snow and Ice Removal

Snow cover shall be cleared from the riverbank and hauled off-site prior to placement of the rockfill riprap. The methodology to clear the snow shall be subject to the approval of the Contract Administrator.

Ice at the shoreline of the River shall be broken and cleared before the placement of riprap below ice level. Care shall be taken to ensure that the ice is removed, and does not become trapped below rockfill riprap placement.

E10.3.6 Safety Fence

The Contractor shall erect and maintain for the duration of the project, a safety fence acceptable to the Contract Administrator to restrict access to the Site. The fencing shall enclose the entire Site with appropriate gates or openings that are closed at the end of each Work day. Appropriate signs shall be erected to warn all recreational users of the river that an open water hazard exists. This shall include but not be limited to snowmobilers and skiers. The installed fencing shall consist of Dupont Number L70 orange plastic safety fence or approved equal, with a mesh spacing of 45 mm, constructed as shown in the contract drawings. Upon completion of the Work, the fence shall be removed and disposed of off Site.

E10.3.7 Environmental Regulations

- (b) The Contractor shall adhere to all relevant Federal and Provincial environmental regulations.
- (c) The Contractor shall plan to Work in accordance with the current environmental regulations of "Manitoba Stream Crossing Guidelines for Protection of Fish and Fish Habitat", Fisheries and Oceans, and Manitoba Natural Resources.
- (d) The Contractor shall supply, in writing, prior to commencement of Work on-site, a detailed plan for sediment control on this project.
- (e) The Contractor shall ensure that a sufficient supply of suitable spill kits are on-site to cleanup minor spills, should they occur. The Contractor shall supply the name, address and phone number of a local supplier, where additional kits are available on short notice.

E10.3.8 General Site Cleanup and Restoration

All areas of the construction Site shall be restored to a condition at least equivalent to its original condition prior to initiation of Work. This may include, but is not necessarily limited

to the Contractor's lay down area, the removal of the Contract Administrator Site trailer, and removal of all temporary fencing.

**E10.3.9 Topsoil and Sod**

All topsoil and sodding Work within the limits of the right of way and shear key area shall be in accordance with E17. All other existing grassed areas disturbed by the Contractor during construction, which are not designated for construction of items to be permanently incorporated into the Work, shall be restored by the Contractor to existing condition or better using topsoil and sod at his own cost.

**E10.4 Method of Measurement and Payment**

**Site Development and Restoration**

The Site development and restoration will be measured and paid for at the Contract Lump Sum Price for "Site Development and Restoration", which price shall be payment in full for supplying all materials and for performing all operations herein described and all other items incidental to the Work included in this Specification.

**E11. AUTHORIZED WORK ON PRIVATE PROPERTY**

**E11.1** Portions of the Work must be performed on private property. The Contract Administrator will obtain permission for any permanent Work that must be performed at 1 and 7 Roslyn Road.

**E11.2** Further to C 6.26, the Contractor shall confine his Works to the right-of-way or easements. Where Work is required to be done on private property other than specified in E11.1 the Contract Administrator will authorize such Work in writing after the Contractor has provided in writing to the Contract Administrator the permission of the affected property owner.

**E12. OUTFALL SEWER REPAIRS**

**E12.1 Description**

This Specification shall amend and supplement Standard Specifications CW 2130, CW 2160, and CW 3610.

The Work to be done by the Contract under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies, and all things necessary for and incidental to the satisfactory performance and completion of all Work hereinafter specified.

**E12.2 Materials**

**E12.2.1 Handling and Storage of Materials**

All materials shall be handled and stored in a careful and Workman-like manner, to the satisfaction of the Contract Administrator.

**E12.2.2 Testing and Approval**

All materials supplied under this Specification shall be subject to inspection and testing by the Contract Administrator or by the Testing Laboratory designated by the Contract Administrator. There shall be no charge to the City for any materials supplied for testing purposes.

**E12.2.3 Slip Joint**

Shop drawings shall be submitted for all slip joints. The slip joint shall be installed as shown on the drawings. Galvanizing shall be hot-dip conforming to the requirements of CSA G164-N1981, to a minimum net retention of 600g/m<sup>2</sup>. All bolts and nuts shall be galvanized steel conforming to ASTM A-325. All welding shall be fully approved by the Canadian

Welding Bureau in conformance with CSA Standard W.47.1. Welding splatter and other fabricator burrs, where exposed, shall be ground off and/or field smooth, and left ready for subsequent operations. All miscellaneous metal, after fabrication, shall be hot-dip galvanized.

E12.2.4 Galvanized Primer

Galvanized primer for repair of damaged coating shall be zinc rich, ready mix to CGSB-1-GP-181M.

E12.2.5 Bedding and Backfill Material

Sand bedding and Modified Class 2 backfill material as per CW 2030, modified to have 0.6 m of compacted excavated Site select material as opposed to the detailed 0.3 m of compacted excavated material.

E12.2.6 CSP Outfall Pipe

Shall be the wall thickness as shown on the construction drawings, CSP as per Clause 5.3 of CW 3610.

E12.2.7 CSP Couplers, CSP Saddles and Concrete Transition Coupler

- (a) Material for CSP to CSP connections shall conform to CSA Specification CAN3-G401. Standard or dimpled with bolt and angle attachments.
- (b) Material for CSP saddle connections shall conform to CSA Specification CAN3-G401. Galvanized primer for repair of damaged coating shall be zinc rich, ready mix to CGSB-1-GP-181M.
- (c) Material for concrete transition collars shall be in accordance with CW 2160 Type B concrete.

E12.2.8 Debris Grating

Shop drawings shall be submitted for the debris gratings and shall be installed as shown on the drawings. Galvanizing shall be hot-dip conforming to requirements of CSA G164-N1981 to a minimum net retention of 600g/m<sup>2</sup>. All bolts and nuts shall be typical steel, conforming to ASTM A-320 Grade B8M. All welding shall be fully approved by the Canadian Welding Bureau in conformance with CSA Standard W47.1. Welding shall be done by currently licensed welders only. Welding splatter and other fabricator burrs, where exposed, shall be ground off and/or filed smooth, and left ready for subsequent operations. All miscellaneous metal, after fabrication, shall be hot-dip galvanized. No separate measurement will be made for hot-dip galvanizing.

E12.2.9 Equipment

All equipment, implements, tools and facilities used shall be of a size and type as required to complete the Work in a reasonable time, approved by the Contract Administrator. The Contractor shall keep all equipment in good Working order, and have sufficient standby equipment available at all times, as required.

E12.3 Construction Methods

E12.3.1 Bedding

Ensure bedding is thoroughly tamped and that the pipe is uniformly supported throughout and completed in accordance with CW 2030, unless otherwise indicated by the Contract Administrator.

E12.3.2 Backfill

Backfill around the pipe, in maximum 300-mm lifts, alternating from side to side. At no time should the difference in backfill elevation on either side of the pipe be greater than 450 mm. Work must be completed in accordance with CW 2030, unless otherwise indicated by the Contract Administrator.

Backfilling above the pipe shall be in accordance with CW 2030 for Modified Class 2 backfill. The top 600-mm of backfill is to be Site select excavated material, as approved on Site by the Contract Administrator, not the standard 300 mm excavated material. The Contractor shall ensure the compaction equipment utilized, is consistent with degree of compactive effort required to achieve the specified densities, and adequately protects against overloading the pipe.

#### E12.3.3 Trench Shoring And Excavation

At locations shown on the drawings the trench shall be dug and maintained using a wood or steel shoring, designed and sealed by a Structural Professional Engineer who is a member of the Association of Professional Engineers and Geoscientists of the Province of Manitoba (APEGM). The Contractor shall provide shop drawings to the Contract Administrator, for review, prior to the start of excavation. Work must be completed in accordance with CW 2030, unless otherwise indicated by the Contract Administrator.

The Contractor shall provide temporary shoring as specified in section E26 at the locations and to the grades shown on the drawings. The temporary shoring installed during the construction operations must be removed upon completion of construction. Shoring installed shall be common for the weir structure and pipe trench.

The Contractor shall take precautionary steps to prevent damage from construction activities to adjacent private property. All damage to adjacent private property caused by the Contractor's activities shall be repaired to, equal or better condition than prior to construction, as approved by the Contract Administrator. No separate measurement or payment will be made for the protection of adjacent private property.

#### E12.3.4 Diversion of Flows

Flows such as snowmelt, rainfall, a watermain break, or any other flow travelling through the outfall shall be diverted during construction. The cost of the flow diversion is considered incidental to the installation of the pipe.

#### E12.3.5 Removal and Installation of CSP

CSP field cuts shall be straight circumferential cuts. Clean all ends free of burrs etc., and touch up all areas affected by Work with galvanized primer.

The Contractor shall excavate and dispose of the existing outfall piping and debris grate in accordance with the Standard Construction Specifications.

All outfall pipes shall be installed as shown on the drawings and in accordance with CW 3610.

All pipes shall be laid to the established line and grade.

Work required for "Removal and Installation of CSP shall include removal and disposal of existing the CSP, including any debris found within.

#### E12.3.6 Connections

Provide lean mix concrete pipe bedding and backfill to the lines and grades as detailed in the contract drawings.

Slip joints are to be internal unless noted otherwise on the drawings. The receiving pipes are to be cleaned of all surface debris, including but not limited to frozen backfill, ice and internal sediment.

The slip joints are to be installed in locations as shown on the drawings and as directed by the Contract Administrator. Angle brackets are to be located at the 9:00 and 3:00 o'clock position unless approved otherwise by the Contract Administrator. Bolts are to be tightened evenly throughout the coupler.

E12.3.7 Installation of Debris Grate

Debris Grates shall be installed as detailed and in the location shown on the contract drawings.

E12.3.8 Shop Drawings

Submit prepared shop drawings for the: slip joint and debris grate details in accordance with Clause 1.5 of CW 1110.

E12.4 Method of Measurement and Payment

E12.4.1 Removal and Installation of CSP

The removal and installation of the CSP shall be measured on a linear basis. The length to be paid for shall be the total number of linear meters of CSP, measured from the tie-in point to the tip of the manufactured bevelled end section, horizontally above the center of the pipe installed in accordance with this Specification and acceptable to the Contract Administrator. The bevelled end section, and removal of both the existing CSP and existing debris grate shall be considered incidental to the installation of the CSP and no separate payment will be made.

Removal and installation of CSP will be paid for at the Contract Unit Price for "Removal and Installation of CSP", measured specified herein, which price shall be payment in full for performing all operations described and all other items incidental to the Work included in this Specification.

E12.4.2 Supply and Installation of Slip Joints

The supply and installation of Slip Joints shall be measured on a unit basis. The Contractor shall be paid for the total number of slip joints installed in accordance with this Specification, as measured by the Contract Administrator.

E12.4.3 Supply and Installation of Debris Grates

The supply and installation of the Debris Grate shall be measured on a unit basis. The units to be paid for shall be the total number of Debris Grates installed in accordance with this Specification and acceptable to the Contract Administrator as computed from measurements made by the Contract Administrator.

Supply and installation of Debris Grate will be paid for at the Contract Unit Price for "Supply and Installation of Debris Grate", measured specified herein, which price shall be payment in full for performing all operations described and all other items incidental to the Work included in this Specification.

E12.4.4 Supply and Installation of Trench Shoring

The supply and installation of the trench shoring shall be paid be paid for at the contract lump sum price for "Supply and Installation of Trench Shoring", as specified in E26, which price shall be payment in full for performing all operations described, including but not limited to excavation within the shoring and all other items incidental to the Work included in this Specification.

E12.4.5 Supply and Placement of Lean Mix Concrete

The supply and installation of lean mix concrete shall be paid be paid for at the contract unit price for "Lean Mix Concrete", which price shall be payment in full for performing all operations described and all other items incidental to the Work included in this Specification.

**E13. GEOTEXTILE**

E13.1 Description

E13.1.1 This Specification shall cover the supply and placement of the geotextile fabric below the rockfill riprap.

E13.2 Materials

E13.2.1 Each geotextile roll to be used shall be tagged to provide product identification for inventory and quality control purposes.

E13.2.2 Geotextile rolls shall be furnished with suitable wrapping for protection against moisture and extended exposure from the sun, and contamination from dirt, dust, and any other deleterious materials. The geotextile shall remain wrapped in a protective covering until it is used.

E13.2.3 Non-woven geotextile fabric shall meet or exceed the following requirements:

Parameter	Test Method	Minimum Criteria
Grab Tensile Strength	ASTM D4632	900 N
Mullen Burst	ASTM D3786	2600 kPa
Puncture	ASTM D4833	550 N
Trapezoidal Tear	ASTM D4533	350 N
Apparent Opening Size	ASTM D4751	1.2 mm
Permittivity	ASTM D4491	1.2 sec <sup>-1</sup>
zFlow Rate	ASTM D4491	60 L/sec/m <sup>2</sup>

E13.2.4 Suitable products shall be Amoco 4553, Layfield LP 8, Emco R080, Geotex 801, Terrafix 600R, Armtec 250, Mirafi 180 N, Trevira 011/250, or approved equivalent.

E13.3 Construction Methods

E13.3.1 Geotextiles shall consist of non-woven fabric.

E13.3.2 All Work related to the geotextile storage, handling, and installation shall comply with the procedures and recommendations of the manufacturers, and as accepted by the Contract Administrator.

E13.3.3 Snow and ice shall be cleared from the riverbank in accordance with E10.3.5 prior to placement of geotextile.

E13.3.4 The fabric shall be loosely laid in order to allow conformity to the bedding surface. Folds and wrinkles in the fabric shall be avoided. Pins, nails or weights shall be installed to hold the fabric in place such that placement of fill material will not excessively stretch or tear the fabric and seam overlaps will be maintained.

E13.3.5 The fabric shall be overlapped in a downstream direction (upstream panel overtop of downstream panel) at all joints a minimum of 600 mm. The overlap shall be pinned or secured as approved by the Contract Administrator.

E13.3.6 A minimum of 300 mm of material shall be placed over the fabric prior to equipment passage.

E13.3.7 Riprap shall be placed on the geotextile in such a manner that the geotextile is not damaged, torn, excessively stretched, or punctured.

E13.3.8 Any damaged geotextile, as identified by the Contract Administrator, shall be repaired immediately at the Contractors own cost. All fill material shall be cleared a minimum of 1 m

around the damaged area. The damaged area shall be covered with a geotextile patch that shall be large enough to be sewn or overlapped a minimum of 600 mm onto the undamaged geotextile.

**E13.4 Measurement and Payment**

E13.4.1 The supply and placement of geotextile, and related Work specified herein will be measured on an area basis and paid for at the Contract Unit Price for "Geotextile". The area to be paid for shall be the total number of square metres of ground covered by geotextile, placed in accordance with this Specification, accepted and measured by the Contract Administrator.

E13.4.2 Overlap at all joints shall be considered a single layer of geotextile for measure and payment purposes.

E13.4.3 Geotextile used for repairs will be excluded from the quantity paid.

**E14. ROCKFILL RIPRAP**

**E14.1 Description**

E14.1.1 This Specification shall cover the supply and placement of rockfill riprap.

**E14.2 Materials**

E14.2.1 The rockfill material for use as riprap shall consist of a clean free draining, sound, dense, durable, crushed rock. The material shall be free from organics, roots, silts, sand, clay, snow, ice or any other material that would detract from the strength and drainage characteristics of clean rockfill.

E14.2.2 Individual particles shall be shaped such that no dimension is greater than two times the smallest dimension. Flat, elongated, or platy particle shapes will not be accepted.

E14.2.3 Should the Contractor choose to use limestone, it shall be durable white crystalline limestone. Softer buff to yellow dolomite or dolostone will not be accepted.

E14.2.4 The rockfill material shall meet the following requirements:

Parameter	Test Method	Specified Limit
Bulk Specific Gravity	ASTM C127	2.6 minimum
Absorption	ASTM C127	2.5 % maximum
LA Abrasion Loss	ASTM C131	32% maximum
Soundness	ASTM C88	13% maximum
Gradation	ASTM D5519	See below

E14.2.5 Rockfill riprap shall be well graded having a full range and even distribution of sizes and shall conform to the following gradation:

Canadian Metric Sieve Size (millimeters)	Percent of Total Dry Weight Passing Each Sieve
450	100%
300	35-80%
100	20-60%
50	10-30%
5	0-5%

### E14.3 Submittals

E14.3.1 The Contractor shall submit the proposed supplier(s) and location of quarry Sites for supply of riprap.

E14.3.2 Representative samples of the rockfill riprap submitted for material testing purposes shall be completed as specified herein.

### E14.4 Quarry Sites

E14.4.1 Contractors supplying rockfill riprap shall be responsible for demonstrating that the material is of adequate quality and volume to meet the material specifications contained herein.

### E14.5 Testing and Approval

E14.5.1 All materials set forth in this Specification shall be subject to inspection and testing by the Contract Administrator or by the testing laboratory designated by the Contract Administrator. There shall be no charge for any materials taken by the Contract Administrator for testing purposes.

E14.5.2 The Contract Administrator will visit proposed quarry Sites for inspection of the proposed rockfill material and quarry faces a minimum of fourteen (14) days prior to supply and placement of riprap.

E14.5.3 No supply and placement of riprap will be permitted prior to the Contract Administrator reviewing the source.

E14.5.4 The procedures for preparation of all rockfill samples for use in material inspection and testing shall be subject to review and acceptance by the Contract Administrator for individual tests. The samples may be obtained from crushed and processed material at the sizing necessary for specific tests if the material is deemed to be representative of the riprap that will be used, subject to the acceptance of the Contract Administrator.

E14.5.5 The testing frequency necessary to confirm the material quality will be specified at the discretion of the Contract Administrator.

### E14.6 Construction Methods

E14.6.1 Riverbank regrading shall be performed in accordance with E.20

E14.6.2 Snow and ice shall be cleared from the bank in accordance with E10.3.5.

E14.6.3 Rockfill shall be pushed or rolled into place in such a manner that the larger rocks are uniformly distributed and the smaller rocks serve to fill the places between the larger rocks such that excessive segregation of the various particle sizes does not occur.

E14.6.4 Sufficient levelling shall be done to produce a neat and uniform surface, conforming to the shape and dimensions shown on the Drawings.

E14.6.5 The allowable fill tolerances shall be within  $\pm 50$  mm of the grades and thickness shown on the Drawings, provided positive downslope grading is achieved.

E14.6.6 Provide a smooth uniform surface from the existing grade and new riprap when placing outside edges or transitions, as accepted by the Contract Administrator.

E14.6.7 Temporary stockpiling of riprap along the riverbank shall not be permitted. Material shall be placed to the required lines and grades shown the Drawings immediately upon delivery to the Site.

### E14.7 Measurement and Payment

E14.7.1 The supply and placement of rockfill shall be measured on a weight basis and paid for at the Contract Unit Price for "Rockfill Riprap". The weight to be paid for shall be the total number of metric tonnes of rockfill supplied and placed in accordance with this

Specification, as measured by a certified weigh scale and accepted by the Contract Administrator.

- E14.7.2 The Contractor shall provide the weigh tickets to the Contract Administrator for the material supplied to the Site at the time of delivery. No payment will be made for any weigh tickets which are not supplied at the time of delivery, or which are lost.

## **E15. ROCKFILL SHEAR KEY**

### **E15.1 Description**

- E15.1.1 This Specification shall cover the construction of the rockfill shear key, including the excavation, disposal of excavated material, supply and placement of rockfill and clay cap backfill, and provisions for handling groundwater infiltration.

- E15.1.2 The Work to be done by the Contractor under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies and all things necessary for an incidental to the satisfactory performance and completion of all Work as hereinafter specified.

### **E15.2 Materials**

#### **E15.2.1 General**

- (a) The Contractor shall be responsible for the supply, safe storage and handling of all materials set forth in this Specification.

#### **E15.2.2 Rockfill Backfill**

- (a) The rockfill material for use as backfill shall be as specified for rockfill riprap in section E14.2

#### **E15.2.3 Clay Cap**

The impervious clay cap at the top of the rockfill shear key shall consist of a high plasticity clay material, with a liquid limit in excess of 50%. The clay shall be free of deleterious material such as roots, organic material, ice, snow or other unsuitable materials, and may be salvaged from the on-site excavation, as approved by the Contract Administrator. Frozen material will not be accepted.

### **E15.3 Submittals**

- E15.3.1 The Contractor shall submit the proposed supplier(s) and location of quarry Sites for supply of rockfill backfill.

### **E15.4 Quarry Sites**

- E15.4.1 Contractors supplying rockfill backfill shall be responsible for demonstrating that the material is of adequate quality and volume to meet the material specifications contained herein.

### **E15.5 Testing and Approval**

- E15.5.1 All materials set forth in this Specification shall be subject to inspection and testing by the Contract Administrator or by the testing laboratory designated by the Contract Administrator. There shall be no charge for any materials taken by the Contract Administrator for testing purposes.

- E15.5.2 The Contract Administrator will visit proposed quarry Sites for inspection of the proposed rockfill material and quarry faces a minimum of fourteen (14) days prior to supply and placement of riprap.

- E15.5.3 No supply and placement of rockfill backfill will be permitted prior to the Contract Administrator reviewing the source.

E15.5.4 The procedures for preparation of all rockfill samples for use in material inspection and testing shall be subject to review and acceptance by the Contract Administrator for individual tests. The samples may be obtained from crushed and processed material at the sizing necessary for specific tests if the material is deemed to be representative of the riprap that will be used, subject to the acceptance of the Contract Administrator.

E15.5.5 The testing frequency necessary to confirm the material quality will be specified at the discretion of the Contract Administrator.

## E15.6 Construction Methods

### .1 General

The excavation shall be supervised at all times, and open shafts shall be adequately guarded or covered for safety.

### .2 Shear Key Construction

The shear key excavation shall be excavated to the depths and widths, and in the locations shown on the Drawings. An adequate volume of rockfill for backfilling shall be on-site prior to excavation of each incremental length of trench shear key. The excavation shall proceed in a timely manner and rockfill must be placed as soon as excavation takes place. Stockpiling of excavated material on the riverbank will not be permitted. The maximum open length of the shear key shall be 2 metres along the bottom of the excavation. The Contractor shall maintain the excavation in dry condition and shall require to prevent surface water from entering the excavation.

In no case shall the shear key be left open at the end of the day. The shear key must be filled with rockfill at the end of each day.

After placement of the rockfill to the required dimensions as shown on the Drawings, the impervious clay cap shall be placed in layers not exceeding 200 millimetres, and compacted to a minimum 95% of the Standard Proctor Maximum Dry Density. The clay cap shall be located within undisturbed native material surrounding the trench. Care shall be taken to ensure that an effective seal results between the wall of the excavation and the clay material placed to protect against water infiltration into the trench, as approved by the Contract Administrator.

Water infiltration and bottom blow out may occur as the bottom of the trench approaches the till. The top elevation of the trench excavation shall be located to minimize the risk of river water entering the excavation. Discharge water contained within the trench excavation from displacement of the rockfill during placement will be acceptable. The Contractor shall be responsible to contain and direct any displaced water such that it will not affect other construction work or cause excessive erosion of the native riverbank soils. The control of water shall be the responsibility of the Contractor and shall be considered incidental to the Work.

### .3 Supply of Rockfill

The Contractor shall monitor the supply rate of rockfill material to ensure backfilling operations are not delayed.

### .4 Stockpiling of Rockfill Material

The stockpiling of rockfill material on the lower bank will not be permitted at locations where the trench shear key has not been installed. The methodology for stockpiling of rockfill at the lower area at locations where the trench shear key has been installed shall be subject to approval of the Contract Administrator.

### .5 Contaminated Rockfill Material

Where crushed limestone has become contaminated with silt, clay, snow, ice or other deleterious material due to the Contractor's method of operation, negligence, failure to backfill in a timely manner, etc. the material shall be classified as rejected backfill and shall be weighed prior to disposal for deduction from the total weight of crushed limestone measured for payment.

## 6.8 Measurement and Payment

### .1 Shear Key Excavation

The excavation for the shear key construction will be measured on a volume basis and paid for at the Contract Unit Price for "Shear Key Excavation". The volume to be paid for shall be the total number of cubic metres of material excavated and disposed of in accordance with this Specification as computed from the measured depth and length, fixed base width and 0.25H:1V side slopes as shown on the Drawings.

The supply and placement of the clay cap shall be incidental to the shear key excavation. No separate payment will be made for the clay cap.

### .2 Rockfill

The supply and placement of the rockfill for the trench shear key will be measured on a weight basis and paid for at the Contract Unit Price for "Rockfill Backfill". The weight to be paid for shall be the total number of metric tonnes of rockfill material supplied and placed in accordance with this Specification as measured by a certified weigh scale and accepted by the Contract Administrator. The Contractor shall provide the weigh tickets to the Contract Administrator for the material supplied to the Site at the time of delivery. No payment will be made for any weigh tickets which are not supplied at the time of delivery, or which are lost.

## E16. CHANNEL PROTECTION

The ice surface and riverbank channel shall be cleared of construction materials prior to ice break-up. The Contractor shall clean up all materials, including but not limited to: soil, snow fence, construction debris, etc. from this construction activity. All items that will have an adverse impact on the channel shall be removed. Channel Protection shall be considered incidental to the Works of this Contract and no measurement or payment will be made for this item.

## E17. TOPSOIL AND SODDING

The riverbank area within the limits of the outfall Right of Way and limits of rockfill shear key and riprap construction shall be re-vegetated with topsoil and sod or seed and straw mulch, as indicated on the Drawings. Work shall be in accordance with, and shall be measured and paid in accordance with CW 3510.

## E18. SILT FENCE

### E18.1 Description

E18.1.1 This specification covers the erection of temporary silt fencing, which shall be installed and maintained at the locations shown on the drawings to control runoff and minimize the release of detrimental silt loading to watercourses.

E18.1.2 The scope Work included in this specification is as follows:

- (a) Supply and Install temporary silt fencing at the locations as indicated on the Drawings, in accordance with the detailed drawing provided, immediately upon completion of the shear key and riprap placement and prior to undertaking any other activities on the Site where silt fencing is required.
- (b) Maintain the silt fencing in serviceable condition throughout the entire duration of activities at the Site where silt fencing is required, including final restoration and cleanup of the construction Site.
- (c) Remove the silt fencing and restore the area where the fencing was installed, without further disturbing the area and without releasing any deleterious substances to the adjacent watercourse.

**E18.2 Materials**

**E18.2.1 Fences Posts**

- (b) Fence posts shall be 100 mm diameter untreated wood posts or 50 mm diameter steel.

**E18.2.2 Filter Fabric**

- (c) Filter Fabric Shall be a woven geotextile material specifically designed for a silt fence applications, meeting the following minimum requirements:

<b>Property</b>	<b>Test Method</b>	<b>Value</b>
Grab Tensile Strength	ASTM D 4632	0.55 kN
Grab Tensile Elongation	ASTM D 4632	15%
Mullen Burst	ASTM D 4786	2060 kPa
Puncture	ASTM D 4833	0.285 kN
Trapezoid Tear	ASTM D 4533	0.285 kN
UV Resistance	ASTM D 435	5 80 % @ 500 hrs
Apparent Opening Size (AOS)	ASTM D 4751	0.60 mm
Flow Rate	ASTM D 4491	405 l/min/m <sup>2</sup>

Acceptable Product: "Amoco 2130 Silt Fence Fabric" or approved equal.

**E18.2.3 Wire Mesh**

- (a) Wire mesh shall be galvanized or plain metal with wire gauge = 3.0 mm, wire spacing @ 150 mm o/c.

**E18.2.4 Fencing Material Fasteners**

- (a) Staples or wire ties of sufficient strength and spacing to withstand 500 N (100 lbf) pull test at any point on the wire mesh.

**E18.3 Construction Methods**

**E18.3.1** Ensure that no deleterious substances are discharged into the adjacent watercourse at any time during construction activities.

**E18.3.2 Silt Fence Installation**

- (b) Excavate 150 x 150 anchor trench along alignment of silt fence as indicated.
- (c) Install fence posts as indicated. Ensure that fence posts are firmly driven into undisturbed soil, or are completely and firmly backfilled if installed via auger methods. Attach wire mesh as support backing for silt fence filter fabric with fasteners as specified in E18.2.4. Attach silt fence filter fabric on top of wire mesh in similar fashion. Overlap any fence seams (wire mesh or filter fabric) by 450 mm minimum. Ensure that wire mesh and filter fabric are installed on the upslope side of the post and are fully laid in anchor trench as shown.
- (d) Install and compact impermeable excavated materials into anchor trench and slope as indicated. Compact to 95% of maximum dry density (ASTM D-698).

**E18.3.3 Silt Fence Maintenance**

- (e) Inspect silt fence daily, prior to starting any other construction activities. If fence posts are found loose or not upright, repair in accordance with installation procedure as specified in E18.3.2. If silt fence is found to be loose or torn, repair or replace as necessary to comply with E18.3.2.
- (f) If silt deposition at the fence is 300 mm or more in depth, carefully remove and dispose of silt offsite without disturbing silt fence.

#### E18.3.4 Silt Fence Removal

- (g) The silt fence shall remain in place until new vegetation growth has established on the bank, as determined by the Contract Administrator.
- (h) Upon authorization of the Contract Administrator, remove all fence posts, wire mesh, fabric, and fasteners from Site.
- (i) Restore areas disturbed in accordance with E10, without releasing any deleterious substances to the adjacent watercourse.

#### E18.4 Measurement and Payment

E18.4.1 The supply, placement, and removal of silt fence shall be measured on a length basis and paid for at the Contract Unit Price per lineal metre for "Silt Fence". The length to be paid for shall be the total number of metres supplied and placed in accordance with this Specification, accepted and measured by the Contract Administrator. Payment of silt fence shall be in accordance with the following payment schedule:

- (a) Sixty percent (60%) of the Contract Unit Price per lineal metre for "Silt Fence" shall be paid following supply and installation.
- (b) Forty percent (40%) of the Contract Unit Price per lineal metre for "Silt Fence" shall be paid following final removal.

E18.4.2 Removal of accumulated sediment from the silt fence is considered incidental to the Work and no separate measurement or payment will be made.

### **E19. TREE REMOVAL**

#### E19.1 Description

E19.1.1 This specification shall cover the removal of existing trees.

E19.1.2 The Work to be done by the Contractor under this specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies and all things necessary for and incidental to the satisfactory performance and completion of all Work as hereinafter specified.

#### E19.2 Materials

##### E19.2.1 Existing Trees to be Removed

The existing trees to be removed include, but not limited to ash, elm, cottonwood, oak, pine, maple, spruce, etc., all of which may be cut with standard chain saw equipment. The existing trees range from 50 mm to 1,000 mm diameter.

#### E19.3 Construction Methods

E19.3.1 Prior to commencement of the Work the Contract Administrator shall identify all trees for removal. The Contractor shall cut down only trees designated to be removed, and grub out all stumps and roots greater than 100 mm diameter. In general, the Contractor shall start at the top of the tree and remove branches or trunks not longer than 2 m. Trees are to be felled so as to land within the limits of the Works. The Contractor shall load and haul all trees, stumps, roots, logs, brush, rubbish and all other surface litter from the Site and dispose of these materials at an approved disposal Site, acceptable to the Contract Administrator.

E19.3.2 The Contractor shall take all precautions to prevent damage to structures, adjacent property and to trees and shrubs. In the event of damage, the Contractor will be held liable, and shall be required to provide appropriate restoration at his cost, to the satisfaction of the Contract Administrator.

E19.3.3 Any trees damaged during construction activities shall be examined by a bonded tree care professional and pruned as required. Damaged trees which are not viable shall be replaced by the Contractor at his own cost.

#### E19.4 Measurement and Payment

- E19.4.1 The removal of existing trees shall be measured on a per tree basis and paid for at the Contract Unit Price per unit for "Tree Removal", "50 mm to 250 mm diameter", "greater than 250 mm to 500 mm diameter", "greater than 500 mm diameter". The amount to be paid shall be the total number of trees removed in accordance with this specification, accepted and measured by the Contract Administrator.
- E19.4.2 The removal of trees and brush less than 50 mm diameter is considered incidental to the Work and no separate measurement or payment will be made.

### **E20. RIVERBANK REGRADING**

#### E20.1 Description

- E20.1.1 This Specification shall cover excavation and regrading of the riverbank.
- E20.1.2 The Work to be done under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies, and all things necessary for and incidental to the satisfactory performance and completion of all Works as hereinafter specified.
- E20.1.3 This Specification shall supplement and amend standard City of Winnipeg Specification CW3170-R3.

#### E20.2 Materials

##### E20.2.1 Excavation

The materials covered in this Specification consist of the in-situ overburden soils and may include but not necessarily limited to organic topsoil, clay, silt, sand, gravel, fill, rubble, trees, tree roots, shrubs, etc., all of which may be excavated with standard hydraulic excavation equipment.

##### E20.2.2 Clay Fill

The clay backfill for the slope regrading shall consist of a high plasticity material with a liquid limit in excess of 50%. The clay shall be free of deleterious material such as roots, organics, ice, snow or other unsuitable materials, and may be salvaged from the rockfill shear key excavation as approved by the Contract Administrator. Placement of frozen material will not be acceptable.

#### E20.3 Construction Methods

##### E20.3.1 Stripping and Topsoil Excavation

All existing vegetation and topsoil within the limits of the riverbank regrading shall be stripped in accordance with clauses 9.2(a) and (b) of CW3170-R3 and disposed of off Site.

##### E20.3.2 Common Excavation

All material encountered within the limits of the riverbank regrading following stripping shall be excavated to the lines and grades shown on the Drawings. All excavation shall proceed from the top of slope down to minimize the potential for slope instability. All materials shall be removed off Site immediately upon excavation. The allowable excavation tolerances shall be with 50 mm of the grade shown on the Drawings, provided positive drainage is achieved.

##### E20.3.3 Clay Fill

Open scarps shall be subcut to a depth of 0.6m x 1.0m wide and backfilled with select clay as directed by the Contract Administrator.

Clay fill shall be placed along the bank to the lines, grades, and elevations shown on the Drawings. The clay shall be spread and placed in layers not exceeding 150 mm thick and compacted to 95% SPMDD.

## E20.4 Measurement and Payment

### E20.4.1 Riverbank Regrading

- (a) Riverbank regrading including Stripping, Topsoil and Common Excavation shall be measured on a volume basis and paid for at the Contract Unit Price for "Riverbank Regrading". The volume to be paid for shall be the total number of cubic metres of material excavated in accordance with this Specification, as measured by the Contract Administrator. Excavated volumes will be computed by the average end area method.
- (b) Excavation required for outfall pipe repairs and concrete weir construction is not part of this Specification. This item is to be completed in accordance with Specification E12.

### E20.4.2 Clay Fill

Placement of clay fill is considered incidental to the regrading Work and no separate measurement or payment will be made.

## E21. STRAW MULCH

### E21.1 Description

- E21.1.1 This Specification shall cover the supply and placement of straw mulch on all areas of the riverbank to provide temporary erosion protection where existing vegetation has been removed.

### E21.2 Materials

- E21.2.1 The material shall consist of wheat or barley straw, or other plants approved by the Contract Administrator. The straw mulch shall be air dried, reasonably light in colour, and shall not be musty, mouldy, caked or otherwise of low quality. The mulch shall be free of coarse (chaff) material and free of noxious weeds and/or seeds to prevent the introduction of weeds into previously seeded and planted areas. Dry mulching material that breaks down and does not bend will not be acceptable. The power mulching process shall produce a minimum of 75% of the straw being between 150 mm and 200 mm in length.

### E21.3 Construction Methods

#### E21.3.1 General

- (a) The Contractor shall supply and place straw mulch material immediately after final grading is completed and prior to March 31 of any year.
- (b) Straw mulch shall be placed ensuring that there is a minimum of 90% ground coverage by area, as measured and accepted by the Contract Administrator.
- (c) Mulched areas shall be inspected periodically and after runoff producing storm events. Damaged areas shall be repaired immediately as determined by the Contract Administrator. Areas requiring remulching as directed by the Contract Administrator will be re-measured and additionally paid for at the Contract Unit Price for the Work item.

#### E21.3.2 Spreading of Straw Mulch Material

- (a) The straw mulch material shall be spread at a rate of 0.45 kg/m<sup>2</sup>, to a layer 25 to 50 mm in thickness. Mulch that remains clumped or bunched after application shall be separated and respread.

#### E21.3.3 Removal of Straw Mulch

- (a) Immediately prior to placement of topsoil and sod and/or topsoil and seed all straw mulch shall be removed and disposed of off Site.

#### E21.4 Measurement and Payment

- E21.4.1 Supply placement and removal of straw mulch will be measured on an area basis and paid for at the Contract Unit Price for "Straw Mulch". The area to be paid for shall be the total number of square metres of ground covered by straw mulch, supplied and placed in accordance with this specification, accepted and measured by the Contract Administrator.

#### **E22. DFO PROJECT REVIEW**

- E22.1 The Contractor is advised that the City of Winnipeg has submitted a request for project review to Fisheries and Oceans Canada. A copy of the DFO Submission is included in the Appendix. Methodologies outlined in the submission, including but not limited to, construction methods, schedules, sediment and erosion control, and site restoration shall apply to the Work.

#### **E23. ENVIRONMENTAL PROTECTION PLAN**

- E23.1 The Contractor shall plan and implement the Work of this Contract strictly in accordance with the requirements of the Environmental Protection Plan as herein specified, Fisheries Authorization & CEAA Screening report.
- E23.2 The Contractor is advised that at least the following Acts, Regulations, and By-laws apply to the Work and are available for viewing at the office of the Contract Administrator.

##### **A. Federal**

1. Canadian Environmental Assessment Act (CEAA) c.37
2. Transportation of Dangerous Goods Act and Regulations c.34
3. The Fisheries Act
4. Navigable Waters Protection Act

##### **B. Provincial**

1. The Dangerous Goods Handling and Transportation Act D12
2. The Endangered Species Act E111
3. The Environment Act c.E125
4. The Fire Prevention Act F80
5. The Manitoba Heritage Resources Act H39.1
6. The Manitoba Noxious Weeds Act N110
7. The Manitoba Nuisance Act N120
8. The Public Health Act c.P210
9. The Workplace Safety and Health Act W210
10. And current applicable associated regulations.  
(Note: Provincial regulations updated as of September 1999)

##### **C. Municipal**

1. The City of Winnipeg By-law No. 2480/79 and all amendments up to and including 7969/2000
2. The City of Winnipeg By-law No. 1573/77 and all amendments up to and including 7670/2000
3. And any other applicable Acts, Regulations, and By-Laws.

- E23.3 The Contractor is advised that the following environmental protection measures apply to the Work.

##### **A. Materials Handling and Storage**

1. Construction materials shall not be deposited or stored on riverbanks or river shorelines unless written acceptance from the Contract Administrator is received in advance.

2. Construction materials and debris shall be prevented from entering the Assiniboine River. In the event that materials and/or debris inadvertently enter the watercourse, the Contract shall be required to remove the material and restore the watercourse to its original condition.

#### **B. Fuel Handling and Storage**

1. The Contractor shall obtain all necessary permits from Manitoba Conservation for the handling and storage of fuel products and shall provide copies to the Contract Administrator.
2. All fuel handling and storage facilities shall comply with The Dangerous Goods and Transportation Act Storage and Handling of Petroleum Products Regulation and any local land use permits.
3. Fuels, lubricants, and other potentially hazardous materials as defined in The Dangerous Goods and Transportation Act shall be stored and handled within the approved storage areas.
4. In accordance with Section 2.5 (Construction: General Guidelines) of the Manitoba Stream Crossing Guidelines for the Protection of Fish and Fish Habitat, (DFO and DNR, 1996), the Contractor shall ensure that any temporary fuel storage areas established for construction of the project are contained by an impermeable dike and are located a minimum distance of 100 metres away from the high water line of the Assiniboine River. Dikes shall be designed, constructed, and maintained to retain not less than 100% of the capacity of the total number of containers or 110% of the largest container, whichever is greatest. The dikes shall be constructed of clay or similar impervious material. If this type of material is not available, the dike shall be constructed of locally available material and lined with high density polyethylene (HDPE). Furthermore, the fuel storage area(s) shall be secured by a barrier such as a high fence and gate to prevent vandalism.
5. The Contractor shall ensure that all fuel storage containers are inspected daily for leaks and spillage.
6. Products transferred from the fuel storage area(s) to specific Work Sites shall not exceed the daily usage requirement.
7. When servicing requires the drainage or pumping of fuels, lubricating oils or other fluids from equipment, a groundsheet of suitable material (such as HDPE) and size shall be spread on the ground to catch the fluid in the event of a leak or spill.
8. Refuelling of mobile equipment and vehicles shall take place at least 100 metres from a watercourse.
9. The area around storage Sites and fuel lines shall be distinctly marked and kept clear of snow and debris to allow for routine inspection and leak detection.
10. A sufficient supply of materials, such as absorbent material and plastic oil booms, to clean up minor spills shall be stored nearby on-site. The Contractor shall ensure that additional material can be made available on short notice.

#### **C. Waste Handling and Disposal**

1. The construction area shall be kept clean and orderly at all times during and at completion of construction.
2. At no time during construction shall personal or construction waste be permitted to accumulate for more than one day at any location on the construction Site, other than at a dedicated storage area as may be approved by the Contract Administrator.

3. All resulting debris shall be deposited at a Waste Disposal Ground operating under the authority of Manitoba Regulation #150/91. Exceptions are liquid industrial and hazardous wastes which may require special disposal methods (see SC:21.4 D).
4. Indiscriminate dumping, littering, or abandonment shall not take place.
5. No on-site burning of waste is permitted.
6. Waste storage areas shall not be located so as to block natural drainage.
7. Run-off from a waste storage area shall not be allowed to cause siltation of a watercourse.
8. Waste storage areas shall be left in a neat and finished appearance and/or restored to their original condition to the satisfaction of the Contract Administrator.
9. Equipment shall not be cleaned near watercourses; contaminated water from onshore cleaning operations shall not be permitted to enter watercourses.

**D. Dangerous Goods/Hazardous Waste Handling and Disposal**

1. Dangerous goods/hazardous wastes are identified by, and shall be handled according to, The Dangerous Goods Handling and Transportation Act and Regulations.
2. The Contractor shall be familiar with The Dangerous Goods Handling and Transportation Act and Regulations.
3. The Contractor shall have on-site staff that is trained and certified in the handling of the dangerous/hazardous goods, when said dangerous/hazardous goods are being utilized on-site for the performance of the Work.
4. Different waste streams shall not be mixed.
5. Disposal of dangerous goods/hazardous wastes shall be at approved hazardous waste facilities.
6. Liquid hydrocarbons shall not be stored or disposed of in earthen pits on-site.
7. Used oils shall be stored in appropriate drums, or tankage until shipment to waste oil recycling centres, incinerators, or secure disposal facilities approved for such wastes.
8. Used oil filters shall be drained, placed in suitable storage containers, and buried or incinerated at approved hazardous waste treatment and disposal facilities.
9. Dangerous goods/hazardous waste storage areas shall be located at least 100 metres away from the high water line and be dyked.
10. Dangerous goods/hazardous waste storage areas shall not be located so as to block natural drainage.
11. Run-off from a dangerous goods/hazardous waste storage area shall not be allowed to cause siltation of a watercourse.
12. Dangerous goods/hazardous waste storage areas shall be left in a neat and finished appearance and/or restored to their original condition to the satisfaction of the Contract Administrator.

## **E. Emergency Response**

1. The Contractor shall ensure that due care and caution is taken to prevent spills.
2. The Contractor shall report all major spills of petroleum products or other hazardous substances with significant impact on the environment and threat to human health and safety (as defined in Table 1 below) to Manitoba Conservation, immediately after occurrence of the environmental accident, by calling the 24-hour emergency phone number (204) 945-4888. The Contract Administrator shall also be notified.
3. The Contractor shall designate a qualified supervisor as the on-site emergency response co-ordinator for the project. The emergency response co-ordinator shall have the authority to redirect manpower in order to respond in the event of a spill.
4. The following actions shall be taken by the person in charge of the spilled material or the first person(s) arriving at the scene of a hazardous material accident or the on-site emergency response co-ordinator:
  1. Notify emergency-response co-ordinator of the accident:
    - identify exact location and time of accident
    - indicate injuries, if any
    - request assistance as required by magnitude of accident (Manitoba Conservation 24-hour Spill Response Line (204) 945-4888, Police, Fire Department, Ambulance, company backup)
  - Attend to public safety:
    - stop traffic, roadblock/cordon off the immediate danger area
    - eliminate ignition sources
    - initiate evacuation procedures if necessary
  - Assess situation and gather information on the status of the situation, noting:
    - personnel on-site
    - cause and effect of spill
    - estimated extent of damage
    - amount and type of material involved
    - proximity to waterways, sewers, and manholes
  - If safe to do so, try to stop the dispersion or flow of spill material:
    - approach from upwind
    - stop or reduce leak if safe to do so
    - dike spill material with dry, inert sorbet material or dry clay soil or sand
    - prevent spill material from entering waterways and utilities by diking
    - prevent spill material from entering manholes and other openings by covering with rubber spill mats or diking
  - Resume any effective action to contain, clean up, or stop the flow of the spilled product.
5. The emergency response co-ordinator shall ensure that all environmental accidents involving contaminants shall be documented and reported to Manitoba Conservation according to The Dangerous Goods Handling and Transportation Act Environmental Accident Report Regulation 439/87.
6. When dangerous goods are used on-site, materials for containment and cleanup of spill material (e.g. absorbent materials, plastic oil booms, and oversized recovery drums) shall be available on-site.
7. Minor spills of such substances that may be contained on land with no significant impact on the environment may be responded to with in-house resources without formal notification to Manitoba Environment.

8. City emergency response, 9-1-1, shall be used if other means are not available.
9. The on-site emergency response coordinator shall contact The Canadian Coast Guard, Selkirk (204) 785-6030, if the spill material reaches and is on or in the Red or Assiniboine Rivers.

**Table 1 Spills that must be reported to the Manitoba Conservation as Environmental Accidents**

<u>Classification</u>	<u>Hazard</u>	<u>Reportable Quantity/Level</u>
1	Explosives	All
2.1	Compressed Gas (flammable)	100 L*
2.2	Compressed Gas	100 L*
2.3	Compressed Gas (toxic)	All
2.4	Compressed Gas (corrosive)	All
3	Flammable Liquids	100 L
4	Flammable Solids	1 kg
5.1	PG** I & II	Oxidizer
	PG III	Oxidizer
5.2	Organic Peroxide	1 kg or 1 L
6.1	PG I	Acute Toxic
	PG II & III	Acute Toxic
6.2	Infectious	All
7	Radioactive	Any discharge or radiation level exceeding 10 mSv/h at the package surface and 200 uSv/h at 1 m from the package surface
8	Corrosive	5 kg or 5 L
9.1	Miscellaneous	50 kg (except PCB mixtures)
9.1	PCB Mixtures	500 g
9.2	Aquatic Toxic	1 kg or 1 L
9.3	Wastes (Chronic Toxic)	5 kg or 5 L

\* Container capacity (refers to container water capacity)

\*\* PG = Packing Group(s)

**F. Vegetation**

1. Vegetation shall not be distributed without written permission of the Contract Administrator. The Contractor shall protect plants or trees which may be at risk of accidental damage. Such measures may include protective fencing or signage and shall be approved in advance by the Contractor Administrator.
2. Trees damaged during construction activities shall be examined by bonded tree care professionals; viable trees damaged during construction activities shall be pruned according to good practise by bonded tree care professionals. Damaged trees which are not viable shall be replaced at the expense of the Contractor.
3. Trees identified to be at risk by the Contract Administrator are to be strapped with 25 x 100 x 2400 millimetre wood planks, or suitably protected as approved by the Contract Administrator.

4. Herbicides and pesticides shall not be used adjacent to any surface watercourses.
5. All landowners adjacent to the area of application of herbicides or pesticides shall be notified prior to the Work.
6. Trees or shrubs shall not be felled into watercourses.
7. Areas where vegetation is removed during clearing, construction, and decommissioning activities, shall be revegetated as soon as possible in accordance with the landscaping plans forming part of the contract, or as directed by the Contract Administrator.

#### **G. Landscaping**

1. Restoration of boulevards requiring topsoil and sod.

#### **H. Red and Assiniboine Rivers Navigation Protection**

##### Dangerous Goods/Hazardous Waste Handling and Disposal

- (a) The Red and Assiniboine Rivers are open to navigation from approximately mid April to mid November, annually. During this period, it will be the responsibility of the Contractor to fully ensure the safety of river users.
- (b) The Contractor shall provide, install, and maintain adequate warning signs and lighting on any structure beyond the water's edge to notify boats and other craft navigating on the Assiniboine River that construction is underway. These warnings shall meet the requirements of the Winnipeg Rivers and Streams Authority Number One and of the Canadian Coast Guard.
- (c) Prior to commencing any applicable operations over the Red River, the Contractor shall provide to the Contract Administrator a copy of all necessary approvals received by the Contractor.

#### **E24. LEAN MIX CONCRETE**

##### E24.1 Description

- E24.1.1 All lean mix concrete work in this project, materials and construction methods, shall be according to the details in specification E25.

##### E24.2 Measurement and Payment

- E24.2.1 Lean mix concrete will be measured on a unit basis and payment shall be at the unit price for "Lean Mix Concrete".

#### **E25. CONSTRUCTION OF CONCRETE WEIR STRUCTURE**

##### E25.1 Description

- E25.1.1 This specification shall cover construction of cast-in-place concrete used in the construction of the concrete weir structure and shall supplement, revise and amend CW 2160.

##### E25.2 Materials

- (a) Concrete Mix Design
  - (i) Concrete mix design shall be as indicated in the Construction Notes on the Drawings.
- (b) Lean-Mix Concrete Design
  - (i) Proportioning of fine aggregate, coarse aggregate, cement, and water for lean mix concrete shall be as follows:

- Cement: Type MS
  - Minimum Compressive Strength @ 28 days: 7.5 MPa
  - Slump: 80 mm
  - Air Content: nil
  - Minimum Cement Content = 240 kg/m<sup>3</sup>
  - Maximum Water/Cement Ratio = 0.55
- (c) Grout
- (i) Grout shall be Sika Grout 212 or approved equal.
- (d) Reinforcing Steel
- (i) Bar accessories:
    - To be made from a non-corroding material.
    - Shall not stain, blemish or spall the concrete surface for the life of the concrete.
    - Shall be approved by the Contract Administrator.
    - Bar chairs shall be PVC.
- (e) Bonding Agent shall be ACRYL-STIX or approved equal.
- (f) Miscellaneous Metals and Accessories in accordance with E30 of this specification and as shown on the Drawings.
- (g) Shop Drawings
- (i) Provide shop drawings in accordance with E8 of this specification.
  - (ii) Submit shop drawings for reinforcing steel a minimum of one (1) week prior to the fabrication of any reinforcing steel.
- (h) Backfill
- (i) In accordance with CW 2030. Class of backfill to be as shown on the Drawings.

### E25.3 Construction Methods

#### E25.3.1 Construction Method Submission

- (a) No Work shall commence on construction of cast-in-place concrete until after the Contract Administrator's review of the Contractor's Construction Method submission.
- (b) Excavation for the construction of subsurface concrete shall be by the shored excavation method.
- (c) The Contractor shall prepare for the Contract Administrator's review a Construction Method submission detailing:
  - (i) Construction sequence to be followed including all methods to be employed to ensure no damage occurs to existing structures or adjacent properties within or adjacent to an excavation.
  - (ii) Shoring system to be used.
  - (iii) Proposed method of chamber construction.
  - (iv) Specialized equipment to be used.
  - (v) Any design revisions proposed to accommodate the Contractor's proposed construction method.
  - (vi) Water control considerations including details on the Contractor's proposed method of groundwater and surface runoff control.
- (d) The Contractor shall respond to any concerns that may be raised by the Contract Administrator after review of Construction Method submission.

#### E25.3.2 Cast in place Concrete Construction

- (a) Construct cast in place concrete in accordance with CW 2160, except as supplemented, revised or amended in this specification and as indicated in the construction notes on the Drawings.
- (b) Adjust the location of reinforcing steel adjacent to openings to frame those openings in accordance with good practice, and maintain the bar spacing intent.
- (c) Do not use welded splices for reinforcing steel.
- (d) Order all wall reinforcing steel in lengths to best suit the spacing of walers so that reinforcing bars will not be bent or misformed in order to remove the walers.
- (e) Install foundation waterproofing as specified on drawings.

#### E25.3.3 Backfill

- (a) Place and compact backfill material as indicated on the Drawings in accordance with CW 2030.
- (b) Do not place backfill material in a frozen state.
- (c) Supply heating and hoarding in accordance with CW 2160 if required to ensure material does not freeze before compaction is complete.
- (d) Notify the Contract Administrator at least one (1) full Working Day in advance of any backfilling operation. No Backfill shall be placed against concrete until approved by the Contract Administrator and in no case before field cured test cylinders show the concrete strength to be 75% of that specified.

#### E25.3.4 Grout

- (a) Mix and apply grout in accordance with the manufacturer's instructions. Consistency to be suitable for the intended application.

#### E25.3.5 Miscellaneous Metal Fabrications

- (a) Install miscellaneous metal fabrications as shown on the Drawings and in accordance with E28 of this specification.

#### E25.4 Measurement and Payment

- E25.4.1 Construction of cast-in-place concrete will be measured on a unit basis and paid for at the Contract Unit Price for "Cast-in-place Concrete". Said price shall be payment in full for supplying all materials and performing all operations herein described and all other items incidental to the Work included in this specification except installation of control gates supply and installation of miscellaneous metal and rehabilitation of existing slide gate which shall be paid for separately.

### **E26. EXCAVATION AND SHORING**

#### E26.1.1 Excavation

- (a) Remove excavated material from the Site immediately. Excavated material shall not be stockpiled on-site unless it will be used as backfill the same day it is excavated.
- (b) Place a minimum 50 millimetre thick lean mix concrete slab in the bottom of the excavation to provide a clean Working base upon completion of the excavation to the required limits.
- (c) Lean mix concrete shall be well-tamped and screed to give a level Working platform for setting up forms and placing reinforcing steel. Allow the concrete to set for twenty-four (24) hours before setting up forms or placing reinforcing steel.
- (d) Supply and place lean mix concrete, as directed by the Contract Administrator, as backfill for any portions of the excavation, carried beyond the required limits of excavation. The limits of excavation shall be considered to be the inside face of the shoring system and the underside of the Working base slab.

- (e) All Working areas below grade shall be kept adequately and securely supported during and after excavation until the shoring and bracing is in place to prevent loss of ground or injury to any person from falling material.

#### E26.1.2 Excavation Security Fence

- (a) Further to Clause 3.1 of CW 1130, completely cover the excavation and provide a security fence to completely surround the excavation when unattended generally in accordance with the following.
- (b) Security fence shall be chain link fence or approved equal, a minimum 1.80 metres high with metal support posts embedded far enough into the ground and spaced close enough together so the fence will not sag or collapse.
- (c) Attach fencing securely to posts.
- (d) Secure the gate or end of the fencing to a post with chain and a padlock.
- (e) Provide alternate security fence proposal to Contract Administrator for approval.

#### E26.1.3 Shoring

- (a) The type, strength, and amount of shoring and bracing shall be such as the nature of the ground and attendance conditions may require, taking into account property lines, existing slopes, utilities and roadways.
- (b) Shoring and bracing shall be so spaced and dimensioned as to prevent caving, loss of ground, surface settlement, or squeezing of the soil beyond the neat lines of excavation. It shall be free from defects that might impair its strength or suitability for the Work. Sheeting/shoring and bracing shall conform to the latest revisions of the "Construction Safety Act" of the Department of Labour of the Government of Manitoba.
- (c) Supporting design calculations as required to facilitate review of the submission for conformance with the Contract Documents.
- (d) Submit Shop Drawings and design calculations for the shoring/excavation system designed and sealed by a Professional Engineer registered or licensed to practice in the Province of Manitoba and experienced in the structural design of shoring systems. The designer of the shoring system shall inspect the system during construction and certify, in writing to the Contract Administrator, that construction is in conformance with the approved design.
- (e) Shoring and bracing shall be installed such that the structure size and wall thickness shown on the drawings can be obtained subsequent to installation of the shoring system.
- (f) Shoring and bracing shall remain in place until concrete has attained 75% of the design strength.

#### E26.2 Measurement and Payment

- E26.2.1 Excavation and shoring will be paid for at the contract unit price for "Excavation and Trench Shoring". Said price shall be payment in full for supplying all materials and performing all operations herein described and all other items incidental to the Work included in this specification.

### **E27. COLD WEATHER REQUIREMENTS**

#### E27.1 Description

- (a) Should any concrete Work be required to be carried out when the mean daily temperature is below 5 °C or anticipated to be below 5 °C within the next 24 hours, cold weather requirements will be specified herein.
- (b) All freshly placed concrete shall be protected from the elements and from defacements due to construction operations.

## E27.2 Construction Methods

- (a) The following are minimum requirements for protecting concrete during and after placement during freezing weather, but mere adherence to these requirements will not relieve the Contractor of the necessity for producing concrete which has not been weakened or injured by frost or freezing, or replacing such damaged Work at no additional expense to the City;
- (i) Before any concrete is placed, all ice, snow, and frost shall be completely removed from all formwork, and other surfaces against which concrete temperatures of such surfaces raised above 7°C for twenty-four (24) hours minimum prior to concreting. Where concrete Work is to come in contact with the earth, the surface of the earth shall be completely free of frost when concrete is placed thereon.
  - (ii) Concrete aggregates and water shall be heated to not over 80°C. Concrete shall be not less than 20°C or more than 30°C in temperature when deposited. Concrete when placed during freezing weather, or if freezing is anticipated during curing period, shall be fully enclosed and the temperature of same maintained at not less than 20°C for five (5) days nor less than 5°C for an additional five (5) days.
  - (iii) Heating enclosures shall be strong and wind-proof, well ventilated with heating units so located as to prevent local overheating or drying of the concrete or damage from combustion gases. Only indirect fired heaters will be accepted. Units must be vented outside the enclosure. No direct fired units will be accepted.
  - (iv) The Contractor shall inform the Contract Administrator well in advance as to the methods of enclosure and frost protection he proposes to employ.

## E27.3 Measurement and Payment

- E27.3.1 Cold weather requirements shall be considered incidental to the the construction of cast-in-place concrete and no measurement or payment will be made for this item.

## E28. METAL FABRICATIONS

### E28.1 Description

#### E28.1.1 General

- (a) This Specification shall cover the supply, fabrication, transportation, handling, delivery and placement of metal fabrications.

### E28.2 Materials

- E28.2.1 All materials shall be of a type acceptable to the Contract Administrator, and shall be subject to inspection and testing by the Contractor Administrator.
- E28.2.2 Material intended for use in the various assemblies shall be new, straight, clean, with sharply defined profiles.
- E28.2.3 Steel Sections and Plates: to CAN/CSA G40.20/G40.21, Grade 300 W, except W, HP and HSS sections, which shall be Grade 350 W.
- E28.2.4 Steel Pipe: to ASTM A53/A53M, seamless, galvanized, as specified by item.
- E28.2.5 Welding materials: to CSA W59.
- E28.2.6 Hot dipped galvanized steel repair material: Galvalloy and Gal-Viz
- E28.2.7 Stud Anchors: to ASTM A108, Grade 1020.
- E28.2.8 Aluminum: to CAN/CSA S157 and the Aluminum Association 'Specifications for Aluminum Structures'. Aluminum for plates shall be Type 6061-T651. Aluminium plate shall have an approved raised oval or multi-grip pattern.

- E28.2.9 Isolating sleeves shall be “Nylite” – headed sleeve as manufactured by SPAE-Naur of Kitchener, Ontario, or approved equal.
- E28.2.10 Anchor bolts and fasteners: ASTM A276, Type 316 stainless steel, of ample section to safely withstand the forces created by operation of the equipment or the load to which they will be subjected.
- E28.3 Construction Methods
- E28.3.1 Submittals
- (a) The Contractor shall submit the qualifications of the fabricator and welders to the Contractor Administrator for acceptance. Submit shop drawings in accordance with E8 clearly indicating materials, core thickness, finishes, connections, joints, method of anchorage, number of anchors, supports, reinforcement, details and, accessories. Indicate field measurements on shop drawings.
- E28.3.2 Fabrication
- (a) Fabricate Work square, true, straight and accurate to required size, with joints closely fitted and properly secured. Assemble Work in such a way that no disfigurements will show in the finished Work, or impair the strength.
- (b) Confirm measurements for all fabrications before fabricating.
- (c) Cut aluminium plate with edges straight and true, and as far as practical, maintain continuity of the pattern at abutting edges.
- (d) Pieces shall be of the sizes indicated on the Drawings and shall not be built up from scrap pieces. Confirm sizes with field measurements.
- (e) Where possible, fit Work and shop assemble, ready for erection.
- (f) Angle frames shall be of the same material as the cover plate (except for existing frames designated on the drawings for re-use), and cover plates shall be hinged and be supplied with lifting handles, as shown on the Drawings. Exterior covers shall be supplied with a hasp for a padlock.
- (g) Remove and grind smooth burrs, filings, sharp protrusions, and projections from metal fabrications to prevent possible injury. Correct any dangerous or potentially harmful installations as directed by Contract Administrator.
- (h) All steel welding shall conform to CSA Standard W.59. Fabricator shall be fully approved by the Canadian Welding Bureau, in conformance with CSA Standard W.47.1. Welding shall be done by currently licensed welders only.
- (i) All aluminum welding shall be in accordance with the requirements of CSA W59.2. The fabricator shall be fully certified in conformance with CSA Standard W47.2. All welding shall be done in a licensed welding shop, and no field welding will be permitted unless approved in writing, in advance, by the Contract Administrator.
- (j) Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush.
- (k) All steel shall be hot-dip galvanizing after fabrication, in accordance with CAN/CSAG164, to a minimum net retention of 600 gm/m<sup>2</sup>.
- (l) Seal exterior steel fabrications to provide corrosion protection in accordance with CAN3-S16.1.
- (m) Use self-tapping shake-proof flat-headed screws on items requiring assembly by screws.
- E28.3.3 Erection
- (a) Do steel welding Work in accordance with CSA W59 and aluminum welding Work in accordance with CSA W59.2
- (b) Erect metal Work in accordance with reviewed shop drawings, square, plumb, straight, and true, accurately fitted, with tight joints and intersections.

- (c) Provide suitable means of anchorage acceptable to Contract Administrator such as dowels, anchor clips, bar anchors, expansion bolts and shields, and toggles where not specifically indicated on the Drawings.
- (d) Provide components for building in accordance with shop drawings and schedule.
- (e) Make field connections with bolts to CAN/CSA-S16, or weld.
- (f) Touch-up rivets, bolts and burnt or scratched surfaces that are to receive paint finish, with zinc primer after completion of erection.
- (g) Repair damaged galvanized surfaces and field welds with self-fluxing, low temperature, zinc-based alloy rods in accordance with ASTM A780, Repair of Damaged Hot Dip Galvanizing Coatings. The general procedure shall be to allow a small amount of the repair alloy to flow then spread by brushing briskly with a wire brush. Brushing shall be sufficient to obtain a bright finish. Repeat process three times to ensure a proper thickness is achieved. Temperatures shall be kept below 177°C (350°F) at all times. All heating of structural steel. Work shall be done in the presence of the Contract Administrator.
- (h) Install access hatch frames square and level at the locations show on the Drawings. Embed anchors in concrete as shown on the Drawings. Install covers and adjust hardware to proper function.
- (i) All aluminum surfaces in contact with concrete shall be isolated using alkali resistant bituminous paint meeting the requirements of CGSB 31-GP-3M.
- (j) Install electrochemical isolation gaskets and sleeves to electrically isolate dissimilar metals.

#### E28.4 Measurement and Payment

- E28.4.1 Supply, fabrication, transportation, handling, delivery and placement of metal fabrications will be paid for at the Contract Unit Price for "Supply and Installation of Miscellaneous Metals".

### **E29. CLEANING EXISTING CONCRETE STORM PIPE**

- E29.1 The existing 2.4 metre diameter concrete pipe from the gate chamber north of River Avenue downstream to the location of the proposed weir structure (approximately 114.2 m long, 2400 mm dia.) is clogged with sediments and waste material. The consistency of the material is semi solid with a high liquid content. Three test holes were drilled and cored into the pipe and the resulting information has been used to develop a profile along the length of the pipe, indicating the depth of material found in the pipe as shown on Drawing xxx. The Contractor shall clean the section of pipe between the gate chamber and the proposed weir structure of all debris, waste and sediments and shall dispose of all material off site at a location approved by the Contract Administrator. The Contractor shall repair the holes cored into the top of the pipe during the test drilling to the satisfaction of the Contract Administrator. At the pre-construction meeting, the successful bidder shall submit his proposed methodology for cleaning the pipe and disposing of the waste material. This Work shall be measured on a per cubic metre basis and paid at the unit price for the item "Cleaning Existing Concrete Storm Pipe". Repair of the cored holes shall be considered incidental to the Work and no separate payment will be made.

### **E30. ACCESS ROAD CONSTRUCTION**

- E30.1 The access road shall be constructed to the lines and grades shown on the Drawings. Work shall be in accordance with and shall be measured and paid for in accordance with CW 3110 R7.

### **E31. SITE INSTRUMENTATION**

- E31.1 The Contractor is advised that geotechnical instrumentation will be installed by a drilling contractor concurrently with this contract. The costs for the instrumentation will be paid for under the item "Allowance for Site Instrumentation". The Contractor shall make an allowance in his schedule for co-ordinating his Work with, and maintaining access for, the forces of the Contract Administrator and a drilling contractor. The geotechnical instrumentation referred to in this specification is separate from any instrumentation the Contractor may install for monitoring movement of trench shoring Work. The Work is anticipated to take approximately 1 day. No extra payment will be made for the co-ordination or access requirements describe above.