



**THE CITY OF WINNIPEG**

# **BID OPPORTUNITY**

**91-2007 BID OPPORTUNITY**

**2007 ALLEY RENEWAL PROGRAM**

## TABLE OF CONTENTS

### PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	4
Form G1: Bid Bond and Agreement to Bond	16
Form G2: Irrevocable Standby Letter of Credit and Undertaking	18

### PART B - BIDDING PROCEDURES

B1. Contract Title	1
B2. Submission Deadline	1
B3. Enquiries	1
B4. Addenda	1
B5. Substitutes	1
B6. Bid Components	2
B7. Bid	3
B8. Prices	4
B9. Qualification	4
B10. Bid Security	5
B11. Opening of Bids and Release of Information	6
B12. Irrevocable Bid	6
B13. Withdrawal of Bids	6
B14. Evaluation of Bids	7
B15. Award of Contract	7

### PART C - GENERAL CONDITIONS

C0. General Conditions	1
------------------------	---

### PART D - SUPPLEMENTAL CONDITIONS

#### General

D1. General Conditions	1
D2. Scope of Work	1
D3. Contract Administrator	1
D4. Contractor's Supervisor	2
D5. Notices	2
D6. Furnishing of Documents	2

#### Submissions

D7. Authority to Carry on Business	2
D8. Safe Work Plan	3
D9. Insurance	3
D10. Performance Security	3
D11. Subcontractor List	4
D12. Detailed Work Schedule	4

#### Schedule of Work

D13. Commencement	4
D14. Working Days	4
D15. Restricted Work Hours	5
D16. Work By Others	5
D17. Sequence of Work	5
D18. Substantial Performance	5
D19. Total Performance	5
D20. Liquidated Damages	6
D21. Scheduled Maintenance	6

#### Control of Work

D22. Job Meetings	6
-------------------	---

D23. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	6
<b>Warranty</b>	
D24. Warranty	7
Form H1: Performance Bond	8
Form H2: Irrevocable Standby Letter of Credit	10
Form J: Subcontractor List	12
Form L: Detailed Work Schedule	13

## **PART E - SPECIFICATIONS**

### **General**

E1. Applicable Specifications and Drawings	1
E2. Geotechnical Report	1
E3. Protection Of Existing Trees	2
E4. Traffic Control	2
E5. Traffic Management	2
E6. Refuse and Recycling Collection	3
E7. Water Used By Contractor	3
E8. Surface Restorations	3
E9. Supply and Installation of Geotextile fabrics	4
E10. Supply and Installation of Geogrid	4
E11. Fence Removal and Restoration	5
E12. Installation of Subdrains	6
E13. Recycled Concrete Base Course Material	6

### **Appendix 'A' - Geotechnical Report**

## **PART B - BIDDING PROCEDURES**

### **B1. CONTRACT TITLE**

B1.1 2007 Alley Renewal Program

### **B2. SUBMISSION DEADLINE**

B2.1 The Submission Deadline is 12:00 noon Winnipeg time, February 22<sup>nd</sup> 2007.

B2.2 Bids determined by the Manager of Materials to have been received later than the Submission Deadline will not be accepted and will be returned upon request.

B2.3 The Contract Administrator or the Manager of Materials may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

### **B3. ENQUIRIES**

B3.1 All enquiries shall be directed to the Contract Administrator identified in D3.1.

B3.2 If the Bidder finds errors, discrepancies or omissions in the Bid Opportunity, or is unsure of the meaning or intent of any provision therein, the Bidder shall notify the Contract Administrator of the error, discrepancy or omission, or request a clarification as to the meaning or intent of the provision at least five (5) Business Days prior to the Submission Deadline.

B3.3 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator to all Bidders by issuing an addendum.

B3.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator only to the Bidder who made the enquiry.

B3.5 The Bidder shall not be entitled to rely on any response or interpretation received pursuant to B3 unless that response or interpretation is provided by the Contract Administrator in writing.

### **B4. ADDENDA**

B4.1 The Contract Administrator may, at any time prior to the Submission deadline, issue addenda correcting errors, discrepancies or omissions in the Bid Opportunity, or clarifying the meaning or intent of any provision therein.

B4.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.

B4.2.1 Addenda will be available on the Bid Opportunities page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

B4.2.2 The Bidder is responsible for ensuring that he has received all addenda and is advised to check the Materials Management Branch internet website for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.

B4.3 The Bidder shall acknowledge receipt of each addendum in Paragraph 10 of Form A: Bid. Failure to acknowledge receipt of an addendum may render a Bid non-responsive.

### **B5. SUBSTITUTES**

B5.1 The Work is based on the Plant, Materials and methods specified in the Bid Opportunity.

- B5.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.
- B5.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.
- B5.4 The Bidder shall ensure that any and all requests for approval of a substitute:
- (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative;
  - (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
  - (c) identify any anticipated cost or time savings that may be associated with the substitute;
  - (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance;
  - (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance.
- B5.5 The Contract Administrator, after assessing the request for approval of a substitute, may in his sole discretion grant approval for the use of a substitute as an “approved equal” or as an “approved alternative”, or may refuse to grant approval of the substitute.
- B5.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, only to the Bidder who requested approval of the substitute.
- B5.6.1 The Bidder requesting and obtaining the approval of a substitute shall be entirely responsible for disseminating information regarding the approval to any person or persons he wishes to inform.
- B5.7 If the Contract Administrator approves a substitute as an “approved equal”, any Bidder may use the approved equal in place of the specified item.
- B5.8 If the Contract Administrator approves a substitute as an “approved alternative”, any Bidder bidding that approved alternative may base his Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B14.
- B5.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.

## **B6. BID COMPONENTS**

- B6.1 The Bid shall consist of the following components:
- (a) Form A: Bid;
  - (b) Form B: Prices, hard copy;
  - (c) Form G1: Bid Bond and Agreement to Bond, or  
Form G2: Irrevocable Standby Letter of Credit and Undertaking, or  
a certified cheque or draft.

- B6.2 Further to B6.1, the Bidder should include the written correspondence from the Contract Administrator approving a substitute in accordance with B5.
- B6.3 All components of the Bid shall be fully completed or provided, and submitted by the Bidder no later than the Submission Deadline, with all required entries made clearly and completely, to constitute a responsive Bid.
- B6.4 The Bid shall be submitted enclosed and sealed in an envelope clearly marked with the Bid Opportunity number and the Bidder's name and address.
- B6.4.1 Samples or other components of the Bid which cannot reasonably be enclosed in the envelope may be packaged separately, but shall be clearly marked with the Bid Opportunity number, the Bidder's name and address, and an indication that the contents are part of the Bidder's Bid.
- B6.4.2 A hard copy of Form B: Prices must be submitted with the Bid. If there is any discrepancy between the Adobe PDF version of Form B: Prices and the Microsoft Excel version of Form B: Prices, the PDF version shall take precedence.
- B6.5 Bidders are advised not to include any information/literature except as requested in accordance with B6.1.
- B6.6 Bidders are advised that inclusion of terms and conditions inconsistent with the Bid Opportunity document, including the General Conditions, may result in the Bid being determined to be non-responsive.
- B6.7 Bids submitted by facsimile transmission (fax) or internet electronic mail (e-mail) will not be accepted.
- B6.8 Bids shall be submitted to:  
The City of Winnipeg  
Corporate Finance Department  
Materials Management Branch  
185 King Street, Main Floor  
Winnipeg MB R3B 1J1

**B7. BID**

- B7.1 The Bidder shall complete Form A: Bid, making all required entries.
- B7.2 Paragraph 2 of Form A: Bid shall be completed in accordance with the following requirements:
- (a) if the Bidder is a sole proprietor carrying on business in his own name, his name shall be inserted;
  - (b) if the Bidder is a partnership, the full name of the partnership shall be inserted;
  - (c) if the Bidder is a corporation, the full name of the corporation shall be inserted;
  - (d) if the Bidder is carrying on business under a name other than his own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.
- B7.2.1 If a Bid is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B7.2.
- B7.3 In Paragraph 3 of Form A: Bid, the Bidder shall identify a contact person who is authorized to represent the Bidder for purposes of the Bid.
- B7.4 Paragraph 12 of Form A: Bid shall be signed in accordance with the following requirements:
- (a) if the Bidder is a sole proprietor carrying on business in his own name, it shall be signed by the Bidder;

- (b) if the Bidder is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
- (c) if the Bidder is a corporation, it shall be signed by its duly authorized officer or officers and the corporate seal, if the corporation has one, shall be affixed;
- (d) if the Bidder is carrying on business under a name other than his own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.

B7.4.1 The name and official capacity of all individuals signing Form A: Bid shall be printed below such signatures.

B7.4.2 All signatures should be witnessed, except where a corporate seal has been affixed.

B7.5 If a Bid is submitted jointly by two or more persons, the word "Bidder" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Bidders in the Bid and the Contract, when awarded, shall be both joint and several.

## **B8. PRICES**

B8.1 The Bidder shall state a price in Canadian funds for each item of the Work identified on Form B: Prices.

B8.1.1 For the convenience of Bidders, and pursuant to B6.4.2 and B14.4.2, an electronic spreadsheet Form B: Prices in Microsoft Excel (.xls) format is available along with the Adobe PDF documents for this Bid Opportunity on the Bid Opportunities page at the Materials Management Branch internet website at <http://www.winnipeg.ca/matmgt>.

B8.2 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Bids.

B8.3 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.

## **B9. QUALIFICATION**

B9.1 The Bidder shall:

- (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba; and
- (b) be financially capable of carrying out the terms of the Contract; and
- (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.

B9.2 The Bidder and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:

- (a) be responsible and not be suspended, debarred or in default of any obligations to the City (a list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>); and
- (b) have successfully carried out work similar in nature, scope and value to the Work; and
- (c) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract; and
- (d) have a written workplace safety and health program if required pursuant to The Workplace Safety and Health Act (Manitoba).

- B9.3 Further to B9.2(d), the Bidder shall, within three (3) Business Days of a request by the Contract Administrator, provide proof satisfactory to the Contract Administrator that the Bidder/Subcontractor has a workplace safety and health program meeting the requirements of The Workplace Safety and Health Act (Manitoba), by providing:
- (a) a valid COR certification number under the Certificate of Recognition (COR) Program administered by the Manitoba Construction Safety Association or by the Manitoba Heavy Construction Association's Safety, Health and Environment Program; or
  - (b) a report or letter to that effect from an independent reviewer acceptable to the City. (A list of acceptable reviewers and the review template are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt.>)
- B9.4 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.
- B9.5 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

## **B10. BID SECURITY**

- B10.1 The Bidder shall provide bid security in the form of:
- (a) a bid bond, in the amount of at least ten percent (10%) of the Total Bid Price, and agreement to bond of a company registered to conduct the business of a surety in Manitoba, in the form included in the Bid Submission (Form G1: Bid Bond and Agreement to Bond); or
  - (b) an irrevocable standby letter of credit, in the amount of at least ten percent (10%) of the Total Bid Price, and undertaking issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form included in the Bid Submission (Form G2: Irrevocable Standby Letter of Credit and Undertaking); or
  - (c) a certified cheque or draft payable to "The City of Winnipeg", in the amount of at least fifty percent (50%) of the Total Bid Price, drawn on a bank or other financial institution registered to conduct business in Manitoba.
- B10.1.1 If the Bidder submits alternative bids, the bid security shall be in the amount of the specified percentage of the highest Total Bid Price submitted.
- B10.1.2 All signatures on bid securities shall be original, and shall be witnessed or sealed as required.
- B10.2 The bid security of the successful Bidder and the next two lowest evaluated responsive and responsible Bidders will be released by the City when a Contract for the Work has been duly executed by the successful Bidder and the performance security furnished as provided herein. The bid securities of all other Bidders will be released when a Contract is awarded.
- B10.2.1 Where the bid security provided by the successful Bidder is in the form of a certified cheque or draft pursuant to B10.1(c), it will be deposited and retained by the City as the performance security and no further submission is required.
- B10.2.2 The City will not pay any interest on certified cheques or drafts furnished as bid security or subsequently retained as performance security.
- B10.3 The bid securities of all Bidders will be released by the City as soon as practicable following notification by the Contract Administrator to the Bidders that no award of Contract will be made pursuant to the Bid Opportunity.

## **B11. OPENING OF BIDS AND RELEASE OF INFORMATION**

B11.1 Bids will be opened publicly, after the Submission Deadline has elapsed, in the office of the Corporate Finance Department, Materials Management Branch, or in such other office as may be designated by the Manager of Materials.

B11.1.1 Bidders or their representatives may attend.

B11.1.2 Bids determined by the Manager of Materials, or his designate, to not include the bid security specified in B10 will not be read out.

B11.2 Following the submission deadline, the names of the Bidders and their Total Bid Prices (unevaluated, and pending review and verification of conformance with requirements) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

B11.3 After award of Contract, the name(s) of the successful Bidder(s) and the Contract Amount(s) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

B11.4 The Bidder is advised that any information contained in any Bid may be released if required by City policy or procedures, by The Freedom of Information and Protection of Privacy Act (Manitoba), by other authorities having jurisdiction, or by law.

## **B12. IRREVOCABLE BID**

B12.1 The Bid(s) submitted by the Bidder shall be irrevocable for the time period specified in Paragraph 11 of Form A: Bid.

B12.2 The acceptance by the City of any Bid shall not release the Bids of the next two lowest evaluated responsive Bidders and these Bidders shall be bound by their Bids on such Work until a Contract for the Work has been duly executed and the performance security furnished as herein provided, but any Bid shall be deemed to have lapsed unless accepted within the time period specified in Paragraph 11 of Form A: Bid.

## **B13. WITHDRAWAL OF BIDS**

B13.1 A Bidder may withdraw his Bid without penalty by giving written notice to the Manager of Materials at any time prior to the Submission Deadline.

B13.1.1 Notwithstanding C23.3, the time and date of receipt of any notice withdrawing a Bid shall be the time and date of receipt as determined by the Manager of Materials.

B13.1.2 The City will assume that any one of the contact persons named in Paragraph 3 of Form A: Bid or the Bidder's authorized representatives named in Paragraph 12 of Form A: Bid, and only such person, has authority to give notice of withdrawal.

B13.1.3 If a Bidder gives notice of withdrawal prior to the Submission Deadline, the Manager of Materials will:

- (a) retain the Bid until after the Submission Deadline has elapsed;
- (b) open the Bid to identify the contact person named in Paragraph 3 of Form A: Bid and the Bidder's authorized representatives named in Paragraph 12 of Form A: Bid; and
- (c) if the notice has been given by any one of the persons specified in B13.1.3(b), declare the Bid withdrawn.

B13.2 A Bidder who withdraws his Bid after the Submission Deadline but before his Bid has been released or has lapsed as provided for in B12.2 shall be liable for such damages as are imposed upon the Bidder by law and subject to such sanctions as the Chief Administrative

Officer considers appropriate in the circumstances. The City, in such event, shall be entitled to all rights and remedies available to it at law, including the right to retain the Bidder's bid security.

#### **B14. EVALUATION OF BIDS**

B14.1 Award of the Contract shall be based on the following bid evaluation criteria:

- (a) compliance by the Bidder with the requirements of the Bid Opportunity (pass/fail);
- (b) qualifications of the Bidder and the Subcontractors, if any, pursuant to B9 (pass/fail);
- (c) Total Bid Price;
- (d) economic analysis of any approved alternative pursuant to B5.

B14.2 Further to B14.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities, if the interests of the City so require.

B14.3 Further to B14.1(b), the Award Authority shall reject any Bid submitted by a Bidder who does not demonstrate, in his Bid or in other information required to be submitted, that he is responsible and qualified.

B14.4 Further to B14.1(c), the Total Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.

B14.4.1 If there is any discrepancy between the Total Bid Price written in figures, the Total Bid Price written in words and the sum of the quantities multiplied by the unit prices for each item, the sum of the quantities multiplied by the unit prices for each item shall take precedence.

B14.4.2 The electronic Form B: Prices and the formulas imbedded in that spreadsheet are only provided for the convenience of Bidders. The City makes no representations or warranties as to the correctness of the imbedded formulas. It is the Bidder's responsibility to ensure the extensions of the unit prices and the sum of Total Bid Price performed as a function of the formulas within the electronic Form B: Prices are correct.

#### **B15. AWARD OF CONTRACT**

B15.1 The City will give notice of the award of the Contract or will give notice that no award will be made.

B15.2 The City will have no obligation to award a Contract to a Bidder, even though one or all of the Bidders are determined to be responsible and qualified, and the Bids are determined to be responsive.

B15.2.1 Without limiting the generality of B15.2, the City will have no obligation to award a Contract where:

- (a) the prices exceed the available City funds for the Work;
- (b) the prices are materially in excess of the prices received for similar work in the past;
- (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with its own forces;
- (d) only one Bid is received; or
- (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.

B15.3 Subject to B15.2, where an award of Contract is made by the City, the award shall be made to the responsible and qualified Bidder submitting the lowest evaluated responsive Bid.

**B15.3.1** Following the award of contract, a Bidder will be provided with information related to the evaluation of his Bid upon written request to the Contract Administrator.

## **PART C - GENERAL CONDITIONS**

### **C0. GENERAL CONDITIONS**

- C0.1 The *General Conditions for Construction* (Revision 2006 12 15) are applicable to the Work of the Contract.
- C0.1.1 The *General Conditions for Construction* are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.
- C0.2 A reference in the Bid Opportunity to a section, clause or subclause with the prefix “**C**” designates a section, clause or subclause in the *General Conditions for Construction*.

## **PART D - SUPPLEMENTAL CONDITIONS**

### **GENERAL**

#### **D1. GENERAL CONDITIONS**

D1.1 In addition to the General Conditions for Construction, these Supplemental Conditions are applicable to the Work of the Contract.

#### **D2. SCOPE OF WORK**

D2.1 The Work to be done under the Contract shall consist of:

(a) Pavement Reconstruction

- (i) Ethelbert St. / Canora St. Alley from the Wolseley Ave. North Alley to the Westminster Ave. South Alley; the Woseley Ave. North Alley from Ethelbert St. to Canora St.; and the Westminster Ave. South Alley from Ethelbert St. to Canora St. (Concrete).
- (ii) Hargrave St. / Donald St. Alley from Assiniboine Ave. to Hargrave Pl. (Concrete).
- (iii) McAdam Ave. / Matheson Ave. Alley from Powers St. to Salter St. (Concrete)
- (iv) Yale Ave. / Grosvenor Ave. Alley from Rockwood St. to Wilton St. (Concrete)

D2.2 The major components of the Work are as follows:

(a) Pavement Reconstruction

- (i) Removal of existing pavement
- (ii) Excavation
- (iii) Installation of catchbasins, manholes and drainage connection pipe
- (iv) Installation of subdrains
- (v) Compaction of existing subgrade
- (vi) Placement of separation / reinforcement fabric
- (vii) Placement of geogrid
- (viii) Placement of sub-base and base course material
- (ix) Adjustment of existing catchbasins and inlets
- (x) Construction of 150mm concrete pavement (reinforced)
- (xi) Installation of lip curb, modified curb and curb ramp.
- (xii) Renewal of existing sidewalk
- (xiii) Restoration of adjacent surfaces
- (xiv) Restoration of boulevards

#### **D3. CONTRACT ADMINISTRATOR**

D3.1 The Contract Administrator is KGS Group, represented by:

Roy Houston, P.Eng.  
Manager of Civil / Municipal Services  
3<sup>rd</sup> Floor – 865 Waverley Street

Telephone No. (204) 896-1209  
Facsimile No. (204) 896-0754

D3.2 At the pre-construction meeting, Roy Houston, P.Eng. will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

#### **D4. CONTRACTOR'S SUPERVISOR**

- D4.1 At the pre-construction meeting, the Contractor shall identify his designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.
- D4.2 At least two (2) business days prior to the commencement of any Work on the site, the Contractor shall provide the Contract Administrator with a phone number where the supervisor identified in D4.1 or an alternate can be contacted 24 hours a day to respond to an emergency.

#### **D5. NOTICES**

- D5.1 Except as provided for in C23.2.2, all notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the Contractor shall be sent to the address or facsimile number identified by the Contractor in Paragraph 2 of Form A: Bid.
- D5.2 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the City, except as expressly otherwise required in D5.3, D5.4 or elsewhere in the Contract, shall be sent to the attention of the Contract Administrator at the address or facsimile number identified in D3.1.
- D5.3 All notices of appeal to the Chief Administrative Officer shall be sent to the following address or facsimile number:  
The City of Winnipeg  
Chief Administrative Officer Secretariat  
Attn: Chief Administrative Officer  
Administration Building, 3rd Floor  
510 Main Street  
Winnipeg MB R3B 1B9  
Facsimile No.: (204) 949-1174
- D5.4 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications required to be submitted or returned to the City Solicitor shall be sent to the following address or facsimile number:  
The City of Winnipeg  
Corporate Services Department  
Legal Services Division  
Attn: City Solicitor  
185 King Street, 3rd Floor  
Winnipeg MB R3B 1J1  
Facsimile No.: (204) 947-9155

#### **D6. FURNISHING OF DOCUMENTS**

- D6.1 Upon award of the Contract, the Contractor will be provided with five (5) complete sets of the Bid Opportunity. If the Contractor requires additional sets of the Bid Opportunity, they will be supplied to him at cost.

#### **SUBMISSIONS**

#### **D7. AUTHORITY TO CARRY ON BUSINESS**

- D7.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on

business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

#### **D8. SAFE WORK PLAN**

- D8.1 The Contractor shall provide the Contract Administrator with a Safe Work Plan at least five (5) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.
- D8.2 The Safe Work Plan shall be prepared and submitted in the format shown in the City's template which is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.

#### **D9. INSURANCE**

- D9.1 The Contractor shall provide and maintain the following insurance coverage:
- (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg added as an additional insured, with a cross-liability clause, such liability policy to also contain a contractual liability, unlicensed motor vehicle liability, non-owned automobile liability and products and completed operations, to remain in place at all times during the performance of the Work and throughout the warranty period;
  - (b) automobile liability insurance for owned automobiles used for or in connection with the Work in the amount of at least two million dollars (\$2,000,000.00) at all times during the performance of the Work and until the date of Total Performance;
  - (c) an all risks Installation Floater carrying adequate limits to cover all machinery and equipment utilized during the performance of the Work.
- D9.2 Deductibles shall be borne by the Contractor.
- D9.3 The Contractor shall provide the City Solicitor with a certificate(s) of insurance, in a form satisfactory to the City Solicitor, at least two (2) Business Days prior to the commencement of any Work but in no event later than the date specified in the C4.1 for the return of the executed Contract.
- D9.4 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least fifteen (15) Calendar Days prior written notice to the Contract Administrator.

#### **D10. PERFORMANCE SECURITY**

- D10.1 The Contractor shall provide and maintain performance security until the expiration of the warranty period in the form of:
- (a) a performance bond of a company registered to conduct the business of a surety in Manitoba, in the form attached to these Supplemental Conditions (Form H1: Performance Bond), in the amount of fifty percent (50%) of the Contract Price; or
  - (b) an irrevocable standby letter of credit issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form attached to these Supplemental Conditions (Form H2: Irrevocable Standby Letter of Credit), in the amount of fifty percent (50%) of the Contract Price; or
  - (c) a certified cheque or draft payable to "The City of Winnipeg", drawn on a bank or other financial institution registered to conduct business in Manitoba, in the amount of fifty percent (50%) of the Contract Price.
- D10.1.1 Where the performance security is in the form of a certified cheque or draft, it will be deposited by the City. The City will not pay any interest on certified cheques or drafts furnished as performance security.

D10.2 If the bid security provided in his Bid was not a certified cheque or draft pursuant to B10.1(c), the Contractor shall provide the City Solicitor with the required performance security within seven (7) Calendar Days of notification of the award of the Contract by way of letter of intent and prior to the commencement of any Work on the Site and in no event later than the date specified in the C4.1 for the return of the executed Contract.

#### **D11. SUBCONTRACTOR LIST**

D11.1 The Contractor shall provide the Contract Administrator with a complete list of the Subcontractors whom the Contractor proposes to engage (Form J: Subcontractor List) at or prior to a pre-construction meeting, or at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in the C4.1 for the return of the executed Contract.

#### **D12. DETAILED WORK SCHEDULE**

D12.1 The Contractor shall provide the Contract Administrator with a detailed work schedule (Form L: Detailed Work Schedule) at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in the General Conditions for the return of the executed Contract.

### **SCHEDULE OF WORK**

#### **D13. COMMENCEMENT**

D13.1 The Contractor shall not commence any Work until he is in receipt of a letter of intent from the Award Authority authorizing the commencement of the Work.

D13.2 The Contractor shall not commence any Work on the Site until:

- (a) the Contract Administrator has confirmed receipt and approval of:
  - (i) evidence of authority to carry on business specified in D7;
  - (ii) evidence of the workers compensation coverage specified in C6.15;
  - (iii) the twenty-four (24) hour emergency response phone number specified in D4.2.
  - (iv) the Safe Work Plan specified in D8;
  - (v) evidence of the insurance specified in D9;
  - (vi) the performance security specified in D10;
  - (vii) the subcontractor list specified in D11; and
  - (viii) the detailed work schedule specified in D12.
- (b) the Contractor has attended a pre-construction meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a pre-construction meeting.

D13.3 The Contractor shall not commence the Work on the Site before May 14<sup>th</sup> 2007, and shall commence the Work on Site no later than May 28<sup>th</sup> 2007, as directed by the Contract Administrator and weather permitting.

#### **D14. WORKING DAYS**

D14.1 Further to C1.1(gg);

D14.1.1 The Contract Administrator will determine daily if a Working Day has elapsed and will record his assessment. On a weekly basis the Contract Administrator will provide the Contractor with a record of the Working Days assessed for the preceding week. The Contractor shall sign each report signifying that he agrees with the Contract Administrator's determination of the Working Days assessed for the report period.

D14.1.2 Work done to restore the Site to a condition suitable for Work, shall not be considered “work” as defined in the definition of a Working Day.

D14.1.3 When the Work includes two or more major types of Work that can be performed under different atmospheric conditions, the Contract Administrator shall consider all major types of Work in determining whether the Contractor was able to work in assessing Working Days.

#### **D15. RESTRICTED WORK HOURS**

D15.1 Further to clause 3.10 of CW 1130, the Contractor shall require written permission 48 hours in advance from the Contract Administrator for any work to be performed between 2000 hours and 0700 hours, or on Saturdays, Sundays, Statutory Holidays and or Civic Holidays.

#### **D16. WORK BY OTHERS**

D16.1 Work by others on or near the Site will include but not necessarily be limited to:

- (a) Manitoba Hydro Gas Division – Lowering and/or rock wrapping of underground gas mains and services, if required;
- (b) Manitoba Hydro – installing or protecting overhead street lighting cable, repair/relocation of underground services and adjustment of manholes/chambers, if required;
- (c) City of Winnipeg Geomatics Branch – various work on survey monuments, if required; and
- (d) City of Winnipeg Traffic Services Branch, if required.

#### **D17. SEQUENCE OF WORK**

D17.1 Further to C6.1, the sequence of work shall be as follows:

D17.1.1 The Contractor will be permitted to have a maximum of three (3) alleys under construction at any one time. Completion of an alley means that all of the necessary concrete and asphalt construction including approaches and landscaping Work is completed to the satisfaction of the Contract Administrator.

D17.1.2 Where the Contractor utilizes two (2) or more crews that work independently on the same major component of the Work as identified in D2, the Contract Administrator may approve an increase to the maximum number of alleys under construction at any time.

#### **D18. SUBSTANTIAL PERFORMANCE**

D18.1 The Contractor shall achieve Substantial Performance within fifty (50) consecutive Working Days of the commencement of the Work as specified in D13.

D18.2 When the Contractor considers the Work to be substantially performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Substantial Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be re-inspected.

D18.3 The date on which the Work has been certified by the Contract Administrator as being substantially performed to the requirements of the Contract through the issue of a certificate of Substantial Performance is the date on which Substantial Performance has been achieved.

#### **D19. TOTAL PERFORMANCE**

D19.1 The Contractor shall achieve Total Performance within fifty five (55) consecutive Working Days of the commencement of the Work as specified in D13.

D19.2 When the Contractor or the Contract Administrator considers the Work to be totally performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Total Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be re-inspected.

D19.3 The date on which the Work has been certified by the Contract Administrator as being totally performed to the requirements of the Contract through the issue of a certificate of Total Performance is the date on which Total Performance has been achieved.

## **D20. LIQUIDATED DAMAGES**

D20.1 If the Contractor fails to achieve Substantial Performance in accordance with the Contract by the day fixed herein for Substantial Performance, the Contractor shall pay the City one thousand two hundred dollars (\$1,200) per Working Day for each and every Working Day following the day fixed herein for Substantial Performance during which such failure continues.

D20.2 The amount specified for liquidated damages in D20.1 is based on a genuine pre-estimate of the City's damages in the event that the Contractor does not achieve Substantial Performance by the day fixed herein for same.

D20.3 The City may reduce any payment to the Contractor by the amount of any liquidated damages assessed.

## **D21. SCHEDULED MAINTENANCE**

D21.1 The Contractor shall perform the following scheduled maintenance in the manner and within the time periods required by the Specifications:

- (a) Sodding as specified in CW 3510;
- (b) Seeding as specified in CW 3520.

D21.2 Determination of Substantial Performance and Total Performance shall be exclusive of scheduled maintenance identified herein. All scheduled maintenance shall be completed prior to the expiration of the warranty period. Where the scheduled maintenance cannot be completed during the warranty period, the warranty period shall be extended for such period of time as it takes the Contractor to complete the scheduled maintenance.

## **CONTROL OF WORK**

### **D22. JOB MEETINGS**

D22.1 Regular weekly job meetings will be held at the Site. These meetings shall be attended by a minimum of one representative of the Contract Administrator, One representative of the City and one representative of the Contractor. Each representative shall be a responsible person capable of expressing the position of the Contract Administrator, the City and the Contractor respectively on any matter discussed at the meeting including the Work schedule and the need to make any revisions to the Work schedule. The progress of the Work will be reviewed at each of these meetings.

D22.2 The Contract Administrator reserves the right to cancel any job meeting or call additional job meetings whenever he deems it necessary.

### **D23. PRIME CONTRACTOR – THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA)**

D23.1 Further to C6.24, the Contractor shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

## **WARRANTY**

### **D24. WARRANTY**

- D24.1 Notwithstanding C13.2, the warranty period shall begin on the date of Total Performance and shall expire two (2) years thereafter unless extended pursuant to C13.2.1 or C13.2.2, in which case it shall expire when provided for thereunder.

**FORM H1: PERFORMANCE BOND**  
(See D10)

KNOW ALL MEN BY THESE PRESENTS THAT

\_\_\_\_\_ ,  
(hereinafter called the "Principal"), and

\_\_\_\_\_ ,  
(hereinafter called the "Surety"), are held and firmly bound unto **THE CITY OF WINNIPEG** (hereinafter called the "Obligee"), in the sum of

\_\_\_\_\_ dollars (\$\_\_\_\_\_)

of lawful money of Canada to be paid to the Obligee, or its successors or assigns, for the payment of which sum the Principal and the Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS the Principal has entered into a written contract with the Obligee dated the

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, for:

BID OPPORTUNITY NO. 91-2007

2007 Alley Renewal Program

which is by reference made part hereof and is hereinafter referred to as the "Contract".

NOW THEREFORE the condition of the above obligation is such that if the Principal shall:

- (a) carry out and perform the Contract and every part thereof in the manner and within the times set forth in the Contract and in accordance with the terms and conditions specified in the Contract;
- (b) perform the Work in a good, proper, workmanlike manner;
- (c) make all the payments whether to the Obligee or to others as therein provided;
- (d) in every other respect comply with the conditions and perform the covenants contained in the Contract; and
- (e) indemnify and save harmless the Obligee against and from all loss, costs, damages, claims, and demands of every description as set forth in the Contract, and from all penalties, assessments, claims, actions for loss, damages or compensation whether arising under "The Workers Compensation Act", or any other Act or otherwise arising out of or in any way connected with the performance or non-performance of the Contract or any part thereof during the term of the Contract and the warranty period provided for therein;

THEN THIS OBLIGATION SHALL BE VOID, but otherwise shall remain in full force and effect. The Surety shall not, however, be liable for a greater sum than the sum specified above.

AND IT IS HEREBY DECLARED AND AGREED that the Surety shall be liable as Principal, and that nothing of any kind or matter whatsoever that will not discharge the Principal shall operate as a discharge or release of liability of the Surety, any law or usage relating to the liability of Sureties to the contrary notwithstanding.

IN WITNESS WHEREOF the Principal and Surety have signed and sealed this bond the

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

SIGNED AND SEALED  
in the presence of:

\_\_\_\_\_  
(Witness)

\_\_\_\_\_  
(Name of Principal)

Per: \_\_\_\_\_ (Seal)

Per: \_\_\_\_\_

\_\_\_\_\_  
(Name of Surety)

By: \_\_\_\_\_ (Seal)  
(Attorney-in-Fact)

**FORM H2: IRREVOCABLE STANDBY LETTER OF CREDIT  
(PERFORMANCE SECURITY)**  
(See D10)

\_\_\_\_\_  
(Date)

The City of Winnipeg  
Corporate Services Department  
Legal Services Division  
185 King Street, 3rd Floor  
Winnipeg MB R3B 1J1

RE: PERFORMANCE SECURITY – BID OPPORTUNITY NO. 91-2007  
2007 Alley Renewal Program

Pursuant to the request of and for the account of our customer,

\_\_\_\_\_  
(Name of Contractor)

\_\_\_\_\_  
(Address of Contractor)

WE HEREBY ESTABLISH in your favour our irrevocable Standby Letter of Credit for a sum not exceeding in the aggregate

\_\_\_\_\_  
Canadian dollars.

This Standby Letter of Credit may be drawn on by you at any time and from time to time upon written demand for payment made upon us by you. It is understood that we are obligated under this Standby Letter of Credit for the payment of monies only and we hereby agree that we shall honour your demand for payment without inquiring whether you have a right as between yourself and our customer to make such demand and without recognizing any claim of our customer or objection by the customer to payment by us.

The amount of this Standby Letter of Credit may be reduced from time to time only by amounts drawn upon it by you or by formal notice in writing given to us by you if you desire such reduction or are willing that it be made.

Partial drawings are permitted.

We engage with you that all demands for payment made within the terms and currency of this Standby Letter of Credit will be duly honoured if presented to us at:

\_\_\_\_\_  
(Address)

and we confirm and hereby undertake to ensure that all demands for payment will be duly honoured by us.

All demands for payment shall specifically state that they are drawn under this Standby Letter of Credit.

Subject to the condition hereinafter set forth, this Standby Letter of Credit will expire on

\_\_\_\_\_  
(Date)

It is a condition of this Standby Letter of Credit that it shall be deemed to be automatically extended from year to year without amendment from the present or any future expiry date, unless at least 30 days prior to the present or any future expiry date, we notify you in writing that we elect not to consider this Standby Letter of Credit to be renewable for any additional period.

This Standby Letter of Credit may not be revoked or amended without your prior written approval.

This credit is subject to the Uniform Customs and Practice for Documentary Credit (1993 Revision), International Chamber of Commerce Publication Number 500.

\_\_\_\_\_  
(Name of bank or financial institution)

Per: \_\_\_\_\_  
(Authorized Signing Officer)

Per: \_\_\_\_\_  
(Authorized Signing Officer)

**FORM J: SUBCONTRACTOR LIST**  
(See D11)

2007 Alley Renewal Program

<u>Portion of the Work</u>	<u>Name</u>	<u>Address</u>
<b>SURFACE WORKS:</b>		
<u>Supply of Materials:</u>		
Concrete		
Asphalt		
Base Course & Sub-Base		
Sod/ Seed		
Geotextile Fabric		
Geogrid		
Interlocking Paving Stone		
<u>Installation/Placement:</u>		
Concrete		
Asphalt		
Sub-Base and Base Course		
<b>UNDERGROUND WORKS:</b>		
<u>Supply of Materials:</u>		
Catchbasin		
Catchbasins Frame and Cover		
Subdrain Pipe		
Connecting Pipe		
<u>Installation/Placement:</u>		
Catchbasins		
Subdrain Pipe		
Connecting Pipe		
<u>Others:</u>		

**FORM L: DETAILED WORK SCHEDULE**  
(See D12)

2007 Alley Renewal Program

For each item of Work, indicate the cumulative percentage proposed to be completed by the end of each time period until 100% completion is achieved.						
Items of Work	Time Period in Working Days					
	10	20	30	40	50	60
<b>Ethelbert St. / Canora St. Alley; the Woseley Ave. North; and the Westminster Ave. South Alley</b>						
Excavation						
Subbase & Base Construction						
Concrete Works						
Landscaping and Clean-Up						
<b>Hargrave St. / Donald St. Alley</b>						
Excavation						
Subbase & Base Construction						
Concrete Works						
Landscaping and Clean-Up						
<b>McAdam Ave. / Matheson Ave. Alley</b>						
Excavation						
Subbase & Base Construction						
Concrete Works						
Landscaping and Clean-Up						
<b>Yale Ave. / Grosvenor Ave. Alley</b>						
Excavation						
Subbase & Base Construction						
Concrete Works						
Landscaping and Clean-Up						

## PART E - SPECIFICATIONS

### GENERAL

#### E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

- E1.1 These Specifications shall apply to the Work.
- E1.2 *The City of Winnipeg Standard Construction Specifications* in its entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.
- E1.2.1 *The City of Winnipeg Standard Construction Specifications* is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Branch internet site at <http://www.winnipeg.ca/matmgt>.
- E1.2.2 The version in effect three (3) Business Days before the Submission Deadline shall apply.
- E1.2.3 Further to C2.4(d), Specifications included in the Bid Opportunity shall govern over *The City of Winnipeg Standard Construction Specifications*.
- E1.3 The following are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>	<u>Drawing (Original) Sheet Size</u>
00	Cover Sheet	A1
0001	Wolseley Ave. North Alley Ethelbert St. to Canora St. Sta. 0+93.53 to Sta 1+67.54	A1
0002	Ethelbert St./Canora St. Alley Wolseley Ave. North Alley to Westminster Ave. South Alley Sta. 0+96.94 to Sta. 2+10	A1
0003	Ethelbert St./Canora St. Alley Wolseley Ave. North Alley to Westminster Ave. South Alley Sta. 2+10 to Sta. 2+77.85	A1
0004	Westminster Ave. South Alley Ethelbert St. to Canora St. Sta. 0+91.33 to Sta. 1+76.35	A1
0005	Hargrave St./Donald St. Alley Assiniboine Ave. to Hargrave Pl. Sta 0+94.58 to Sta. 1+81.39	A1
0006	McAdam Ave. Matheson Ave. Alley Powers St. to Salter St. Sta. 0+93.68 to Sta. 2+10	A1
0007	McAdam Ave. Matheson Ave. Alley Powers St. to Salter St. Sta. 2+10 to Sta. 2+85.21	A1
0008	Yale Ave./Grosvenor Ave. Alley Rockwood St. to Wilton St. Sta. 0+93.68 to Sta. 2+10	A1
0009	Yale Ave./Grosvenor Ave. Alley Rockwood St. to Wilton St. Sta. 2+10 to Sta. 2+59.01	A1

#### E2. GEOTECHNICAL REPORT

- E2.1 Further to C3.1, the geotechnical report is provided to aid the Contractor's evaluation of the existing soil conditions. The geotechnical report is contained in Appendix 'A'.

### **E3. PROTECTION OF EXISTING TREES**

- E3.1 The Contractor shall take the following precautionary steps to prevent damage from construction activities to existing boulevard trees within the limits of the construction area:
- (a) The Contractor shall not stockpile materials and soil or park vehicles and equipment on boulevards within 2 metres of trees.
  - (b) Trees identified to be at risk by the Contract Administrator are to be strapped with 25 x 100 x 2400mm wood planks, or suitably protected as approved by the Contract Administrator.
  - (c) Excavation shall be performed in a manner that minimizes damage to the existing root systems. Where possible, excavation shall be carried out such that the edge of the excavation shall be a minimum of 1.5 times the diameter (measured in inches), with the outcome read in feet, from the closest edge of the trunk. Where roots must be cut to facilitate excavation, they shall be pruned neatly at the face of excavation.
  - (d) Operation of equipment within the dripline of the trees shall be kept to the minimum required to perform the work required. Equipment shall not be parked, repaired, refuelled; construction materials shall not be stored, and earth materials shall not be stockpiled within the driplines of trees. The dripline of a tree shall be considered to be the ground surface directly beneath the tips of its outermost branches. The Contractor shall ensure that the operations do not cause flooding or sediment deposition on areas where trees are located.
  - (e) Work on-site shall be carried out in such a manner so as to minimize damage to existing tree branches. Where damage to branches does occur, they shall be neatly pruned.
- E3.2 All damage to existing trees caused by the Contractor's activities shall be repaired to the requirements and satisfaction of the Contract Administrator and the City Forester or his designate.
- E3.3 No separate measurement or payment will be made for the protection of trees.
- E3.4 Elm trees cannot be trimmed between April 1 and July 31, inclusive.

### **E4. TRAFFIC CONTROL**

- E4.1 Further to clauses 3.6 and 3.7 of CW 1130-R1:
- (a) Where directed, the Contractor shall construct and maintain temporary asphalt ramps to alleviate vertical pavement obstructions such as manholes and planing drop-offs to the satisfaction of the Contract Administrator. No measurement for payment will be made for this work.
  - (b) In accordance with the Manual of Temporary Traffic Control, the Contractor ("Agency" in the manual) shall make arrangements with the Traffic Services Section of the City of Winnipeg to place all temporary regulatory signs. The Contractor shall bear all costs associated with the placement of temporary traffic control devices by the Traffic Services Section of the City of Winnipeg in connection with the works undertaken by the Contractor.

### **E5. TRAFFIC MANAGEMENT**

- E5.1 Further to clause 3.7 of CW 1130-R1:
- E5.1.1 Each alley shall be closed to traffic, according to specified phasing. The Contractor shall sign the alley "Alley Closed" in accordance with the Manual of Temporary Traffic Control.
  - E5.1.2 Intersecting street access shall be maintained at all times.
  - E5.1.3 The Contractor shall provide a minimum of 48 hours notification to the affected residence or business and the Contract Administrator, prior to disruption of access. The Contractor shall provide temporary access ramps, as practicable, to minimize the disruption of traffic to commercial properties affected by the construction activities according to the Sequence of Work as detailed in D17.

- E5.1.4 For each alley, construction shall be staged such that backfilling with sub-base material immediately follows excavation and underground works. Excavations shall be filled to the design top of sub-base elevations at the end of each working day.

## **E6. REFUSE AND RECYCLING COLLECTION**

- E6.1 While access to refuse and/or recycling collection vehicles is restricted, on collection day(s) the Contractor shall move all of the affected property owners refuse and/or recycling materials to a nearby common area, prior to an established time, in accordance with E6.2 to permit the normal collection vehicles to collect the materials. Immediately following recycling collection the Contractor shall return recycling receptacles to the addresses marked on the receptacles.

- E6.2 Collection Schedule:

### **Ethelbert St. / Canora St. Alley; the Woseley Ave. North; and the Westminster Ave. South Alley.**

*Collection Day(s):* 5  
*Collection Time:* 8:00 am  
*Common Collection Area:* North-east end of Westmintser Ave. South Alley

### **Hargrave St. / Donald St. Alley.**

*Collection Day(s):* Twice weekly  
*Collection Time:* Varies  
*Common Collection Area:* North end of alley at Hargrave Pl.

### **McAdam Ave. / Matheson Ave. Alley.**

*Collection Day(s):* 1  
*Collection Time:* 8:00am  
*Common Collection Area:* West end of alley at powers St.

### **Yale Ave. / Grosvenor Ave. Alley.**

*Collection Day(s):* 1  
*Collection Time:* 8.00am  
*Common Collection Area:* West end of alley at Rockwood St.

- E6.3 No measurement or payment will be made for the work associated with this specification.

## **E7. WATER USED BY CONTRACTOR**

- E7.1 Further to clause 3.7 of CW 1120-R1, the Contractor shall pay for all costs associated with obtaining water in accordance with the Waterworks By-law. Sewer charges will not be assessed for water obtained from a hydrant.

## **E8. SURFACE RESTORATIONS**

- E8.1 Further to clause 3.3 of CW 1130-R1, when Total Performance is not achieved in the year the Contract is commenced, the Contractor shall temporarily repair any Work commenced and not completed to the satisfaction of the Contract Administrator. The Contractor shall maintain the temporary repairs in a safe condition as determined by the Contract Administrator until permanent repairs are completed. The Contractor shall bear all costs associated with temporary repairs and their maintenance.

## **E9. SUPPLY AND INSTALLATION OF GEOTEXTILE FABRICS**

### **E9.1 Description**

(a) This specification shall amend CW 3130

Add 2.1.2: Use only non-woven geotextiles materials as approved and listed in accordance with section 4.4 of Approved Products for Surface Works.

Add 2.5.3 with: For sub-grades designated as unstable (requiring geogrid), the Separation/reinforcement fabric will be non-woven fabric.

## **E10. SUPPLY AND INSTALLATION OF GEOGRID**

### **E10.1 Description**

E10.1.1 This specification covers the supply and installation of Geogrid on unstable Sub-grade soil conditions.

E10.1.2 Referenced Standard Construction Specifications

(a) CW 3110 – Sub-grade, Sub-base and Base Course Construction

### **E10.2 Materials**

E10.2.1 Material will be polypropylene, extruded bi-axial single layer Geogrid.

E10.2.2 Acceptable products will be Tenax LBO 302, Nillex BX 1200 or an equal approved by the Contract Administrator.

E10.2.3 All Geogrid rolls must clearly show the product style number and unique roll number.

E10.2.4 Storage and Handling

(a) Store and handle in accordance with the manufacturer's recommendations.

E10.2.5 Mill Certificate and MARV Data

(a) Provide the Mill Certificate and MARV (Minimum Average Roll Data) Data upon request by the Contract Administrator.

### **E10.3 Construction Methods**

E10.3.1 Commence installation of Geogrid after approval by the Contract Administrator and the preparation of the sub-grade has been completed in accordance with CW 3110.

E10.3.2 Supply and install additional separation/reinforcement fabric material in accordance with CW 3130 at locations as directed by the Contract Administrator.

E10.3.3 Unroll Geogrid as smooth as possible on the prepared sub-grade or separation/reinforcement fabric as applicable, in the direction of construction traffic.

E10.3.4 Install the Geogrid in the longest continuous practical length, free from tension, stress, folds wrinkles and creases.

E10.3.5 Overlap joints a minimum of 900mm.

E10.3.6 Tie adjacent rolls with joint fasteners in accordance to the manufacturer's recommendations.

E10.3.7 Construction vehicles are not permitted directly on the Geogrid.

E10.3.8 Place and compact sub-base material to a minimum depth of 300mm in accordance with CW 3110.

E10.3.9 Avoid sudden stops or sharp turns by construction equipment during placement of sub-base materials.

- E10.3.10 Remove or replace Geogrid improperly installed or damaged as directed by the Contact Administrator.
- E10.4 Measurement and Payment
- E10.4.1 Supply and installation of Geogrid will be measured on an area basis and paid for at the Contract Unit Price per square metre for "Supply and Install Geogrid". The area to be paid for will be the total number of square metres of Geogrid, supplied and installed in accordance with this specification, accepted and measured by the Contract Administrator.
- E10.4.2 Only material placed within the designated sub-grade limits will be included in the payment for "Supply and Install Geogrid".
- E10.4.3 No measurement or payment will be made for Geogrid removed and replaced due to improper installation or damaged materials.
- E10.4.4 Adjacent roll joint fasteners will be included in payment for "Supply and Install Geogrid"

## **E11. FENCE REMOVAL AND RESTORATION**

### **E11.1 DESCRIPTION**

#### **(a) General**

- (i) This specification covers the removal and renewal of existing miscellaneous fencing.
- (ii) The intention is to provide alternate access for vehicular parking during reconstruction of the project.

#### **(b) Definitions**

- (i) Fence Removal and Restoration – existing adjacent fencing removed prior to project construction and restored after completing project construction.

### **E11.2 MATERIALS**

#### **(a) Salvage**

- (i) Salvage all existing material where practical, or replace with similar material as approved by Contract Administrator.

#### **(b) Wooden Fencing**

- (i) Supply wooden fencing to match existing or as approved by Contract Administrator.

#### **(c) Electrical**

- (i) Supply electrical components to restore existing power supply locations or as approved by Contract Administrator.

### **E11.3 CONSTRUCTION METHODS**

#### **(a) Removal**

- (i) Allow vehicular access to parking areas originally bounded by fencing.
- (ii) Remove fencing to limits given by Contract Administrator.
- (iii) Salvage materials as practicable for future reinstallation

#### **(b) Renewal**

- (i) Reinstall fencing to original limits or as directed by Contract Administrator.
- (ii) Install new replacement materials where required as directed by Contract Administrator.
- (iii) Build fencing with stiffness and strength of original fencing.
- (iv) Ensure integrity of electrical power supply to fencing if applicable.

### **E11.4 MEASUREMENT AND PAYMENT**

- (a) Removal and renewal of existing fencing is measured on a lump sum basis and paid at the Contract Unit Price for " Fence Removal and Restoration". The lump sum to be paid will be for the specified completed locations, accepted by the Contract Administrator.

## **E12. INSTALLATION OF SUBDRAINS**

### E12.1 Description

- (a) This specification shall amend CW 3120

Replace 3.2.3 to read:           Install drainage fabric in accordance to this specification and the Drawings.

## **E13. RECYCLED CONCRETE BASE COURSE MATERIAL**

### DESCRIPTION

#### E13.1 General

- E13.1.1 Further to CW 3110, this specification covers supply and placement of recycled concrete base course material for Full-Depth Partial Slab Patches (Class A, B, C, & D), miscellaneous concrete slabs and sidewalks.

#### E13.2 Definitions

- E13.2.1 Deleterious material – are materials such as vegetation, organic material, wood, glass, plastic, metal, reinforcing steel, building rubble, brick, salvaged asphalt materials, clay, shale, and friable particles.

#### E13.3 Referenced Standard Construction Specifications

- (a) CW 3110 – Sub-Grade. Sub-Base and Base Course Construction.
- (b) CW 3230 – Full-Depth Patching of Existing Pavement Slabs and Joints.
- (c) CW 3235 – Renewal of Existing Miscellaneous Concrete Slabs.
- (d) CW 3325 – Portland Cement Concrete Sidewalk.

### MATERIALS

#### E13.4 Recycled Concrete Base Course Material

- E13.4.1 Recycled concrete base course material when used for Full-Depth Partial Slab Patches (Class A, B, C, & D), miscellaneous concrete slabs and sidewalks will be considered equal to granular or limestone base course material specified in Section 2.2 of CW 3110.
- E13.4.2 Recycled concrete base course material will be approved by the Contract Administrator.
- E13.4.3 Recycled concrete base course material will consist of sound durable particles produced by crushing, screening, and grading of recovered concrete materials, free from soft material that would disintegrate through decay or weathering.
- E13.4.4 The recycled concrete base course material will be well graded and conform to the following grading requirements:  
  
Recycled Concrete Base Course Material Grading Requirements

CANADIAN METRIC SIEVE SIZE	PERCENT OF TOTAL DRY WEIGHT PASSING EACH SIEVE
20 000	100%
5 000	40% - 70%
2 500	25% - 60%
315	8% - 25%
80	6% - 17%

E13.4.5 Recycled concrete base course material when subjected to the abrasion test will have a loss of not more than 35% when tested in accordance with grading B of ASTM C131, Test for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

E13.4.6 The amount of deleterious material will be limited to a maximum of two percent of the total dry weight.

#### CONSTRUCTION METHODS

E13.5 Placement of Recycled Concrete Base Course Material

E13.5.1 Place and compact recycled concrete base course material as a levelling course to a maximum thickness of 50 millimetres.

E13.5.2 Spread materials uniformly to avoid segregation free of pockets of fine and coarse material.

E13.5.3 Level and compact to the finished elevation. Compact to 100% Standard Proctor Density for Full-Depth Partial Slab Patches (Class A, B, C, & D) and 90% Standard Proctor Density for miscellaneous concrete slabs and sidewalks.

E13.5.4 Maintain the finished material until the pavement or sidewalk is placed.

#### MEASUREMENT AND PAYMENT

E13.6 Recycled Concrete Base Course Material

E13.6.1 The supplying, placing and compaction of recycled concrete base course material will be measured on a volume basis and paid for at the Contract Unit Price per cubic metre for the "Supplying and Placing Base Course Material" as specified in accordance with CW 3110.

E13.6.2 No measurement or payment will be made for material placed as a levelling course under miscellaneous concrete slabs and sidewalks where the costs are included in accordance with CW 3235 and CW 3325.

E13.6.3 No measurement or payment will be made for materials rejected by the Contract Administrator.

# **APPENDIX 'A'**

# **GEOTECHNICAL REPORT**

## APPENDIX 'A' - GEOTECHNICAL REPORT


### TABLE OF CONTENTS

<b>GEOTECHNICAL REPORT FOR ETHELBERT ST. / CANORA ST. ALLEY; THE WOSELEY AVE. NORTH; AND THE WESTMINSTER AVE. SOUTH ALLEY</b>	<b>1</b>
Test Hole Locations	1
Summary of Core Samples	2
Test Hole Log for 1	3
Test Hole Log for 2	4
Test Hole Log for 3	5
Test Hole Log for 4	6
Test Hole Log for 5	7
Test Hole Log for 6	8
Test Hole Log for 7	9
<b>GEOTECHNICAL REPORT FOR HARGRAVE ST. / DONALD ST.</b>	<b>12</b>
Test Hole Locations	12
Summary of Core Samples	13
Test Hole Log for 1	14
Test Hole Log for 2	15
Pavement Core Photos	16
<b>GEOTECHNICAL REPORT FOR MCADAM AVE. / MATHESON AVE. ALLEY</b>	<b>17</b>
Test Hole Locations	17
Summary of Core Samples	18
Test Hole Log for 1	19
Test Hole Log for 2	20
Test Hole Log for 3	21
Test Hole Log for 4	22
Pavement Core Photos	23
<b>GEOTECHNICAL REPORT FOR YALE AVE. / GROSVENOR AVE. ALLEY</b>	<b>24</b>
Test Hole Locations	24
Summary of Core Samples	25
Test Hole Log for 1	26
Test Hole Log for 2	27
Test Hole Log for 3	28
Pavement Core Photos	29

The geotechnical report is provided to aid in the Contractor's evaluation of the soil conditions. The information presented is considered accurate at the locations shown on the Drawings and at the time of drilling. However, variations in soil conditions may exist between test holes and fluctuations in groundwater levels can be expected seasonally and may occur as a result of construction activities. The nature and extent of variations may not become evident until construction commences.

### Geotechnical Report for Ethelbert St. / Canora St. Alley; the Woseley Ave. North; and the Westminster Ave. South Alley

#### Test Hole Locations



**THE NATIONAL TESTING LABORATORIES LIMITED**  
 ESTABLISHED IN 1923

Project No.: KGS-631  
 Date: Dec. 21, 2006

Drawn By: KK  
 Scale: NTS


Testhole Location Plan  
 2007 City of Winnipeg Alley Renewals  
 Ethelbert Street/Canora Street Alley  
 Between Wolseley Avenue and Westminster Avenue

## Summary of Core Samples


**2007 City of Winnipeg  
Alley Renewals  
Geotechnical Investigation  
Ethelbert Street/Canora Street  
Wolsley Avenue to Westminster Avenue**

Testhole ID	Testhole Location	Pavement Surface		Pavement Structure Material		Sample Description	Sample Depth (m)	Moisture Content (%)	Particle Size Analysis				Atterberg Limits		
		Type	Thickness (mm)	Type	Thickness (mm)				Gravel (%)	Sand (%)	Silt (%)	Clay (%)	Liquid Limit	Plastic Limit	Plasticity Index
TH1	5.0 m E of W property line of 105 Ethelbert St., 2.0 m N of S side of lane	Concrete	155	Granular	50	N/A	-	-	-	-	-	-	-	-	-
TH2	4.3 m W of N property line of 80 Ethelbert St., 2.75 m N of S side of lane	Asphalt/Concrete	10/145	Granular	50	N/A	-	-	-	-	-	-	-	-	-
TH3	4.2 m N of S property line of 111 Ethelbert St., 1.7 m E of W side of lane	Concrete	160	Granular	25	Silty Clay	0.9	39.2	0.0	4.7	32.7	62.6	71	26	45
TH4	3.5 m N of S property line of 129 Ethelbert St., 1.4 m E of W side of lane	Asphalt/Concrete	15/175	Granular	50	N/A	-	-	-	-	-	-	-	-	-
TH5	1.2 m S of N property line of 137 Ethelbert St., 1.0 m E of W side of lane	Concrete	140	Granular	50	N/A	-	-	-	-	-	-	-	-	-
TH6	4.8 m E of W property line of 141 Ethelbert St., 1.6 m S of N side of lane	Concrete	150	Granular	150	N/A	-	-	-	-	-	-	-	-	-
TH7	9.0 m W of E property line for 132 Canora St., 0.4 m S of N side of lane	Concrete	175	Granular	50	Silt	1.2	14.0	0.0	3.4	76.1	20.5	24	18	6

**Test Hole Log for 1**



**Test Hole Log for 2**



**Test Hole Log for 3**


Subsurface Profile			Laboratory Testing					
Depth (m)	Symbol	Description	Moisture Content (%)		Gravel (%)	Sand (%)	Silt (%)	Clay (%)
			PL	LL				
0.0		Ground Surface						
		<b>Concrete</b>						
		<b>Granular Fill</b> - 37.5 mm maximum size						
		<b>Clay Fill</b> - black, frozen, mixture of sand and clay						
0.5		- grey/brown below 0.5 m, moist, firm, high plasticity clay, some sand, trace fine grained gravel						
1.0		<b>Silty Clay</b> - black/grey, moist, stiff, high plasticity - brown below 1.1 m - and silt between 1.2 m and 1.5 m			0.0	4.7	32.7	62.6
1.5								
2.0								
2.1		End of testhole at 2.1 m below grade.						
2.5		No water seepage or soil sloughing were observed during or after the completion of drilling.						

**TESTHOLE TH3**




**Project Name:** 2007 City of Winnipeg Alley Renewals  
**Client:** KGS Group  
**Site:** Ethelbert/Canora Alley, Wolseley Ave. to Westminster Ave.  
**Testhole Location:** 4.2 m N of the S property line of 111 Ethelbert St. , 1.7 m E of the W side of the lane

**Date Drilled:** December 7, 2006  
**Depth of Testhole:** 2.1 m  
**Logged by:** Kurtis Kulchyski




Gravel (%)	Sand (%)	Silt (%)	Clay (%)
0.0	4.7	32.7	62.6




**Test Hole Log for 4**




**Test Hole Log for 5**





**Test Hole Log for 6**

<b>TESTHOLE TH6</b>			
<b>Project Name:</b> 2007 City of Winnipeg Alley Renewals <b>Client:</b> KGS Group <b>Site:</b> Ethelbert/Canora Alley, Wolseley Ave. to Westminster Ave. <b>Testhole Location:</b> 4.8 m E of the W property line of 141 Ethelbert St., 1.8 m S of the N side of the lane		<b>Date Drilled:</b> December 7, 2006 <b>Depth of Testhole:</b> 2.1 m <b>Logged by:</b> Kurtis Kulchyski	
Subsurface Profile		Laboratory Testing	
Depth	Symbol	Description	Water Content (%)
			0 20 40 60 80 100
0.0		<b>Concrete</b>	
		<b>Granular Fill</b> - 37.5 mm maximum size	
0.5		<b>Silty Clay</b> - black/grey, stiff, moist, high plasticity	
1.0		<b>Silt</b> - tan, dry, firm, low plasticity	
1.5		<b>Clay</b> - brown, moist, stiff to firm, high plasticity, thinly varved with silt	
2.0		End of testhole at 2.1 m below grade.  No water seepage or soil sloughing were observed during or after the completion of drilling.	
2.5			

**Test Hole Log for 7**




Pavement Core Photos





**Geotechnical Report for Hargrave St. / Donald St.**

**Test Hole Locations**




 <p><b>THE          NATIONAL          TESTING          LABORATORIES          LIMITED</b>  <i>Established in 1923</i></p>	Project No.: KGS-630	Drawn By: SD	Testhole Location Plan 2007 City of Winnipeg Alley Renewals Hargrave Street/Donald Street Alley Between Assiniboine Avenue and Hargrave Place
	Date: Dec. 20, 2006	Scale: NTS	





**Test Hole Log for 1**

Subsurface Profile			Laboratory Testing					
Depth (m)	Symbol	Description	Moisture Content (%)		Gravel (%)	Sand (%)	Silt (%)	Clay (%)
			PL	LL				
		Ground Surface	0	100				
0.0		<b>Concrete</b>						
0.0 - 0.4		<b>Granular Base</b> - 50 mm maximum size						
0.4 - 1.2		<b>Clay Fill</b> - black, frozen mixture of black clay and sand - black/grey below 0.6 m, moist, firm, high plasticity, trace sand, trace fine grained gravel						
1.2 - 2.1		<b>Silty Clay</b> - brown, moist, firm, high plasticity, and silt						
1.5					0.0	0.8	35.4	63.8
2.0								
2.5		End of testhole at 2.1 m below grade.  No water seepage or soil sloughing were observed during or after the completion of drilling.						

**Test Hole Log for 2**




**Pavement Core Photos**



### Geotechnical Report for McAdam Ave. / Matheson Ave. Alley

#### Test Hole Locations




 <p><b>THE NATIONAL TESTING LABORATORIES LIMITED</b>  <small>Established in 1929</small></p>	Project No.: KGS-631	Drawn By: SD	Testhole Location Plan 2007 City of Winnipeg Alley Renewals McAdam Avenue/Matheson Avenue Alley Between Powers Street and Salter Street
	Date: Dec. 20, 2006	Scale: NTS	

## Summary of Core Samples

2007 City of Winnipeg  
Alley Renewals  
Geotechnical Investigation  
McAdam Avenue/Matheson Avenue Alley  
Powers Street to Salter Street

Testhole ID	Testhole Location	Pavement Surface		Pavement Structure Material		Sample Description	Sample Depth (m)	Moisture Content (%)	Particle Size Analysis				Atterberg Limits		
		Type	Thickness (mm)	Type	Thickness (mm)				Gravel (%)	Sand (%)	Silt (%)	Clay (%)	Liquid Limit	Plastic Limit	Plasticity Index
TH1	2.4 m W of W property line of 375/373 Matheson Ave., 0.5 m N of S side of lane	Concrete	220	N/A	-	-	-	-	-	-	-	-	-	-	-
TH2	1.9 m W of E property line of 359 Matheson Ave., 1.5 m N of S side of lane	Asphalt/Concrete	15/210	N/A	-	Clay	0.9	37.4	0.0	2.4	16.7	80.9	87	24	63
TH3	1.0 m W of E property line of 338 McAdam Ave., 1.3 m N of S side of lane	Concrete	215	N/A	-	-	-	-	-	-	-	-	-	-	-
TH4	In line with W property line of 318 McAdam Ave., 1.8 m N of S side of lane	Asphalt/Concrete	15/210	N/A	-	Clayey Silt	1.5	24.2	0.0	1.9	66.9	31.2	31	19	12

**Test Hole Log for 1**



**Test Hole Log for 2**

Subsurface Profile			Laboratory Testing						
Depth (m)	Symbol	Description	Moisture Content (%)		Gravel (%)	Sand (%)	Silt (%)	Clay (%)	
			PL	LL					
			0	25	50	75	110		
0.0		Ground Surface							
		Asphalt							
		Concrete							
		Clay - black/grey, moist, firm, high plasticity - brown below 0.9 m							
0.5									
1.0		Clayey Silt - tan, moist, firm, low plasticity, with clay				0.0	2.4	16.7	80.9
1.5									
2.0		Clay - brown, moist, firm, high plasticity, varved with silt							
		End of testhole at 2.1 m below grade.							
		No water seepage or soil sloughing were observed during or after the completion of drilling.							
2.5									


**TESTHOLE TH2**





**Project Name:** 2007 City of Winnipeg Alley Renewals  
**Client:** KGS Group  
**Site:** McAdam/Matheson Alley between Powers St. and Salter St.  
**Testhole Location:** 1.9 m W of the E property line of 359 Matheson Ave., 1.5 m N of the S side of the lane

**Date Drilled:** December 7, 2006  
**Depth of Testhole:** 2.1 m  
**Logged by:** Kurtis Kulchyski

**Test Hole Log for 3**



**Test Hole Log for 4**

Subsurface Profile			Laboratory Testing					
Depth (m)	Symbol	Description	Moisture Content (%)		Gravel (%)	Sand (%)	Silt (%)	Clay (%)
			PL	LL				
0.0			0	25	50	75	110	
Ground Surface								
0.0		Asphalt						
0.0		Concrete						
0.0		Clay - black/grey, moist, firm, high plasticity - brown below 1.0 m						
0.5								
1.0								
1.5		Clayey Silt - tan, moist, firm, low plasticity, with clay						
2.0								
2.5		End of testhole at 2.1 m below grade.  No water seepage or soil sloughing were observed during or after the completion of drilling.						


**TESTHOLE TH4**



**Project Name:** 2007 City of Winnipeg Alley Renewals  
**Client:** KGS Group  
**Site:** McAdam/Matheson Alley between Powers St. and Salter St.  
**Testhole Location:** In line with the W property line of 318 McAdam Ave., 1.8 m N of the S side of the lane

**Date Drilled:** December 7, 2006  
**Depth of Testhole:** 2.1 m  
**Logged by:** Kurtis Kulchyski

**Moisture Content (%)**




Gravel (%)	Sand (%)	Silt (%)	Clay (%)
0.0	1.9	66.9	31.2

**Pavement Core Photos**



### Geotechnical Report for Yale Ave. / Grosvenor Ave. Alley

#### Test Hole Locations



**THE  
 NATIONAL  
 TESTING  
 LABORATORIES  
 LIMITED**  
*Established in 1923*

Project No.: KGS-625

Drawn By: SD

Date: Dec. 6, 2006

Scale: NTS


Testhole Location Plan  
 2007 City of Winnipeg Alley Renewals  
 Yale Avenue/Grosvenor Avenue Alley  
 Between Rockwood Street and Wilton Street

## Summary of Core Samples



**2007 City of Winnipeg  
Alley Renewals  
Geotechnical Investigation  
Yale Avenue/Grosvenor Avenue Alley  
Rockwood Street to Wilton Street**

Testhole ID	Testhole Location	Pavement Surface		Pavement Structure Material		Sample Description	Sample Depth (m)	Moisture Content (%)	Particle Size Analysis				Atterberg Limits		
		Type	Thickness (mm)	Type	Thickness (mm)				Gravel (%)	Sand (%)	Silt (%)	Clay (%)	Liquid Limit	Plastic Limit	Plasticity Index
TH1	4.3 m E of W property line of 296 Yale Avenue, 1.9 m S of S side of lane	Asphalt/Concrete	25/160	N/A	-	N/A	-	-	-	-	-	-	-	-	-
TH2	1.4 m E of E property line of 284 Yale Avenue, 2.1 m S of S side of lane	Asphalt/Concrete	15/160	N/A	-	Clayey Silt	0.9	27.3	0.0	2.9	50.5	46.6	44	15	29
TH3	3.0 m E of W property line of 268 Yale Avenue, 1.2 m S of S side of lane	Asphalt/Concrete	25/195	N/A	-	Clay	1.8	44.3	0.0	0.3	4.9	94.8	103	22	81

**Test Hole Log for 1**



**Test Hole Log for 2**


Subsurface Profile			Laboratory Testing					
Depth (m)	Symbol	Description	Moisture Content (%)		Gravel (%)	Sand (%)	Silt (%)	Clay (%)
			PL	LL				
Ground Surface								
0.0		<b>Asphalt</b>						
		<b>Concrete</b>						
0.5		<b>Clay</b> - black, moist, firm, high plasticity						
1.0		<b>Clayey Silt</b> - tan, moist, soft, intermediate plasticity, with clay			0.0	2.9	50.5	46.6
1.5		<b>Clay</b> - brown, moist, firm, high plasticity, some silt pockets - firm to stiff below 1.8 m						
2.0		End of testhole at 2.1 m below grade.  No water seepage or soil sloughing were observed during or after completion of drilling.						

**TESTHOLE TH2**




**Project Name:** 2007 City of Winnipeg Alley Renewals  
**Client:** KGS Group  
**Site:** Yale/Grosvenor Alley between Rockwood St. and Wilton St.  
**Testhole Location:** 1.4 m E of E property line of 284 Yale Avenue, 2.1 m S of S side of lane

**Date Drilled:** December 4, 2006  
**Depth of Testhole:** 2.1 m  
**Logged by:** Sarah Didychuk



Gravel (%)	Sand (%)	Silt (%)	Clay (%)
0.0	2.9	50.5	46.6

**Test Hole Log for 3**



**Pavement Core Photos**

