



## 504-2008 ADDENDUM 3

### CONSTRUCTION OF EAST VESTIBULES AND MECHANICAL HAVAC UPGRADES – PAN AM POOL

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: July 15, 2008  
BY: Coleen Groening  
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20070419

---

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 7 of Form A: Bid may render your Bid non-responsive.

---

#### **PART B – BIDDING PROCEDURES**

Revise: B2.1 to read: The Submission Deadline is 4:00 P.M. Winnipeg time, July 18, 2008.

#### **PART E – SPECIFICATIONS**

Add: E1.5. Transom Infill Panels

Add: 1.5.1 The infill for the two transoms at mechanical penetrations shall be constructed of anodized aluminum panels both sides (to match existing aluminum door frame finish and colour),  $\frac{3}{4}$ " pressure treated plywood backing both sides,  $\frac{1}{2}$ " rigid insulation complete with additional blocking as may be required to custom suite penetration. Include related fasteners, clips, caulking, and seal and make watertight.

Add: 1.5.2 The Contractor shall verify on site all dimensions for existing transoms that are affected, remove existing glass at those location, and measure onsite the new mechanical unit penetration size.