



**WEATHERPROOF ELECTRICAL SERVICE BOX DETAIL**  
n.t.s.

notes:

1. All wiring for pole luminaires to be min. 2#12 Teck direct buried in trench.
2. Provide and install new 12 CCT electrical panel and 50A-2P main breaker. Provide weatherproof enclosure for new panelboard c/w padlock. Mount panelboard meter and breaker within enclosure.
3. Provide and install new weatherproof electrical enclosure and pedestal.
4. Provide and install 3#6 R90 in 1-1/2" conduit for meter enclosure and new panelboard. Provide 3C#6 Teck direct buried cable to Manitoba Hydro connection point.
5. Co-ordinate electrical service supply with Manitoba Hydro and final location of equipment with Utility and Contract Administrator. *Bidder to include in pole light lump sum a \$5,000.00 cash allowance for Manitoba Hydro connection.*

Project:

**KIRKBRIDGE PARK**

CYNTHIA COHLMAYER LANDSCAPE ARCHITECT 359 McDERMOT AVE, Winnipeg MB R3A 0A6 (204) 943-1394 FAX 942-4426 office@cohlarch.ca	Sheet Title: <b>WEATHERPROOF ELECTRICAL SERVICE BOX</b>				
	Drawn by: <b>CC</b>	File: <b>C0811</b>	Scale: <b>NTS</b>	Date: <b>28/07/08</b>	Sheet No.: <b>L-6</b>