



615-2008 ADDENDUM 1

Old Ex Park - Sgt. Tommy Prince Park Pathway Connection Phase 1

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: August 19, 2008
BY: Susan Russell
TELEPHONE NO. (204) 956-0396

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 615-2008 Bid Submission with 615-2008 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Revised quantities for Supply and install sod and topsoil including rough grading, Supply and install topsoil and native seeded prairie grass including rough grading, erosion control, weed control, and remedial seeding, and Supply and install crushed limestone pathway including removals, rough grading, geotextile fabric and compaction.

Form B(R1): Deleted Supply and install temporary 300mm dia. CSP culverts

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 4:00 p.m. Winnipeg time, August 22, 2008.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D12.1 to read: The Contractor shall achieve Substantial Performance by October 31, 2008.

Revise: D13.1 to read: The Contractor shall achieve Total Performance by September 30, 2011.

Revise: D14.1 to read: If the Contractor fails to achieve Substantial Performance in accordance with the Contract by the day fixed herein for Substantial Performance, the Contractor shall pay the City five hundred dollars (\$500.00) per Calendar Day for each and every Calendar Day following the day fixed herein for Substantial Performance during which such failure continues

PART E – SPECIFICATIONS

Delete: E22.2.2 Temporary culverts in accordance with CW3610 at 300mm diameter.

Revise: E22.4 to read: Method of Measurement / Basis of Payment

Revise: E22.4.1 to read: CSP culverts shall be measured and paid on a per item basis. The number to be paid for shall be the total number of units placed in accordance with this Specification and the Construction Drawings, as determined by the Contract Administrator.

- Revise: E24.6.1 to read : An integrated weed control system will be initiated on the "A" Horizon growth medium. Frequent inspections and follow up treatments combining integrated weed management, may be necessary for at least one-year post revegetation.
- Revise E24.8.1 to read: The Contractor shall:
- (a) manage all aspects of the plant materials installation processes,
 - (b) manage all aspects related to weed control,
 - (c) communicate with other site contractors regarding their work schedules,
 - (d) submit written reports to Contract Administrator identifying:
 - (i) Maintenance Work carried out monthly.
 - (ii) Development and condition of plant material.
 - (iii) Preventative or corrective measures required which are outside Contractor's responsibility.
 - (iv) Annual progress reports (to be submitted by every spring) stating adaptive development of the naturalization process after inspection by a qualified agronomist.
 - (e) notify the Client upon completion of the work outlined herein,
 - (f) develop and implement erosion control plans,
 - (g) provide an invoice upon the completion of each component of Work based on actual quantities.
- Revise E24.9.2 to read: The Contractor assumes no liability for 'act of God' occurrences such as; water damage or drought stress to plant material, extreme climatic events, goose damage, silt deposition, vandalism, and/or tampering in the establishment or subsequent years, which may cause mortality, of plant material installed by the Contractor.
- Revise E24.9.3 to read: The Contractor assumes no liability for damage to plant material by third party contractors, nor does the Contractor assume liability for the deposition of refuse, spoilage, debris, etc

DRAWINGS

Replace: 615-2008 _Drawing_L1-1 with 615-2008 _Addendum_1 Drawing L1-1-R1

615-2008 _Drawing_L2 with 615-2008 _Addendum_1 Drawing L2-R1

Delete: 615-2008 _Drawing_ L1-2