



653-2008 ADDENDUM 1

WEST VESTIBULES MECHANICAL HVAC UPGRADES – PAN AM POOL

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: September 2, 2008
BY: Coleen Groening
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

15010 MECHANICAL GENERAL PROVISIONS

Part 1 – 1.11 Cutting and Patching

Add: .5 The Contractor shall be responsible for: (1) all coring, (2) x-raying of floors and walls, and (3) change in pipe sizing.

15100 INSULATION

PART 4 – SCHEDULES -TABLE 8 – PIPE & DUCTWORK INSULATION

Add: **Remarks G** - Cross reference Drawing 653-2008_RM-1-R0. All piping shall be insulated and finished to match Vestibule requirements.

15600 LIQUID HEAT TRANSFER

Part 1 – 1.3 SCOPE OF WORK

Add: .8 All TAB requirements water and air shall be carried by this Section.

Part 2 – 2.9 PLATE HEAT EXCHANGER

Add: .10 Plate Heat Exchanger – Unit shall be double wall construction. Anchor bolts and external gaskets are by this supplier. Provide (4) air vents and (4) drain valves each side.

Revise: Part 4 - Table 11 – Pumps – WPU-2A Circ: 20 Gpm

Revise: Part 4 – Table 13 – Expansion Tank – Model XA 140

Revise: Part 4 – Table 14 – Balancing Valves – WBV-2A: 20 Gpm, 1 ½” diameter, WBV-3A, 4A, 5A, 6A: Gpm, 1 ¼” diameter

Revise: Part 4 – Table 15 – Hot Water Preheat Coil Glycol – WPHC-1A, 2A: 10 Gpm

Revise: Part 4 - Table 16 Plate Heat Exchanger – Hot Side: 170°F/150°F, Cold Side: 140°/120°F, Cold Side Gpm: 23,
Plates: 25

DRAWINGS

Add: 653-2008_Drawing_RM-1-R0