



**NOTES:**

- .01 Drawings are not to be scaled for estimating purposes
- .02 Contractor is responsible for site verifications of all dimensions
- .03 All areas given are approximate
- .04 Repair membrane fractures, approximately 400 lin. Ft.
- .05 Caulk chimney flashing and storm collars
- .06 Minor repairs to exposed expansion joint membranes and perimeter striping
- .07 Check flashings and re-secure as required
- .08 Check drains to be clear
- .09 Fill pitch boxes

/// Membrane fracture

<p><b>WINNIPEG TRANSIT DEPARTMENT</b>          421 Osborne Street          Winnipeg MB R3L 2A2          Tel: 986-5812 / 479-5430          avecherya@winnipeg.ca</p>		
<p>PROJECT  <b>PROVISION OF ROOF REPLACEMENT AT WINNIPEG TRANSIT DEPARTMENT, 421 OSBORNE STREET</b></p>		
<p>SHEET TITLE  <b>ROOF REPLACEMENT, BUILDING NCH</b></p>		
<p>DRAWN BY  <b>AV</b></p>	<p>CHECKED BY  <b>AV</b></p>	<p>APPR. BY</p>
<p>eFILE  <u>375-2009</u>  <b>DRAWING A-3-RO</b></p>		<p>PROJECT No  <b>375-2009</b></p>
<p>DATE  <b>2009. 05.20</b></p>		<p>SCALE  <b>NTS</b></p>
<p>SHEET No  <b>A-3</b></p>		