



THE CITY OF WINNIPEG

BID OPPORTUNITY

BID OPPORTUNITY NO. 527-2009

**SNOW CLEARING ON REGIONAL AND LOCAL STREETS, BACKLANES AND
LOCAL SIDEWALKS WITHIN THE EAST AREA (SOUTH)**

Summary of Changes from Previous Years' Contracts

1. New

D6	OPERATOR'S COMPENTENCE AND PERFORMANCE
E2.1.17	0.6m median cut on P1/P2 contract plow is now included in lane km price.
E2.1.23	Coordination with garbage / recycling collection required.
E2.4.9	Contractor to provide proposed P3 plow locations for mapping.
E5	DRIVERS LICENSE FOR ALL HIRED HOURLY EQUIPMENT
E8.1(d)	Backlanes have been added to the contract
E8.1(e)	Local sidewalks have been added to the contract
E12	PRICE ADJUSTMENT – FUEL COSTS
E13.2	Reporting damage to City or private property

2. Revisions

D2.1	Two-year contract with a one (1) year extension at the option of the City of Winnipeg
------	---

- E2.4.4 Increased time from 48 hours to 60 hours
- E4.1 Minimum truck plows required increased to 5
- E4.7(c) Minimum truck plow blade width changed from 2.6m to 2.4m wide.
- E13.4 Damaged curbs to be removed by April 15th each year
- E14.1.2 Revised penalty clauses for Priority II and Priority III streets and for backlanes. Changed percentage from 50% to 25%.
- Note: New P2 and P3 boundary's
- Note: St. Anne's removed from P1 street plowing inventory

TABLE OF CONTENTS

PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	3

PART B - BIDDING PROCEDURES

B1. Contract Title	1
B2. Submission Deadline	1
B3. Enquiries	1
B4. Addenda	1
B5. Substitutes	2
B6. Bid Submission	2
B7. Bid	3
B8. Prices	4
B9. Qualification	4
B10. Opening of Bids and Release of Information	5
B11. Irrevocable Bid	5
B12. Withdrawal of Bids	6
B13. Evaluation of Bids	6
B14. Award of Contract	7

PART C - GENERAL CONDITIONS

C0. General Conditions	1
------------------------	---

PART D - SUPPLEMENTAL CONDITIONS

General

D1. General Conditions	1
D2. Scope of Work	1
D3. Definitions	2
D4. Contract Administrator	3
D5. Contractor's Supervisor	3
D6. Operator's Competence and Performance	4
D7. Notices	4

Submissions

D8. Authority to Carry on Business	5
D9. Insurance	5

Schedule of Work

D10. Commencement	5
D11. Total Performance	6
D12. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	6

PART E - SPECIFICATIONS

General

E1. Applicable Specifications and Drawings	1
E2. Snow Clearing Requirements	1
E3. Hourly Equipment Services	6
E4. Equipment	7
E5. Drivers License for all Hired Hourly Equipment	8
E6. Contractor's Supervision and Communication	8
E7. Extreme Snowfall and Blizzard Conditions	9
E8. Quantities	9
E9. Traffic Movement and Parking Restrictions	10
E10. Measurement and Payment	10
E11. Annual Review – Inflationary Adjustment	14
E12. Price Adjustment – Fuel Costs	14

E13. Damage to Public and Private Property
E14. Penalties

15
16

PART F - APPENDICES

PART B - BIDDING PROCEDURES

B1. CONTRACT TITLE

B1.1 SNOW CLEARING ON REGIONAL AND LOCAL STREETS, BACKLANES AND LOCAL SIDEWALKS WITHIN THE EAST AREA (SOUTH)

B2. SUBMISSION DEADLINE

B2.1 The Submission Deadline is 4:00 p.m. Winnipeg time, July 24, 2009.

B2.2 Bids determined by the Manager of Materials to have been received later than the Submission Deadline will not be accepted and will be returned upon request.

B2.3 The Contract Administrator or the Manager of Materials may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

B3. ENQUIRIES

B3.1 All enquiries shall be directed to the Contract Administrator identified in D4.1.

B3.2 If the Bidder finds errors, discrepancies or omissions in the Bid Opportunity, or is unsure of the meaning or intent of any provision therein, the Bidder shall promptly notify the Contract Administrator of the error, discrepancy or omission at least five (5) Business Days prior to the Submission Deadline.

B3.3 If the Bidder is unsure of the meaning or intent of any provision therein, the Bidder should request clarification as to the meaning or intent prior to the Submission Deadline.

B3.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator to all Bidders by issuing an addendum.

B3.5 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator only to the Bidder who made the enquiry.

B3.6 The Bidder shall not be entitled to rely on any response or interpretation received pursuant to B3 unless that response or interpretation is provided by the Contract Administrator in writing.

B4. ADDENDA

B4.1 The Contract Administrator may, at any time prior to the Submission Deadline, issue addenda correcting errors, discrepancies or omissions in the Bid Opportunity, or clarifying the meaning or intent of any provision therein.

B4.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.

B4.2.1 Addenda will be available on the Bid Opportunities page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt/bidopp.asp>

B4.2.2 The Bidder is responsible for ensuring that he has received all addenda and is advised to check the Materials Management Division website for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.

B4.3 The Bidder shall acknowledge receipt of each addendum in Paragraph 8 of Form A: Bid. Failure to acknowledge receipt of an addendum may render a Bid non-responsive.

B5. SUBSTITUTES

- B5.1 The Work is based on the Plant, Materials and methods specified in the Bid Opportunity.
- B5.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.
- B5.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.
- B5.4 The Bidder shall ensure that any and all requests for approval of a substitute:
- (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative;
 - (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
 - (c) identify any anticipated cost or time savings that may be associated with the substitute;
 - (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance;
 - (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance.
- B5.5 The Contract Administrator, after assessing the request for approval of a substitute, may in his sole discretion grant approval for the use of a substitute as an “approved equal” or as an “approved alternative”, or may refuse to grant approval of the substitute.
- B5.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, only to the Bidder who requested approval of the substitute.
- B5.6.1 The Bidder requesting and obtaining the approval of a substitute shall be entirely responsible for disseminating information regarding the approval to any person or persons he wishes to inform.
- B5.7 If the Contract Administrator approves a substitute as an “approved equal”, any Bidder may use the approved equal in place of the specified item.
- B5.8 If the Contract Administrator approves a substitute as an “approved alternative”, any Bidder bidding that approved alternative may base his Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B13.
- B5.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.
- B5.10 Notwithstanding B5.2 to B5.9, and in accordance with B6.5, deviations inconsistent with the Bid Opportunity document shall be evaluated in accordance with B13.1(a).

B6. BID SUBMISSION

- B6.1 The Bid shall consist of the following components:

- (a) Form A: Bid;
- (b) Form B: Prices.

- B6.2 Further to B6.1, the Bidder should include the written correspondence from the Contract Administrator approving a substitute in accordance with B5.
- B6.3 All components of the Bid shall be fully completed or provided, and submitted by the Bidder no later than the Submission Deadline, with all required entries made clearly and completely in ink, to constitute a responsive Bid.
- B6.4 Bidders are advised not to include any information/literature except as requested in accordance with B6.1.
- B6.5 Bidders are advised that inclusion of terms and conditions inconsistent with the Bid Opportunity document, including the General Conditions, will be evaluated in accordance with B13.1(a)
- B6.6 The Bid may be submitted by mail, courier or personal delivery, or by facsimile transmission.
- B6.7 If the Bid is submitted by mail, courier or personal delivery, it shall be enclosed and sealed in an envelope clearly marked with the Bid Opportunity number and the Bidder's name and address, and shall be submitted to:
- The City of Winnipeg
Corporate Finance Department
Materials Management Division
185 King Street, Main Floor
Winnipeg MB R3B 1J1
- B6.7.1 Samples or other components of the Bid which cannot reasonably be enclosed in the envelope may be packaged separately, but shall be clearly marked with the Bid Opportunity number, the Bidder's name and address, and an indication that the contents are part of the Bidder's Bid Submission.
- B6.8 If the Bid is submitted by facsimile transmission, it shall be submitted to (204) 949-1178.
- B6.8.1 The Bidder is advised that the City cannot take responsibility for the availability of the facsimile machine at any time.
- B6.9 Bids submitted by internet electronic mail (e-mail) will not be accepted.

B7. BID

- B7.1 The Bidder shall complete Form A: Bid, making all required entries.
- B7.2 Paragraph 2 of Form A: Bid shall be completed in accordance with the following requirements:
- (a) if the Bidder is a sole proprietor carrying on business in his own name, his name shall be inserted;
 - (b) if the Bidder is a partnership, the full name of the partnership shall be inserted;
 - (c) if the Bidder is a corporation, the full name of the corporation shall be inserted;
 - (d) if the Bidder is carrying on business under a name other than his own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.
- B7.2.1 If a Bid is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B7.2.
- B7.3 In Paragraph 3 of Form A: Bid, the Bidder shall identify a contact person who is authorized to represent the Bidder for purposes of the Bid.
- B7.4 Paragraph 10 of Form A: Bid shall be signed in accordance with the following requirements:

- (a) if the Bidder is a sole proprietor carrying on business in his own name, it shall be signed by the Bidder;
- (b) if the Bidder is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
- (c) if the Bidder is a corporation, it shall be signed by its duly authorized officer or officers;
- (d) if the Bidder is carrying on business under a name other than his own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.

B7.4.1 The name and official capacity of all individuals signing Form A: Bid should be printed below such signatures.

B7.4.2 All signatures shall be original.

B7.5 If a Bid is submitted jointly by two or more persons, the word "Bidder" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Bidders in the Bid and the Contract, when awarded, shall be both joint and several.

B8. PRICES

B8.1 The Bidder shall state a price in Canadian funds for each item of the Work identified on Form B: Prices.

B8.1.1 Notwithstanding C11.1.1, prices on Form B: Prices shall not include the Goods and Services Tax (GST) which shall be extra where applicable.

B8.2 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Bids.

B8.3 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.

B9. QUALIFICATION

B9.1 The Bidder shall:

- (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Bidder does not carry on business in Manitoba, in the jurisdiction where the Bidder does carry on business; and
- (b) be financially capable of carrying out the terms of the Contract; and
- (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.

B9.2 The Bidder and any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:

- (a) be responsible and not be suspended, debarred or in default of any obligations to the City. A list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt/debar.stm>

B9.3 The Bidder and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:

- (a) have successfully carried out work similar in nature, scope and value to the Work; and
- (b) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract; and

- (c) have a written workplace safety and health program, if required, pursuant to The Workplace Safety and Health Act (Manitoba).

B9.4 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.

B9.5 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

B9.6 Further to B9.3(c), the Bidder shall, within five (5) Business Days of a request by the Contract Administrator, provide proof satisfactory to the Contract Administrator that the Bidder/Subcontractor has a workplace safety and health program meeting the requirements of The Workplace Safety and Health Act (Manitoba), by providing:

- (a) a valid COR certification number under the Certificate of Recognition (COR) Program administered by the Manitoba Construction Safety Association or by the Manitoba Heavy Construction Association's Safety, Health and Environment Program; or
- (b) a report or letter to that effect from an independent reviewer acceptable to the City. (A list of acceptable reviewers and the review template are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt>)

B9.7 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.

B9.8 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

B10. OPENING OF BIDS AND RELEASE OF INFORMATION

B10.1 Bid Submissions will not be opened publicly.

B10.2 Following the Submission Deadline, the names of the Bidders and their bid prices (unevaluated, and pending review and verification of conformance with requirements) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt>

B10.3 After award of Contract, the name(s) of the successful Bidder(s) and the Contract Amount(s) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt>

B10.4 The Bidder is advised that any information contained in any Bid may be released if required by City policy or procedures, The Freedom of Information and Protection of Privacy Act (Manitoba), or by other authorities having jurisdiction.

B11. IRREVOCABLE BID

B11.1 The Bid(s) submitted by the Bidder shall be irrevocable for the time period specified in Paragraph 9 of Form A: Bid.

B11.2 The acceptance by the City of any Bid shall not release the Bids of the next two lowest evaluated responsive Bidders and these Bidders shall be bound by their Bids on such Work for the time period specified in Paragraph 9 of Form A: Bid.

B12. WITHDRAWAL OF BIDS

- B12.1 A Bidder may withdraw his Bid without penalty by giving written notice to the Manager of Materials at any time prior to the Submission Deadline.
- B12.1.1 Notwithstanding C22.5, the time and date of receipt of any notice withdrawing a Bid shall be the time and date of receipt as determined by the Manager of Materials.
- B12.1.2 The City will assume that any one of the contact persons named in Paragraph 3 of Form A: Bid or the Bidder's authorized representatives named in Paragraph 10 of Form A: Bid, and only such person, has authority to give notice of withdrawal.
- B12.1.3 If a Bidder gives notice of withdrawal prior to the Submission Deadline, the Manager of Materials will:
- (a) retain the Bid until after the Submission Deadline has elapsed;
 - (b) open the Bid to identify the contact person named in Paragraph 3 of Form A: Bid and the Bidder's authorized representatives named in Paragraph 10 of Form A: Bid; and
 - (c) if the notice has been given by any one of the persons specified in B12.1.3(b), declare the Bid withdrawn.
- B12.2 A Bidder who withdraws his Bid after the Submission Deadline but before his Bid has been released or has lapsed as provided for in B11.2 shall be liable for such damages as are imposed upon the Bidder by law and subject to such sanctions as the Chief Administrative Officer considers appropriate in the circumstances. The City, in such event, shall be entitled to all rights and remedies available to it at law.

B13. EVALUATION OF BIDS

- B13.1 Award of the Contract shall be based on the following bid evaluation criteria:
- (a) compliance by the Bidder with the requirements of the Bid Opportunity (pass/fail);
 - (b) qualifications of the Bidder and the Subcontractors, if any, pursuant to B9 (pass/fail);
 - (c) Total Bid Price;
 - (d) economic analysis of any approved alternative pursuant to B5.
- B13.2 Further to B13.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid Submission is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities if the interests of the City so require.
- B13.3 Further to B13.1(b), the Award Authority shall reject any Bid submitted by a Bidder who does not demonstrate, in his Bid or in other information required to be submitted, that he is responsible and qualified.
- B13.4 Further to B13.1(c), the Total Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.
- B13.4.1 If there is any discrepancy between the Total Bid Price written in figures, the Total Bid Price written in words and the sum of the quantities multiplied by the unit prices for each item, the sum of the quantities multiplied by the unit prices for each item shall take precedence.
- B13.4.2 Further to B13.1(a), in the event that a unit price is not provided on Form B: Prices, the City will determine the unit price by dividing the Amount (extended price) by the approximate quantity, for the purpose of evaluation and payment
- B13.5 This Contract will be awarded as a whole.

B14. AWARD OF CONTRACT

- B14.1 The City will give notice of the award of the Contract or will give notice that no award will be made.
- B14.2 The City will have no obligation to award a Contract to a Bidder, even though one or all of the Bidders are determined to be responsible and qualified, and the Bids are determined to be responsive.
- B14.2.1 Without limiting the generality of B14.2, the City will have no obligation to award a Contract where:
- (a) the prices exceed the available City funds for the Work;
 - (b) the prices are materially in excess of the prices received for similar work in the past;
 - (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with its own forces;
 - (d) only one Bid is received; or
 - (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.
- B14.3 Where an award of Contract is made by the City, the award shall be made to the responsible and qualified Bidder submitting the lowest evaluated responsive Bid in accordance with B13 .
- B14.3.1 Following the award of contract, a Bidder will be provided with information related to the evaluation of his Bid upon written request to the Contract Administrator.
- B14.4 Notwithstanding C4.1, the City will issue a Purchase Order to the successful Bidder in lieu of the execution of a Contract.
- B14.5 The Contract Documents, as defined in C1.1(n), in their entirety shall be deemed to be incorporated in and to form a part of the Purchase Order notwithstanding that they are not necessarily attached to or accompany said Purchase Order.

PART C - GENERAL CONDITIONS

C0. GENERAL CONDITIONS

- C0.1 The *General Conditions for Supply of Services* (Revision 2007 04 12) are applicable to the Work of the Contract.
- C0.1.1 The *General Conditions for Supply of Services* are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at http://www.winnipeg.ca/matmgt/gen_cond.stm
- C0.2 A reference in the Bid Opportunity to a section, clause or subclause with the prefix “**C**” designates a section, clause or subclause in the *General Conditions for Supply of Services*.

PART D - SUPPLEMENTAL CONDITIONS

GENERAL

D1. GENERAL CONDITIONS

- D1.1 In addition to the *General Conditions for Supply of Services*, these Supplemental Conditions are applicable to the Work of the Contract.
- D1.2 The General Conditions are amended by striking out "The City of Winnipeg Act" wherever it appears in the General Conditions and substituting "The City of Winnipeg Charter".
- D1.3 The General Conditions are amended by striking out "Board of Commissioners" or "Commissioner" wherever it appears in the General Conditions and substituting the "Chief Administrative Officer".
- D1.4 The General Conditions are amended by striking out "Tender Package" wherever it appears in the General Conditions and substituting "Bid Opportunity".
- D1.5 The General Conditions are amended by striking out "Tender Submission" wherever it appears in the General Conditions and substituting "Bid Submission".
- D1.6 The General Conditions are amended by striking out "Bidding Instructions" wherever it appears in the General Conditions and substituting "Bidding Procedures".

D2. SCOPE OF WORK

- D2.1 The Work to be done under the Contract shall consist of snow clearing supplemental to the City of Winnipeg's snow clearing operations for the period of October 15, 2009 to April 15, 2011, with a one (1) year extension at the option of the City, under mutually agreeable terms.
- D2.1.1 Snow clearing shall be performed on those regional, bus route and collector, and residential streets listed in Appendices A, B and C, where full width snow clearing is required on all or a major portion of the above streets. Snow clearing on back lanes and local sidewalks as shown on drawings.
- D2.2 The Contractor shall perform the Work of this Contract on an "as-required" basis for two winter seasons from October 15, 2009 to April 15, 2011, except as hereinafter specified:
- (a) the Contractor may be required to remove snow which has fallen prior to October 15th and is on the streets as of that date;
 - (b) the Contractor shall continue and complete all authorized Work for a snowfall that begins on or before April 15th, notwithstanding that the Work occurs after April 15th; and,
 - (c) the Contractor shall remedy all damage and deficiencies such as curb damage by June 30th following the Contract year;
 - (d) the above requirements will apply also to any extension mutually agreed upon.
- D2.3 The major components of the Work are as follows:
- (a) full width snow clearing and hauling on the Priority I (Regional) Street System identified in Appendix A;
 - (b) full width snow clearing on the Priority II (Bus Routes and Collectors) Street System identified in Appendix B;
 - (c) full width snow clearing on the Priority III (Residential) Street System identified in Appendix C;
 - (d) 3.0 metre width snow clearing on backlanes identified on Drawing 1 ;
 - (e) 1.5 metre width snow clearing on sidewalks on Priority II and III streets identified on Drawing 1 ;

- (f) opening and keeping streets and lanes open during a major snowfall and/or snow blizzard;
- (g) snow clearing using truck plows on the Priority I, Priority II and Priority III streets noted in Appendices A, B and C;
- (h) other winter maintenance activities as required between major snowfalls.

D2.4 The Contract Administrator reserves the right to perform routine winter maintenance on the streets listed in Appendices A, B and C and the backlanes / sidewlaks shown on Drawing 1 using City forces. Routine winter maintenance includes:

- (a) curb lane spot plowing of street sections;
- (b) full width spot plowing of street sections;
- (c) spot plowing of backlane sections;
- (d) curb lane truck plowing;
- (e) full width truck plowing;
- (f) widening for snow storage;
- (g) snow hauling;
- (h) clearing of drainage inlets in spring.

D3. DEFINITIONS

D3.1 When used in this Bid Opportunity:

- (a) "**Business Day**" means any Calendar Day, other than a Saturday, Sunday, or a Statutory or Civic Holiday;
- (b) "**Submission Deadline**" and "**Time and Date Set for the Final Receipt of Bids**" mean the time and date set out in the Bidding Procedures for final receipt of Bids;
- (c) "**User**" means a person, department or other administrative unit of the City authorized by the Contract Administrator to order Work under this Contract.
- (d) "**Highway**" means any place or way, including any structure forming part thereof, which or any part of which the public is ordinarily entitled or permitted to use for the passage of vehicles or pedestrians, with or without fee or charge therefore, and includes all the space between the boundary lines thereof, whether or not used for vehicular or pedestrian traffic; and, without restricting the generality of the foregoing, includes roads, road allowances, streets, lanes, thoroughfares and other means of communication dedicated to the public use as highways as so defined, and also includes all bridges, subways, underpasses, grade separations, piers, wharves, ferries, and squares, and the road improvements thereon, dedicated to the public use.
- (e) "**Roadway**" means the paved portion of the street that is used exclusively for the passage of motorized vehicles.
- (f) "**Street**" means a highway over which the City of Winnipeg has jurisdiction.
- (g) "**Sidewalk**" means the paved portion of the street that is used exclusively for a passage of pedestrians.
- (h) "**Back lane**" means a highway situated wholly within the limits of any city, town or village or restricted speed area or reduced restricted speed area which has been designated, constructed and intended to provide access to and service at the rear of places of residence or business and includes alleys having a right-of-way width of not more than 9 metres.
- (i) "**Boulevard**" means the area between the street line and the nearest edge of a roadway and/or the area separating the roadways or a divided highway.
- (j) "**Street Right-of-Way**" means the limit of the publicly-owned land acquired for and devoted to streets, boulevards, appurtenances, as well as underground facilities.

- (k) **"Private Approach"** and **"Approach"** means a roadway, culvert crossing or other structure theretofore and hereafter, erected, installed or maintained in a street between the property of an owner and the nearest curb or edge of a roadway in the said street, for the use or benefit of the owner or occupant of the property adjoining or connected therewith, but does not include a roadway or other structure constructed for such purpose within an alley.
- (l) **"Traffic Lane"** means a 3.6 metre or greater width of pavement.
- (m) **"Pavement"** or the adjective **"Paved"** when used to describe a street, road, alley or other area, means an area which has a surface constructed of Portland Cement concrete, asphaltic concrete, brick, tile or similar material.
- (n) **"Bare Pavement"** means that the Contractor shall endeavour to completely clear the full pavement width of snow.
- (o) **"Face to face"** of curb on Priority I and II streets means the periodic exposure of the barrier curb vertical face with a maximum horizontal deviation of 150 mm (6 inches). This will enable the full width of the curb lane to be available for vehicular traffic.
- (p) **"Face to face"** of curb on Priority III streets means the periodic exposure of the top of the roll curb with a maximum horizontal deviation of 300 mm (12 inches) from the top of the curb into the traffic lane. Where barrier curb exists on Priority III streets, "face to face" curb means the periodic exposure of the barrier curb vertical face with a maximum horizontal deviation of 150 mm (6 inches).
- (q) **"Hauling"** means the relocation of cleared snow volumes by equipment normally employed for the snow clearing activity, but does not include the use of trucks.
- (r) **"Hauling away"** means the relocation of cleared snow volumes by use of trucks for purposes of transporting to a distant storage location.
- (s) **"Snow"** means all forms of frozen precipitation including ice associated with such snow.
- (t) **"Wing back"** means the Contractor shall push back the windrow to create storage space for snow in future plowing operations.
- (u) **"Cross Walk"** means any sidewalk at street intersections or at signed corridors.
- (v) **"Compacted Snow Surface"** of backlanes means a level, dense compacted layer of snow that will only allow minimal rutting from vehicular traffic and has a maximum thickness of 200mm from the compacted snow surface to underlying pavement.

D4. CONTRACT ADMINISTRATOR

D4.1 The Contract Administrator is:

Mr. Ken Boyd, P. Eng.
Support Services Engineer
Public Works Department
Streets Maintenance Division
104-1155 Pacific Avenue
Winnipeg, MB R3E 3P1

Telephone No. (204) 986-5076

Facsimile No. (204) 986-5566

D4.2 At the pre-commencement meeting, the Contract Administrator will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

D5. CONTRACTOR'S SUPERVISOR

D5.1 Further to C6.19, the Contractor shall employ and keep on the Work, at all times during the performance of the Work, a competent supervisor and assistants, if necessary, acceptable to the Contract Administrator. The supervisor shall represent the Contractor on the Site. The

supervisor shall not be replaced without the prior consent of the Contract Administrator unless the supervisor proves to be unsatisfactory to the Contractor and ceases to be in his employ.

D5.2 Before commencement of Work, the Contractor shall identify his designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.

D5.2.1 Further to C5.5 Contract Administrator may give instructions or orders to the Contractor's supervisor and such instructions or orders shall be deemed to have been given to the Contractor.

D6. OPERATOR'S COMPETENCE AND PERFORMANCE

D6.1 The Contractor's operator shall maintain all equipment/trucks in good working order and shall perform all obligations expressed and implied in this Bid Opportunity in a good, safe and workmanlike manner. Where, in the opinion of the City Inspector, an operator fails to meet the obligations expressed or implied in this Bid Opportunity, and without limited the generality of the foregoing, the operator is:

- (a) unqualified, or
- (b) operating in an unsafe manner, or
- (c) not performing a satisfactory amount of Work, or
- (d) engaged in activity outside the City's interests.

D6.2 The equipment/truck and operator may be dismissed immediately and shall not be re-engaged until such time as the inadequacies that resulted in the dismissal have been remedied to the sole satisfaction of the Contract Administrator.

D7. NOTICES

D7.1 C22.1 is further amended hereby to include delivery by facsimile transmission (fax) as an acceptable means of delivering notices, consents, approvals, statements, authorizations, documents or other communications required or permitted to be given under this Contract. Deliveries by fax will be deemed to have been received on the day of delivery, if a business day, or if not a business day, on the business day next following the day of delivery.

D7.2 Further to C22.2, all notices, consents, approvals, statements, authorizations, documents or other communications to the City, except as expressly otherwise required in D7.3, D7.4 or elsewhere in the Contract, shall be sent to the attention of the Contract Administrator at the address or facsimile number identified in D4.1.

D7.3 All notices of appeal to the Chief Administrative Officer shall be sent to the following address or facsimile number:

The City of Winnipeg
Chief Administrative Officer Secretariat
Administration Building, 3rd Floor
510 Main Street
Winnipeg MB R3B 1B9
Facsimile No.: (204) 949-1174

D7.4 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications required to be submitted or returned to the City Solicitor shall be sent to the following address or facsimile number:

The City of Winnipeg
Corporate Services Department
Legal Services Division
185 King Street, 3rd Floor
Winnipeg MB R3B 1J1

Facsimile No.: (204) 947-9155

SUBMISSIONS

D8. AUTHORITY TO CARRY ON BUSINESS

D8.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

D9. INSURANCE

D9.1 The Contractor shall provide and maintain the following insurance coverage:

- (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg added as an additional insured, such liability policy to also contain a cross-liability clause, contractual liability, unlicensed vehicle liability (contractors' equipment cover), non-owned automobile liability and products and completed operations, to remain in place at all times during the performance of the Work;
- (b) automobile liability insurance for owned automobiles used for or in connection with the Work in the amount of at least two million dollars (\$2,000,000.00); automobile insurance with stated limits to be retained at all times during the performance of the Work.

D9.2 Deductibles must be expressly stated on the certificate of insurance and must not exceed \$5,000.00.

D9.3 Deductibles shall be borne by the Contractor.

D9.4 The Certificate must clearly state: "Operations include snow removal on City right-of-ways during winter months" (i.e. insurance to cover snow removal and ice control of streets, roadways, backlanes/alleys, sidewalks, etc.).

D9.5 The Contractor shall file with the City certificates of insurance, confirming and expressly stating all requirements, in a form satisfactory to the City Solicitor; these certificates must be received by the City and approved, prior to commencement of any Work.

D9.6 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least fifteen (15) Calendar Days prior written notice to the Contract Administrator.

D9.7 The City shall have the right to alter limits and/or coverages as reasonably required from time to time during the continuance of this agreement.

SCHEDULE OF WORK

D10. COMMENCEMENT

D10.1 The Contractor shall not commence any Work until he is in receipt of a purchase order from the City authorizing the commencement of the Work.

D10.2 The Contractor shall not commence any Work on the Site until:

- (a) the Contract Administrator has confirmed receipt and approval of:
 - (i) evidence of authority to carry on business specified in D8;
 - (ii) evidence of the workers compensation coverage specified in C6.14;
 - (iii) evidence of the insurance specified in D9.

- (b) The Contractor has attended a meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a meeting.

D11. TOTAL PERFORMANCE

D11.1 The Contractor shall achieve Total Performance by June 30, 2011 for Work specified in D2.

D11.2 When the Contractor or the Contract Administrator considers the Work to be totally performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Total Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be re-inspected.

D11.3 The date on which the Work has been certified by the Contract Administrator as being totally performed to the requirements of the Contract through the issue of a certificate of Total Performance is the date on which Total Performance has been achieved.

D12. PRIME CONTRACTOR – THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA)

D12.1 Further to C6.23, the Contractor shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

PART E - SPECIFICATIONS

GENERAL

E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

E1.1 These Specifications shall apply to the Work.

E2. SNOW CLEARING REQUIREMENTS

E2.1 GENERAL WORK

E2.1.1 The entire shoulder width of highway type pavement shall be cleared of snow during the snow clearing operation.

E2.1.2 The entire length of the curb along the centre median shall be cleared to the face of the curb.

E2.1.3 Snow shall be cleared from centre median crosswalks and shall be stored on the side boulevards.

E2.1.4 Snow from centre median openings and traffic storage lanes shall be removed and stored in the side boulevards.

E2.1.5 Windrows at all intersections, cross walks, corridors, railway crossing and private approaches shall be removed in the initial clearing operations. The windrows shall be pushed downstream of traffic or into available storage area on the street right-of-way in order to eliminate blind spots for motorists, except as noted in E2.2 under the Priority I (Regional) street system where the snow must be hauled away as part of the initial clearing operation. In any case, snow shall not be placed on boulevards at or near corners so as to block visibility of vehicles moving through the intersection.

E2.1.6 Windrows at pedestrian corridors shall be cleared for a distance of fifteen (15) metres approaching the corridor and five (5) metres leaving the corridor on undivided roadways and for a distance of fifteen (15) metres approaching the corridor on divided roadways.

E2.1.7 Windrows at bus stops shall be removed to a distance of 12 m upstream from the bus stop sign. The bus stop platform and walk area connecting to the adjacent sidewalk shall be level to provide a safe footing for pedestrians.

E2.1.8 Snow windrows at hydrants shall be removed a loader bucket width.

E2.1.9 Snow windrows shall be removed a loader bucket width and a path cleared by back blading to a hard surface from the curb to the sidewalk at a limited number of locations designated as handicapped access. Actual addresses will be supplied to the Contractor after Contract award.

E2.1.10 Snow shall be removed around all G.R.E.A.T. (Guard Rail Energy Absorbing Terminal), Energite Barrel installations and between the curb and any adjacent guard rail that is within 3m of the curb and in the right-of-way. The G.R.E.A.T. units are used as crash cushions on the ends of guard rails to avoid abrupt stoppage of a vehicle. The Energite Barrel installations are used as crash cushions near overhead signs or any posts which do not have breakaway bases. This Work must be done carefully (by hand where necessary) such that the installations are not hit by snow clearing equipment or left covered in snow. The location of a limited number of installations will be supplied to the Contractor after the award.

- E2.1.11 Where adequate storage exists adjacent to the street, snow spillage onto the street as a result of the snow clearing operation shall be removed immediately by the Contractor. Any snow not removed may be removed by the City and the cost of the Work charged to the Contractor.
- E2.1.12 The City reserves the right, at its sole discretion, to allow windrow snow storage on the curb lane where no storage exists, provided that a reasonable attempt, satisfactory to the Contract Administrator or his designate, is made to minimize the extent of the encroachment during the Contractor's snow clearing operation. This storage shall only be utilized when specifically directed to do so by the Contract Administrator or his designate and only during unusual snow and blizzard conditions.
- E2.1.13 Snow shall not be deposited on islands between a yield or turnoff and the main roadway.
- E2.1.14 Snow shall not be stored or deposited on private property.
- E2.1.15 Snow from snow clearing operations shall not be deposited in sidewalk areas. All blocked sidewalk ends at intersections must be immediately cleared of snow in order to provide access for pedestrians and sidewalk plows. Any snow not immediately removed may be removed by the City and the resulting cost of the Work charged against the Contractor.
- E2.1.16 Snow from intersection windrows shall not be placed in bus stop areas.
- E2.1.17 The Contractor shall remove snow from the centre median (median cut) for snow storage and snow thaw purposes as and where directed, by the Contract Administrator. The median cut shall be to a width of 0.6m from the curb face and shall not expose, but be within 100mm of the median surface. The median cut shall be carried out in conjunction with the adjacent grader plow operations, and shall be included in the lane km price.
- E2.1.18 Snow removal at traffic circles shall include the removal of snow from the inner shoulder area, which shall be considered incidental to the full width snow clearing operation.
- E2.1.19 Work for each snow clearing operation shall commence only upon the instructions of the Contract Administrator.
- E2.1.20 Normally, Priority I (Regional) Streets shall receive the highest priority for snow clearing followed by Priority II (Bus Routes and Collectors) Streets and then Priority III (Residential) Streets. However, the Contract Administrator may direct otherwise and the Contractor shall conform to all such directives, either oral or written.
- E2.1.21 Backlane and sidewalk snow clearing operations will normally be undertaken concurrently with street and street priority operations. However, the Contract Administrator may direct otherwise and the Contractor shall conform to all such directives.
- E2.1.22 The Contractor shall respond immediately to rectify snow clearing deficiencies which generate citizens' complaints. If in the opinion of the Contract Administrator, the response is inadequate, then the City shall have the option of performing the necessary Work and the costs of such Work shall be borne by the Contractor.
- E2.1.23 The Contractor shall coordinate residential plowing location to minimize conflicts with the Garbage / Recycling collection.
- E2.2 **PRIORITY I (REGIONAL) STREETS (See Appendix "A")**
- E2.2.1 Snow clearing activities on Priority I streets includes:
- (a) Full width snow clearing and hauling.
 - (b) Curb lane snow clearing
 - (c) Truck plow snow clearing.
 - (d) Interim plowing during major snowfalls.

(e) Other winter maintenance Work.

E2.2.2 Snow clearing on Priority I streets may be required after:

- (a) A recent accumulation of 3 cm or more of snowfall.
- (b) Poor street conditions caused by less than 3 cm of recent snow accumulation accompanied by snow drifting.
- (c) A gradual accumulation of snowfall results in poor street conditions.

E2.2.3 Priority I streets, shall be completed within a twenty-four (24) hour period for a clearing operation following the time of commencement designated by the Contract Administrator.

E2.2.4 Snow clearing on the Priority I street system shall normally be undertaken during the night shift (1900 hours to 0700 hours) unless otherwise directed. Some Priority I streets in outlying areas may be cleared prior to 1900 hours as shown in Appendix "E".

E2.2.5 Priority I streets shall be cleared to bare pavement over the full pavement width and plowed to the sides as shown in Appendix "A". The Contractor shall wing back snow windrows in order to create the required storage and perform the 0.6m median cut as directed by the Contract Administrator.

E2.2.6 The Contractor shall clear and haul away snow from the street and lane intersections, crosswalks, corridors, railroad crossings, private approaches and bus stops on those Priority I streets noted in Appendix "A" during the initial clearing operation. The snow must be hauled away immediately where there is insufficient site storage. The snow shall be removed to within 300 mm of the existing ground elevation. Where there is on-site storage within the street right-of-way, and the on-site storage will not cause interruptions to either vehicular or pedestrian traffic or create a safety hazard, the snow may be stored for up to seventy-two (72) hours from the time commencement designated by the Contract Administrator for a snow clearing operation on Priority I, II and III streets and up to thirty-six (36) hours for a snow clearing operation on Priority I and II streets and bus loops. Snow from bus stops on those Priority I streets listed for hauling away in Appendix "A" shall be hauled away immediately and hauling completed by 0700 hours on the day following the commencement.

E2.2.7 Payment for the full width snow clearing and hauling away of snow on Priority I streets will be made at the unit price Bid per lane kilometre and all the Work herein described shall be considered as incidental to the Contract and no further compensation will be considered.

E2.3 PRIORITY II (BUS ROUTES/COLLECTORS) STREETS (See Appendix "B")

E2.3.1 Snow clearing activities on Priority II streets includes:

- (a) Full width snow clearing and hauling.
- (b) Curb lane snow clearing
- (c) Truck plow snow clearing.
- (d) Interim plowing during major snowfalls.
- (e) Other winter maintenance Work.

E2.3.2 Snow clearing on Priority II streets may be required after:

- (a) A recent accumulation of 5 cm or more of snowfall.
- (b) Poor street conditions caused by less than 5 cm of recent snow accumulation accompanied by snow drifting.
- (c) Gradual accumulation of snowfall results in poor street conditions.

- E2.3.3 Priority II streets shall be completed within a twenty-four (24) hour period for a clearing operation of a recent accumulation following the time of commencement designated by the Contract Administrator.
- E2.3.4 When Priority II streets are plowed within the same snow clearing operation as Priority I streets, the Priority II streets shall be completed within thirty-six (36) hours following the commencement time for the snow clearing operation.
- E2.3.5 Priority II streets shall be cleared to bare pavement over the full pavement width. The Contractor shall wing back snow windrows in order to create the required storage and perform the 0.6m median cut as directed by the Contract Administrator. Where the Contractor is unable to meet the requirements of this specification due to parked vehicles, he shall arrange for a sign and tow operation with City forces to facilitate completion in these areas.
- E2.3.6 Payment for the full width snow clearing of Priority II streets will be made at the unit price Bid per lane kilometre and all the Work herein described shall be considered as incidental to the Contract and no further compensation will be considered.
- E2.4 PRIORITY III (RESIDENTIAL) STREETS (See Appendix "C")
- E2.4.1 Residential streets shall normally be cleared after:
- (a) A recent snow accumulation of 10 cm or more.
 - (b) Poor street conditions caused by less than 10 cm of recent snow accumulation accompanied by snow drifting.
 - (c) Gradual accumulation of snowfall resulting in poor street conditions.
- E2.4.2 Residential streets shall normally be cleared after Priority I and II streets.
- E2.4.3 Priority III streets shall be completed within a thirty-six (36) hour period following the commencement time designated by the Contract Administrator.
- E2.4.4 When Priority III streets are plowed within the same clearing operation as Priority II streets, the Priority III streets shall be completed within 60 hours following the commencement time for the clearing of the Priority II streets.
- E2.4.5 When Priority III streets are plowed within the same snow clearing operation as Priority I and II streets, the Priority III streets shall be completed within seventy-two (72) hours following the commencement time for the snow clearing of the Priority I and II streets.
- E2.4.6 Priority III streets shall be cleared to bare pavement over the full pavement width. The Contractor shall wing back snow windrows in order to create the required storage as directed by the Contract Administrator. Where the Contractor is unable to meet the requirements of this specification due to parked vehicles, he shall arrange for a sign and tow operation with City forces to facilitate completion in these areas.
- E2.4.7 Notwithstanding the requirements of this specification, abnormal snow and ice conditions may make it impossible to adequately clear the Priority III streets to bare pavement. On those occasions, the Contract Administrator shall determine the level of snow clearing required and the time required to complete the operation.
- E2.4.8 Payment for the full width snow clearing of Priority III streets will be made at the unit price Bid per lane kilometre and all the Work herein described shall be considered as incidental to the Contract and no further compensation will be considered.

- E2.4.9 The Contractor shall provide to the Contract Administrator the start location and the area of streets to be completed in each 12 hour shift. This information shall be provided within 2 hours of being notified of the Priority 3 plow for the initial shift and 4 hours prior to each shift thereafter. The information will be used for the Residential Overnight Parking Ban to notify residents when their street is scheduled to be plowed and for enforcement purposes.
- E2.5 BACKLANES (see Drawing 1)
- E2.5.1 Backlanes shall normally be cleared after:
- (a) A recent snow accumulation of 5 cm or more
 - (b) Poor backlane conditions caused by less than 5 cm of recent snow accumulation accompanied by snow drifting
 - (c) Gradual accumulation of snowfall resulting in poor backlane conditions
- E2.5.2 Backlanes shall normally be cleared concurrently with Priority I and II street snow clearing operations and shall normally be undertaken during the day shift (0700 hours to 1900 hours) unless otherwise directed by the Contract Administrator.
- E2.5.3 Backlanes shall be completed within a 48 hour period following the commencement time designated by the Contract Administrator.
- E2.5.4 Backlanes shall be cleared to a width of 3m and maintained to a compacted snow surface as defined in D3.
- E2.5.5 Payment for backlane snow clearing will be made at the unit price bid per kilometre and all work herein described shall be considered incidental to the contract and no further compensation will be considered.
- E2.6 SIDEWALKS (see Drawing 1)
- E2.6.1 Sidewalks shall normally be cleared after:
- (a) A recent snow accumulation of 5 cm or more for sidewalks on Priority II streets and 8 cm or more for sidewalks on Priority III streets
 - (b) Poor sidewalk conditions caused by less than 5 cm of recent snow accumulation accompanied by snow drifting
 - (c) Gradual accumulation of snowfall resulting in poor sidewalk conditions
- E2.6.2 Sidewalks on Priority II streets shall normally be cleared concurrently with Priority II street clearing operations.
- E2.6.3 Sidewalk snow clearing on Priority II streets shall be completed within a 36 hour period following the commencement time designated by the Contract Administrator. Sidewalk snow clearing on Priority III streets shall be completed within 120 hours of the commencement time designated by the Contract Administrator.
- E2.6.4 Sidewalks in the immediate vicinity of schools, hospitals and seniors complexes shall be given their highest priority when scheduling and routing sidewalk clearing operations. Where a senior complex is situated on a Priority III street, the sidewalk to the most logical Priority I or II street shall be cleared within 36 hour of any walk clearing operation.
- E2.6.5 Sidewalks shall be cleared to a width of 1.5m and maintained to a compacted snow surface.
- E2.6.6 Payment for sidewalk snow clearing will be made at the unit price bid per kilometre and all work herein described shall be considered incidental to the contract and no further compensation will be considered.

E3. HOURLY EQUIPMENT SERVICES

E3.1 GENERAL

- E3.1.1 Snow clearing equipment shall be supplied on an hourly basis when requested by the Contract Administrator for winter maintenance activities between storms and opening up streets, backlanes and sidewalks and keeping them open during major snow storms and blizzards.
- E3.1.2 Snow hauling equipment shall be supplied on an hourly basis when requested by the Contract Administrator for the loading and hauling away of snow between major snowfalls.
- E3.1.3 Any equipment supplied by the Contractor on an hourly basis shall meet the following specifications:
- (a) **Semi-Trailer Dump Trucks:** Category 3 GVW 36,500 kg
 - (b) **J2 Class Loaders:** Rubber Tired - 4 Wheel Drive Loader,

SAE Net	Horsepower	Minimum 75 H.P.
Operating Weight	15,000-20,000 lbs.	
Bucket Size	1.5 – 2.25 cu. yd.	
 - (c) **J3 Class Loaders:** Rubber Tired - 4 Wheel Drive Loader

SAE Net	Horsepower	Minimum 100 H.P.
Operating Weight	21,000-28,000 lbs.	
Bucket Size	2.25 – 3.0 cu. yd.	
 - (d) **J5 Class Loaders:** Rubber Tired - 4 Wheel Drive Loader

SAE Net	Horsepower	Minimum 145 H.P.
Operating Weight	28,000-38,000 lbs.	
Bucket Size	3.0 cu. yd. and over	
 - (e) **K4 Class Motor Graders:** Minimum 140 Flywheel Horsepower
 - (f) **K5 Class Motor Graders:** Minimum 160 Flywheel Horsepower
 - (g) **Truck Plows:** As specified in E3.2 and E4.7 of the Specifications
- E3.1.4 Contract supervision shall be as specified in E6.
- E3.1.5 The Contract Administrator may request snow clearing equipment on an hourly basis up to the number and type of pieces of equipment specified in E4.
- E3.1.6 The Contractor shall respond to the assigned location within two hours of official notice from the Contract Administrator or be subject to penalties as outlined in E14.
- E3.1.7 The Contractor shall fill out approved Work tickets showing hours of Work, type of equipment, equipment model and serial number. All Work tickets must be signed by the City inspector and a representative of the Contractor to be valid.
- E3.1.8 Payment for hourly equipment will be made based on the hours actually worked and the unit price per hour shown in Form B: Schedule of Prices. There will be no overtime premium for Work under this Contract.

E3.2 TRUCK PLOW CLEARING OPERATIONS

- E3.2.1 Notwithstanding the requirements of E2 of the Specifications, the clearing of snow using truck plows shall be in accordance with the following:
- (a) Truck plowing on Priority I, Priority II and Priority III streets may be required during and after any measurable snowfall. The decision to perform a snow clearing operation will be made by the Contract Administrator or his designate.
 - (b) Priority I (Regional) streets shall normally receive the highest priority for snow clearing followed by Priority II (Bus Routes and Collectors) streets and then Priority III (Residential) streets. However, there may be circumstances when Collectors and Bus Routes would be cleared before Regional streets. This shall only be done when so directed by the Contract Administrator.
 - (c) Priority I, Priority II and Priority III streets shall be cleared to bare pavement over the full width, except at isolated locations where parked cars make the plowing of the curb lane(s) impossible.
 - (d) Notwithstanding E7 the Contractor may be directed to clear only the travel lanes.
 - (e) Windrows at all intersections, crosswalks, corridors, railway crossings and private approaches shall be removed if the Contract Administrator or his designate deem that they present a hazard to traffic.
 - (f) Reasonable care shall be taken so that snow from the truck plow clearing operations shall not be deposited in sidewalk areas. Snow deposited on the sidewalk areas unnecessarily shall be removed by the Contractor at his expense.
 - (g) Snow may be deposited on centre medians when allowed by the Contract Administrator.

E4. EQUIPMENT

- E4.1 The Contractor shall provide the following minimum quantity and type of equipment in first class working condition:
- (a) 8 motor graders;
 - (b) 10 loaders;
 - (c) 5 truck plows.
 - (d) 1 sidewalk snow plow;
 - (e) 1 sidewalk snow blower.
- E4.2 All equipment shall be made available for inspection by the Contract Administrator or his designate prior to the award of Contract.
- E4.3 The Bidder is not required to own the equipment at the time of the Submission Deadline. The Bidder shall, however, provide the Contract Administrator, within 72 hours of being requested, the name of the registered owner of each proposed piece of equipment and a copy of a binding contract, or option to purchase or to contract, for the use of the equipment for the duration of the Contract.

E4.4 LIGHTING

- E4.4.1 Each vehicle and each piece of equipment shall be provided with all of the necessary lighting prescribed by the motor vehicle laws of the Province of Manitoba.
- E4.4.2 Notwithstanding the generality of the foregoing, the Contractor shall ensure that all equipment is equipped with working lighting systems sufficient to facilitate the Work. At a minimum, all equipment must be equipped with the following lighting:
- (a) at least two headlights;

- (b) at least two rear running lights;
- (c) turning signals front and rear;
- (d) stop light at rear;
- (e) at least one flashing or oscillating blue or amber light, clearly visible in all directions (360 degrees);
- (f) if the machine is in excess of 2 metres wide, at least four clearance lights (one green or amber light on each side at the front, facing the front, and one red light on each side at the rear facing rear-ward).
- (g) All equipment must maintain proper lighting though out the entire shift or be removed from hired and contract work.

E4.5 IDENTIFICATION

- E4.5.1 All equipment shall be clearly labelled, indicating the Contractor's name and unit number. Letters and numbers used for identification purposes must be a minimum of 100 mm in height and positioned in such a manner as to be clearly visible when standing at either side of the machine.

E4.6 COMMUNICATION

- E4.6.1 At least one piece of equipment in a crew working in a specific area must have a means of two-way communications with the Contractor's Supervisor and office.

E4.7 TRUCK PLOWS

- (a) The truck plows shall be capable of providing a level of performance consistent with the front-mounted truck plows currently in use by the City.
- (b) The truck plows shall be equipped with a hydraulically reversible straight blade that will ride on the pavement surface.
- (c) The plow blade shall be suitable for clearing a minimum 2.4 m wide path when fully angled (approximately 40°).
- (d) The plow blade and/or cutting edges shall be spring loaded or flexible to allow deflection when an obstacle is encountered. This deflection shall cause the blade to raise to clear manholes, catch basins, curbs and other obstructions protruding above pavement, without damage.

E5. DRIVERS LICENSE FOR ALL HIRED HOURLY EQUIPMENT

- E5.1 The City requires that the Contractor's supervisor is to ensure all drivers and operators have the appropriate driver's license for all Hired Hourly and Contract Equipment supplied under this contract.

E6. CONTRACTOR'S SUPERVISION AND COMMUNICATION

- E6.1 The Contractor shall have a qualified Supervisor on duty during all snow clearing activities regardless of the type and magnitude of the operation. The Supervisor shall be able to attend, monitor and respond to all operational and equipment concerns throughout the contract area.
- E6.2 The Contractor's Supervisor shall have two-way communications with the Contractor's office and field crews, and continuously direct, coordinate and inspect the work of the field crews.
- E6.3 The Supervisor, or his designate, shall provide a means of two-way communications with City staff involved in the inspection of contract snow clearing operations. Failure by the Contractor

to supply two-way communication to the City staff by first call-out will result in the City furnishing such equipment and deducting costs from the Contract payment.

- E6.4 The Contractor shall have the capability of receiving facsimile transmission (fax machine) and shall supply the facsimile number to the Contract Administrator.

E7. EXTREME SNOWFALL AND BLIZZARD CONDITIONS

- E7.1 The Contractor shall provide snow clearing equipment to keep streets, sidewalks and backlanes open during the extreme snowfall event if requested by the Contract Administrator. The Contract Administrator shall evaluate field conditions and at his discretion, continue or terminate the hourly snow clearing operations.

- E7.2 Time utilized by the Contractor to keep streets, sidewalks and backlanes open during the snow storm shall not be part of the time limits established in E2.2, E2.3, E2.4 and E2.5.

- E7.3 During or after extreme snowfall and/or blizzards, the Contract Administrator may require that Regional and Collector streets, sidewalks and backlanes be opened using both Contract and City forces in order to open such streets and emergency routes as quickly as possible. The Contractor may be required to dispatch his equipment to work inside and outside the contract area with and under the direction of City forces.

- E7.4 Once notified by the Contract Administrator of the official start time for the formal snow clearing operations following extreme snowfall and/or blizzards the Contractor shall immediately initiate the snow clearing operation.

E8. QUANTITIES

- E8.1 Further to B8 of the Bidding Procedures, the estimated quantities identified on Form B: Schedule of Prices (Unit Price) for the clearing and hauling of snow on the Priority I, II and III street systems, sidewalks and backlanes are based on the following:
- (a) **Item No. 1 - Priority I (Regional) Street System:** The approximate quantity is based on 145.18 lane kms of street for one (1) clearing operation of 0-10 cm.
 - (b) **Item No. 2 - Priority II (Bus Routes and Collector) Street System:** The approximate quantity is based on 117.05 lane kms of street for three (3) clearing operations of 0-10 cm.
 - (c) **Item No. 3 - Priority III (Residential) Street System:** The approximate quantity is based on 214.31 lane kms of street for three (3) clearing operations of 0-10 cm.
 - (d) **Item No. 4 – Backlanes:** The approximate quantity is based on 17 linear kms of backlanes for 6 clearing operations of 0-10 cm.
 - (e) **Item No. 6 – Sidewalks (on PII Streets):** The approximate quantity is based on 47 kms of sidewalks for 8 clearing operations of 0-10 cm.
 - (f) **Item No. 7 – Sidewalks (on PIII Streets):** The approximate quantity is based on 17 kms of sidewalks for 3 clearing operations of 0-10 cm.
- E8.2 The total length of lane kilometres, as established by the Public Works Department, are provided in Appendix "A" - Priority I Street System, Appendix "B" - Priority II Street System, and Appendix "C" - Priority III Street System. Drawing 1 indicates the inventory of backlanes and of sidewalks in PI, PII and PIII streets. In the event that streets, backlanes or sidewalks are either added or deleted, then the total length shall be adjusted correspondingly for the purpose of measurement and payment.

E8.3 Appendix "D" showing the precipitation of snow based on the meteorological summary of the Environment Canada Atmospheric Environment Services for the last 40 years, is provided strictly for the information of Bidders.

E9. TRAFFIC MOVEMENT AND PARKING RESTRICTIONS

E9.1 After a significant snowfall, overnight parking may be restricted on all Priority I and Priority II streets with the declaration of the Major Snowfall Parking Ban. This By-Law, when declared by the Mayor, prohibits parking on Priority I and II streets between the hours of midnight and 06:00. The ban will normally last for twenty-four (24) hours but may be extended.

E9.2 During snow clearing and hauling operations, the Contractor shall take all reasonable measures to facilitate the movement of traffic in accordance with the Manual of Temporary Traffic Control.

E10. MEASUREMENT AND PAYMENT

E10.1 This section will govern payment for full width street clearing, backlane clearing and sidewalk clearing of snow and hauling services for snow removal performed by the Contractor which include:

- (a) Clearing and hauling services for snow after a recent accumulation of snow;
- (b) Clearing and hauling services after a gradual accumulation of snow where, in the opinion of the Contract Administrator, such clearing and hauling services are warranted;
- (c) Clearing and hauling services after a recent accumulation of snow combined with a gradual accumulation of snow; and
- (d) Maintenance snow clearing services between storms and keeping streets, sidewalks and backlanes open during major snow storms and/or blizzards on the streets specified in this Contract.

E10.2 In this Contract, each such direction by the Contract Administrator for clearing and hauling services for snow removal and the performance thereof by the Contractor shall be referred to as a "clearing operation".

E10.3 If there is additional precipitation before the expiration of the specified time period, the Contract Administrator will define the end of the most recent snowfall and will set another time limit based on the quantity of precipitation.

E10.4 Where in the opinion of the Contract Administrator the amount of snowfall and/or accompanying severe drifting conditions makes it impractical to complete the full width snow clearing, sidewalk clearing and backlane clearing operations with the Contractor's full complement of equipment and continuous effort, the Contract Administrator may, at his sole discretion, extend the time limits specified.

E10.5 Payment will be made for backlane and sidewalk clearing operations based on the unit price per kilometre. The payment for such clearing operations will be based on multiplying the unit bid price for the Item No. on Form B: Schedule of Prices (Unit Price) by the length in kilometres of backlanes and sidewalk cleared.

E10.6 The Contract Administrator will have the authority to determine whether any clearing and hauling operation constitutes a recent accumulation, a gradual accumulation or a combination of the two. The guideline to be utilized by the Contract Administrator for determining whether a clearing operation is a recent accumulation or a gradual accumulation will be that, where 5 cm or more of snow has fallen over the 48 hour period preceding the direction to commence clearing services, the accumulation will be considered a recent accumulation. Otherwise, the clearing operation will be considered a gradual accumulation.

- E10.7 Payment will be made for full width clearing and hauling operations on Priority I (Regional) Streets, Priority II (Collector) Streets, Priority III (Residential) streets based on the unit price per lane kilometre and a snow accumulation factor (F) which is dependent on the quantity of snowfall and the type of snow accumulation. The payment for all such clearing operations will be based on multiplying the unit price Bid (R) for items (1) to (3), on Form B: Schedule of Prices (Unit Price), as the case may be, by the length in kilometres cleared (L), as determined by the Contract Administrator, multiplied by the snow accumulation factor (F), as determined by the Contract Administrator; or Payment= R x L x F.
- E10.8 The snow accumulation for purposes of payment for a recent accumulation shall be the quantity of snow deemed to be cleared/hailed by the Contractor as determined by the Contract Administrator in accordance with this section. There may be hourly snow hauling, plowing and/or salting operations carried on by others on some portions of the street systems affected by this Contract. Therefore, the depth of the snow accumulation to be used for payment for the removal of a recent accumulation will be that portion of snow that has recently fallen immediately preceding the start of a clearing operation and during the said operation, but not including cleared or removed by others or by environmental processes, as determined solely by the Contract Administrator. The duration and depth of snowfall will be based on official reports from a weather consulting service. Notice of any dispute by the City arising from the amount of snow accumulation used to calculate payments for a recent clearing operation shall be forwarded to the Contract Administrator within 15 days of the City notifying the Contractor of the amounts used for payment for a given clearing operation. Failure by the Contractor to give notice of such dispute within the time specified shall preclude the Contractor from disputing the amount for which the City will pay.
- E10.9 No payment will be made for gradual accumulation after March 15 of the Contract year in the event that all of the gradual accumulation has completely melted and does not physically exist on the street at the time of a plowing operation initiated by a recent accumulation. This determination will be made by the Contract Administrator.
- E10.10 The snow accumulation factor will be determined by the appropriate formula based on the type of accumulation and the quantity of snowfall. The formula to be used to calculate the snow accumulation factor for each payment scenario are identified in the following table and are further detailed in the sections and examples following the table:

Type of Accumulation	Snowfall Measurement	Snow Accumulation Factor Calculation
(1) Recent	0-10.0 cm	$F = 1.000$
(2) Recent	Greater than 10.0 cm	$F = 1 + (0.90 \times (x - 10) / 10)$ where x is the number of centimetres of recent accumulation snowfall.
(3) Gradual	Up to but not including Dec. 15 of Contract year or since the preceding clearing operation, whichever is later.	$F = 1.000$ or $F = (0.30 \times y) / 10$, whichever value is greater, where y is the number of centimetres of gradual accumulation snowfall.
(4) Combination of recent and gradual	0-10.0 cm (x) of recent and y cm of gradual up to but not including Dec. 15 of Contract year or since the preceding clearing operation, whichever is later.	$F = 1.000$ or $F = (x + (0.30 \times y)) / 10$, whichever value is greater, where x is the number of centimetres of recent accumulation snowfall and y is the number of centimetres of gradual accumulation snowfall.
(5) Combination of	Greater than 10.0 cm of recent (x)	$F = 1 + (0.90 \times (x - 10) / 10) + ((0.30 \times y) / 10)$,

recent and gradual	and y cm of gradual up to but not including Dec. 15 of Contract year or since the preceding clearing operation, whichever is later.	where x is the number of centimetres of recent accumulation snowfall and y is the number of centimetres of gradual accumulation snowfall.
--------------------	---	---

E10.10.1 For a clearing operation required as a result of a recent accumulation of ten (10) cm or less (0-10 cm), the accumulation factor (F) is 1.00. Payment will be made at the unit price Bid multiplied by the length in kilometres of traffic lanes cleared multiplied by 1.000.

Example: The total payment for a clearing operation after 9.3 cm of recent accumulation would be unit price Bid x lane kilometres x 1.000).

E10.10.2 For a clearing operation required as a result of a recent accumulation in excess of ten (10) cm, the accumulation factor will be determined by adding 1.000 (which is the factor for the first ten (10) cm) to 90% of the snow accumulation in excess of 10 centimetres divided by 10. Payment will be made at the unit price Bid multiplied by the length in kilometres of traffic lanes cleared multiplied by the snow accumulation factor.

Example: The snow accumulation factor for a clearing operation after 14.3 cm of recent accumulation, would be based on the calculation, $F=1+(0.9 \times (14.3-10)/10)=1.387$. The total payment for the clearing operation would be (unit price Bid x lane kilometres x 1.387).

E10.10.3 For a clearing operation required as a result of a gradual accumulation, the snow accumulation factor would be 1.000 or 30% of the gradual accumulation divided by 10, whichever value is greater. Payment will be made at the unit price Bid multiplied by the length in kilometres of traffic lanes cleared multiplied by the snow accumulation factor.

Example: Assume that, on February 28, the condition of the Priority III streets was such that a plowing operation was required and that no snowfall had occurred in the past 48 hours. The date of the last clearing operation was January 28 and 19 cm of snowfall (gradual accumulation) had fallen since that date. The snow accumulation factor would be 30% of 19 cm divided by 10, or $F = (0.30 \times 19) / 10 = 0.570$. Since the calculated factor is less than 1.000, the greater value of 1.000 would be used and the total payment for the clearing operation would be (unit price Bid x lane kilometres x 1.000).

E10.10.4 For a clearing operation required as result of a recent accumulation of 10.0 cm or less (0-10 cm) and where there has also been gradual accumulation measured up to but not including December 15 of the Contract year or since the immediately preceding clearing operation, whichever is later, the snow accumulation factor will be 1.000 or the value calculated by adding the recent accumulation to 30% of the gradual accumulation and dividing the sum by 10, whichever value is greater. Payment will be made at the unit price Bid multiplied by the length in kilometres of traffic lanes cleared multiplied by the snow accumulation factor.

Example: Assume that during the Contract year there has been a snowfall on January 20 of 5.0 cm with severe winds, and in the opinion of the Contract Administrator, there is need for a snow clearing operation. Assume further that 14.5 centimetres of snow has gradually accumulated between December 15th and the commencement of the recent accumulation on January 20th. The snow accumulation factor and payment would be calculated as follows:

- (i) The recent accumulation of 5.0 cm is added to 30% of the gradual accumulation of 14.5 cm and the sum divided by 10 or $F = (5.0+(0.30 \times 14.5)) / 10 = 0.935$. Since the calculated factor is less than 1.000, the total payment for the clearing operation would be (unit price Bid x lane kilometres x 1.000).

Assume that in the above scenario the snowfall on January 20th was 8.0 cm. Then the snow accumulation factor and payment would be calculated as follows:

- (ii) The recent accumulation of 8.0 cm is added to 30% of the gradual accumulation of 14.5 cm and the sum divided by 10 or $F = (8.0 + (0.30 \times 14.5)) / 10 = 1.235$. The total payment for the clearing operation would be (unit price Bid x lane kilometres x 1.235).

E10.10.5 For a clearing operation required as result of a recent accumulation of greater than 10.0 cm and where there has also been gradual accumulation measured up to but not including December 15 of the Contract year or since the immediately preceding clearing operation, whichever is later, the snow accumulation factor will be determined by adding 1.000 (which is the factor for the first ten (10) cm of recent accumulation) to 90% of the recent snow accumulation in excess of 10 centimetres divided by 10 and then adding 30% of the gradual accumulation and divided by 10. Payment will be made at the unit price Bid multiplied by the length in kilometres of traffic lanes cleared multiplied by the snow accumulation factor.

Example - Assume that during the Contract year there has been a snowfall on January 20 of 16.8 cm and, in the opinion of the Contract Administrator, there is need for a snow clearing operation. Assume further that 20.5 cm of snow has gradually accumulated between December 15th and the commencement of the recent accumulation on January 20th. The snow accumulation factor and payment would be calculated by adding 1.000 for the first 10 cm of recent accumulation to 90% of 6.8 cm (which is the recent snow accumulation in excess of 10 cm) divided by 10 and then adding 30% of 20.5 cm (which is the gradual accumulation) divided by 10, or $F = 1.000 + (0.90 \times (16.8 - 10) / 10) + ((0.30 \times 20.5) / 10) = 2.227$. The total payment for the clearing operation would be (unit price Bid x lane kilometres x 2.227).

- E10.11 Payment shall be made for snow clearing services, such as truck plowing or maintenance snow clearing between snow storms and snow clearing during major storms/blizzards, as specified in E3 of the Specifications at the hourly rate Bid per equipment class on Form B: Schedule of Prices (Unit Price), as the case may be, multiplied by the hours actually worked for each specific class as determined by the Contract Administrator.
- E10.12 Payment for wings, ice blades, and/or straight blades for Motor Graders engaged in a full width snow clearing operation shall be included in the unit price Bid per lane kilometre or kilometre respectively.
- E10.13 Those attachments specifically requested by the Contract Administrator or his designate will be compensated for at the same rate per hour as those specified in the "Hourly Rental Rate for Public Works Department for the 2008 to 2010 Snow Season".
- E10.14 The City shall guarantee to pay to the Contractor a minimum amount (referred to as the "guaranteed minimum amount") equal to 60% of the Bid price shown on Form B: Schedule of Prices (Unit Price).
- E10.14.1 Payment for Work done shall be as provided in E8 and all such payments shall be deducted from the guaranteed minimum amount.
- E10.14.2 On December 31st, all payments received by the Contractor under this Contract will be totalled and the total compared with 10% of the Total Bid Price. If the total of the payments received is less than 10% of the Total Bid Price, then the difference between the aforesaid figures will be paid to the Contractor as an advance on the guaranteed minimum amount. The amount of the advance will be set off against subsequent payments for work done by the Contractor.

- E10.14.3 On February 28th, all payments received by the Contractor under this Contract for Work done and as an advance on the guaranteed minimum amount will be totalled and that total compared with 35% of the Total Bid Price. If the total of the payments received is less than 35% of the Total Bid Price, then the difference will be paid to the Contractor as an advance on the guaranteed minimum amount. The amounts of any advances received by the Contractor will be set off against subsequent payments for Work done by the Contractor pursuant to the Contract.
- E10.14.4 At the conclusion of the Contract year, all payments received by the Contractor or under this Contract for Work done or as an advance on the guaranteed minimum amount will be totalled and that total compared with the guaranteed minimum amount. Only when the total of the payments received is less than the guaranteed minimum amount will additional monies be payable by the City to the Contractor under the terms of this Contract.
- E10.14.5 The Contractor will not be compensated for any inconvenience and costs which may result from excavation Work on the streets, sidewalks or backlanes, the parking of vehicles on the roadway, vehicle movement, or any other obstruction to his Work.
- E10.14.6 The Contractor shall note that on the Regional Streets System portion of this Contract, the unit price Bid shall include the cost of all necessary hauling for Priority I (Regional) Streets as specified in the Contract.
- E10.14.7 The Contractor shall note that on the P1 and P2 street system portion of this Contract, the unit price bid shall include the cost of the 0.6m median cut as specified in the contract.
- E10.14.8 It is the City of Winnipeg's intent to hold back five (5) percent of progress estimates for all Work performed under this Contract as a damage deposit relating to E13 of the Specifications. These funds will be released when damages are rectified in accordance with E13.

E11. ANNUAL REVIEW – INFLATIONARY ADJUSTMENT

- E11.1 The unit prices specified on Form B: Prices will be adjusted on the first Contract anniversary date, and subsequent anniversary dates based on the percentage increase or decrease in unit prices for the Contract year from the All-items Consumer Price Index for Winnipeg, normally referred to by Statistics Canada as Table 326-0001. The calculation of the adjustment will be based on October 1 of the previous year to October 1 of the current year. The first inflationary adjustment shall occur on October 1, 2010. The maximum annual adjustment shall not exceed 10%.
- E11.2 The index used will be that prepared by Statistics Canada. Since the index may not be available until some time after the adjustment date, the adjustment will be retroactive.

E12. PRICE ADJUSTEMENT – FUEL COSTS

- E12.1 Notwithstanding C11.2, price adjustments for unforeseen fuel cost changes will include increases or decreases in the price of diesel fuel.
- E12.2 The City of Winnipeg will determine the Base Price of fuel costs based on the average diesel fuel price for the month of July of 2009 charged to the Streets Maintenance Division by the City of Winnipeg Fleet Management Agency.
- E12.3 Price adjustments will be assessed on October 1 and on January 1 of each contract year.
- E12.3.1 Price adjustments will only be made for any fuel price increase or decrease in excess of three percent (3%).
- E12.3.2 The actual diesel fuel price (Actual Price) will be determined on the dates indicated in E12.3 using the average fuel price of the previous month (e.g. for October 1 the average

price for the month of September will be used and for January 1 the average price for December will be used).

- E12.4 Price adjustments will be applied to seventeen percent (17%) of the Unit Price bid by the Contractor on all items, which is the portion of the bid price that is attributable to fuel.
- E12.4.1 If fuel prices increase by more than three percent (3%) of the Base Price identified in E12.2, then a price adjustment for fuel will be made and paid for based on the quantity of eligible work on each progress estimate following the date of adjustment in accordance with the following formula:
- $$\text{Price Adjustment} = (\text{Actual Price} - (1.03 \times \text{Base Price})) \times (.17 \times \text{Unit Price})$$
- E12.4.2 If fuel prices decrease by more than three percent (3%) of the Base Price, then a price adjustment for fuel will be made and paid for based on the quantity of eligible Work on each progress estimate following the date of adjustment in accordance with the following formula:
- $$\text{Price Adjustment} = ((0.97 \times \text{Base Price}) - \text{Actual Price}) \times (.17 \times \text{Unit Price})$$

E13. DAMAGE TO PUBLIC AND PRIVATE PROPERTY

- E13.1 The Contractor will be held responsible for any damage to City or private property sustained as a result of his snow clearing operation. Prior to commencement of the first clearing operation, the Contractor shall document and/or photograph all existing damage to pavements, curbs, utilities, street furniture, street signs, parking meters, etc., and shall provide this information to the City for verification.
- E13.2 The Contractor shall immediately report damages to City or private property to the Contract Inspector.
- E13.3 Any damage to pavements, boulevards, trees, etc. that in no way present a hazard to either pedestrian or vehicular traffic shall be reported to the Contract Administrator and rectified by the Contractor in accordance with City of Winnipeg specifications prior to June 30 following the snow clearing season. Damages not rectified by June 30 may be rectified by the City or its agents and all costs shall be borne by the Contractor and shall be deducted from monies owing.
- E13.4 The Contractor shall repair all curbs damaged as a result of snow clearing operations. The repairs will be conducted at the exact locations at which the curb damage was assessed. The Contractor shall remove and dispose of any loose curb material prior to April 15th each year.
- E13.5 Any damage to street appurtenances such as, but not limited to, street light standards, signal lights, hydrants, valve boxes, railway signal arm protective devices shall be rectified immediately. If in the process of clearing snow from a street, the Contractor dislodges a manhole frame, it must be restored immediately. Failure to rectify damages immediately may result in the damages being rectified by the City or its agents and the associated costs borne by the Contractor. In the event that the manhole frame is damaged beyond replacement, the Contractor shall immediately install temporary warning devices to protect pedestrians and vehicles and notify the City at 311, so that a repair can be made by City forces. The costs for such repair will be borne totally by the Contractor.
- E13.6 The Contractor shall repair any sod damage caused by his snow clearing operations with top soil and seed or with sod as directed by the Contract Administrator. All restorations shall be in accordance with City of Winnipeg Standard Construction Specifications.
- E13.7 The Contractor shall replace with equal, any recycling bins or refuse containers destroyed, lost or misplaced by his operations at least (1) day prior to the next refuse day cycle.

E14. PENALTIES

- E14.1 Where the Contractor does not satisfactorily complete the Work on Priority I, II or III streets, sidewalks or backlanes in accordance with the time and quality requirements specified in E2, the Contractor shall be assessed a penalty.
- E14.1.1 For Priority I streets, the penalty shall be in the amount of \$1,500.00 or an amount equal to fifty percent (50%) of the unit price Bid per lane kilometre multiplied by the lane kilometres not satisfactorily completed multiplied by the snow accumulation factor, whichever is greater.
- E14.1.2 For Priority II and Priority III streets, the penalty shall be in the amount of \$1,500.00 or an amount equal to twenty-five percent (25%) of the unit price bid per lane kilometre multiplied by the lane kilometres not satisfactorily completed multiplied by the snow accumulation factor, whichever is greater.
- E14.1.3 For sidewalks and backlanes, the penalty shall be in the amount of \$1,500.00 or an amount equal to twenty-five percent (25%) of the unit price Bid per kilometre times the kilometres not satisfactorily completed, whichever is greater for each backlane.
- E14.1.4 Streets, sidewalks and backlanes that the Contract Administrator deems to be deficient in whole and not in part will be considered incomplete and may be subject to the above penalty.
- E14.2 Where the Contractor does not supply up to the minimum quantity and type of equipment identified in E4 within two hours as outlined in E3.2 of the Specifications, the Contractor shall be assessed a penalty of five hundred dollars (\$500.00) per piece of equipment per call out below the minimum number as specified in E4. The minimum requirement shall apply throughout the duration of the operation from call-out to release of equipment.
- E14.3 Where the Contractor does not satisfactorily perform any snow clearing operation in accordance with the requirements of E2, particularly in reference to the quality of the Work following an inspection by the Contract Administrator the Work shall be declared a deficiency. The Contractor shall be requested to rectify the portion of streets, sidewalks or backlanes found to be unsatisfactory in quality within 24 hours of notification or in a time period to be agreed to by the Contract Administrator. Failure to respond may result in the City performing the required Work and charging the cost of such Work back to the Contractor.
- E14.4 Any performance deficiency related to E2 such as, but not limited to, depositing snow in unauthorized locations, depositing snow on private property, or not removing snow windrows from approaches, shall be rectified immediately by the Contractor. Failure to respond will result in the City or its agent rectifying the deficiencies and charging the costs back to the Contractor.
- E14.5 Where the Contractor fails to replace recycling bins or refuse containers as described in E13.7, the City will replace these items and assess a penalty of \$100.00 per item.

PART F - APPENDICES

APPENDIX A – EAST AREA (SOUTH) PRIORITY I

Street	From	To	Where to Plow	Kms of Street	No. of Lanes	No. of Lane Kms
Archibald	Desalaberry	S. End/Subway	B/S	0.18	5	0.91
Archibald*	South End/Subway	Elizabeth Rd.	E/S	3.71	4, 3	14.62
Archibald	Elizabeth	Fermor	B/S	1.77	4	7.22
Dakota	St. Mary's	Abbotsford	B/S	1.04	2, 4	6.20
Dakota	Abbotsford	Paddington	B/S	1.62	4	6.48
Dakota	Paddington	Aldgate	B/S	1.29	2	2.58
Dunkirk Dr/Kingston Row/Churchill Interchange			Side	2.12	1, 2	2.71
Dunkirk	Jubilee	St. Mary's Rd.	B/S	2.97	4	12.98
Fermor*	Dunkirk	Plessis	B/S	7.07	4	32.48
Main*	Stradbrook	Broadway	B/S	0.63	8	5.55
St. Mary's*	Stradbrook	Bishop Grandin	B/S	6.44	4, 5, 6	34.29
St. Mary's	Bishop Grandin	Perimeter	B/S	4.43	2, 4	18.76
Bus Loop	St. Mary's	Avalon	B/S	0.10	2	0.20
Bus Loop	Lagimodiere	Peterson	B/S	0.10	2	0.20
				TOTAL PI		145.18

* Snow cleared from street and lane intersections, pedestrian crosswalks and corridors, private approaches, railway crossings and bus stops to be hauled away when street is cleared.

APPENDIX B – EAST AREA (SOUTH) PRIORITY II

St	From	To	Where to Plow	Kms of St	No. of Lanes	No. of Lane Kms
Autumnwood Drive	Drake Bv	Fermor Avenue	B/S	1.83	3, 4	5.81
Beaverhill Bv	Fermor Avenue	Park Terrace Drive (N/Leg)	B/S	0.36	4	1.44
Beaverhill Bv	Park Terrace Drive (N/Leg)	Willowlake Crescent	B/S	2.40	2, 3	6.70
Betournay Street	Lagimodiere Bv	Autumnwood Drive	B/S	0.98	3	2.94
Blue Mountain	Royal Park	Royal Mint Dr	B/S	0.55	2	1.10
Burmac Road	Lagimodiere Bv	Capston Road	B/S	0.63	3	1.89
Burning Glass Rd	Sage Creek Bv	Red Moon Rd S. Leg	B/S	0.52	2	1.04
Capston Road	Lagimodiere	Cliffwood Drive	B/S	0.29	2, 4	0.78
Comanche Road	Rue Archibald	Seine River	B/S	0.60	2	1.20
Cottonwood Road	Lagimodiere Bv	Rue Archibald	B/S	1.98	3, 4	6.09
Crestwood Crescent	Westmount Drive	Autumnwood Drive	B/S	0.96	2	1.92
Dawson Rd S	Royal Mint Dr	Fermor Avenue	B/S	0.32	2	0.64
De La Seigneurie Bv	Bishop Grandin Bv	Nordstrom	B/S	2.24	3,4	8.38
Debourmont Avenue	Maginot Street	Autumnwood Drive	B/S	0.69	2	1.38
Des Hivernants Bv	Sage Creek Bv	Warde Av	B/S	1.46	2	2.92
Desjardins Drive	De La Seigneurie Bv	Island Lakes Drive	B/S	0.60	3	1.80
Drake Bv	Elizabeth RD	Cottonwood Road	B/S	1.30	3	3.89
Drake Bv	Promenade Burnet	Elizabeth RD	B/S	0.36	3	1.09
Dussault Avenue	Betournay Street	Cottonwood Road	B/S	0.46	2	0.92
East Mint Pl	Lagimodiere	Royal Mint Dr	B/S	0.18	4	0.72
Edgewater Drive	Beaverhill Bv	Lakewood Bv	B/S	0.98	2	1.96
Elizabeth Road	Speers Road	Rue Archibald	B/S	1.49	3	4.47
Harper Av	Howden Rd	Elizabeth Road	B/S	0.17	2	0.34
Howden Rd	Betournay Street	Harper Av	B/S	0.67	2	1.34
Ironweed Rd	Tallgrass Cr	Des Hivernants Bv	B/S	0.12	2	0.24
Island Lakes Drive	De La Seigneurie Bv	Island Shore Bv	B/S	1.16	2, 3	3.25
Island Shore Bv	Bishop Grandin	De la Seigneurie	B/S	2.12	2, 3, 4	6.24
Lafrance Ln	Burning Glass Rd	Des Hivernants Bv	B/S	0.22	2	0.44
Lakewood Bv	Fermor Avenue	Bishop Grandin Bv	B/S	1.81	2, 3, 4	5.59

Lomond Bv	Paterson St	Paterson St	B/S	0.67	2	1.34
Maginot Street	Lagimodiere Bv	Spears	B/S	0.20	4	0.80
Maginot Street	Spears	Debourmont Avenue	B/S	0.52	2	1.04
Meadowbrook Road	Lakewood Bv	Pebble Beach Road	B/S	0.32	2	0.64
Newcroft Road	Shamrock Drive	Cliffwood Drive	B/S	0.37	2	0.74
Niakwa Rd.	Royal Salinger Rd.	Seine River	B/S	0.56	2	1.12
Niakwa Road	Pebble Beach Road	Archibald Street	B/S	0.33	2	0.66
Paterson Street	Lagimodiere Bv	Westmount Drive	B/S	0.87	2, 3	2.41
Pebble Beach Road	Niakwa Road	Willowlake Crescent	B/S	0.95	2	1.90
Royal Mint Dr	Dawson	Royal Park (North Leg)	B/S	1.52	2, 3	4.13
Royal Mint Dr	Dawson	Fermor Avenue	B/S	0.12	2, 3	0.32
Sage Creek Bv	Lagimodiere Bv	Des Hivernants Bv	B/S	0.74	2,4	2.05
Shamrock Drive	Newcroft Road	Beaverhill Bv	B/S	0.45	2	0.90
Shorehill Dr	Bishop Grandin	St Anne's	B/S	2.75	3, 4	9.25
Southside	Shorehill	Bridgetown	B/S	0.64	3	1.92
Speers Road	Cottonwood Road	Crestwood Cres.	B/S	0.47	2	0.94
Speers Road	Maginot Street	Betournay Street	B/S	0.89	2	1.78
Vermillion Road	Beaverhill Bv	Lakewood Bv	B/S	1.22	2, 3	3.25
Warde Av	Des Hivernants Bv	Des Hivernants Bv	B/S	0.03	2	0.06
Waterfront	SL Island Shore	Desjardin	B/S	0.61	2	1.22
Westmount Drive	Cottonwood Road	Fermor Avenue	B/S	0.55	3	1.65
Willow Point Rd	Pebble Beach Rd	Willowlake Crescent	B/S	0.56	2	1.12
Willowlake Crescent	Lakewood Bv	Beaverhill Bv	B/S	1.05	1	1.05
Wood Sage Cr	Des Hivernants Bv	Wood Sage Cr	B/S	0.12	2	0.24
				TOTAL P2		117.05

APPENDIX C – EAST AREA (SOUTH) PRIORITY III

St	From	To	Where to Plow	Kms of St	No. of Lanes	No. of Lane Kms
Abington	SL Beaverhill	South End	B/S	0.10	2	0.20
Agate	WL Drake	WL Drake	B/S	0.35	2	0.70
Alderwood	EL Drake	SL Elizabeth	B/S	0.31	2	0.62
Almond	EL Drake	EL Drake	B/S	0.37	2	0.74
Appleby Cove	Lakewood	West End	B/S	0.05	2	0.10
Applewood	EL Drake	NL Autumnwood	B/S	0.21	2	0.42
Argonne	WL Drake	WL Drake	B/S	0.38	2	0.76
Arpin Bay	Pauline Boutal	Pauline Boutal	B/S	0.34	2	0.68
Arundel	SL Elizabeth	SL Elizabeth	B/S	0.52	2	1.04
Ashwood Cove	WL Sweetwater	West End	B/S	0.03	2	0.06
Aspen	WL Grover Hills	West End	B/S	0.04	2	0.08
Aubin Dr	Orchard Hill Dr	Shorehill	B/S	0.39	2	0.78
Autumnwood	WL Drake	West End	B/S	0.16	3	0.48
Barberry	EL Drake	SL Autumnwood	B/S	0.31	2	0.62
Baudoux	EL Speers	East End	B/S	0.23	2	0.46
Bayshore	WL Beaverhill	W/End Beaverhill	B/S	0.04	2	0.08
Baywater	NL Beaverhill	NL Beaverhill	B/S	0.03	2	0.06
Beaudry By	Shorehill	Shorehill	B/S	0.35	2	0.70
Beaupre Bay	WL Charbonneau	NL Gauvreau	B/S	0.29	2	0.58
Beaverhill Bv	Service Bay	W/S S/Grover Hills	B/S	0.06	2	0.12
Bedard Cr	Shorehill	Highridge Rd	B/S	0.25	2	0.50
Bellington Pl.	Southbridge	North End	B/S	0.07	2	0.14
Bentwood	WL Drake	WL Drake	B/S	0.35	2	0.70
Berkshire	WL Drake	WL Drake	B/S	0.66	2	1.32
Bernier	EL Speers	EL Speers	B/S	0.52	2	1.04
Bibeau	EL Dussault	EL Dussault	B/S	0.76	2	1.52
Birch	EL Drake	NL Cottonwood	B/S	0.25	2	0.50
Bittersweet	EL Drake	EL Drake	B/S	0.41	2	0.82
Black Pearl Cove	Island Lakes Dr.	Island Lakes Dr.	B/S	0.14	2	0.28

Blackberry	EL Drake	EL Drake	B/S	0.52	2	1.04
Bleau	SL Dugas	NL Elizabeth Rd.	B/S	0.09	2	0.18
Blue Stem Cv	Blue Mountain	S. End	B/S	0.07	2	0.14
Blueberry	WL Drake	WL Drake	B/S	0.34	2	0.68
Bluewater	EL Cherwell	WL Willowlake	B/S	0.68	2	1.36
Bluewater	Bluewater	Beaverhill	B/S	0.19	2	0.38
Boiselle Bay	SL Island Lakes	SL Island Lakes	B/S	0.28	2	0.56
Bonavista Pl.	SI Vermillion	West End	B/S	0.08	2	0.16
Boulder	WL Drake	NL Cottonwood	B/S	0.36	2	0.72
Bounty Bay	Island Lakes Dr.	South End	B/S	0.08	2	0.16
Brasswell By	Wildfire	Wildfire	B/S	0.33	2	0.66
Breakwater Cove	SL Island Shore	Shore South End	B/S	0.10	2	0.20
Brebeuf	NL Cottonwood	WL Dussault	B/S	0.22	2	0.44
Breland By	Wilmington	Wilmington	B/S	0.25	2	0.50
Brereton	SL Vermillion	EL Clearwater	B/S	0.24	2	0.48
Breton	Southside	East End	B/S	0.09	2	0.18
Brian Monkman By	Island Shore	De La Seigneurie	B/S	0.40	2	0.80
Briarwood	SL Boulder	NL Cottonwood	B/S	0.20	2	0.40
Bridgetown	Southside	Shorehill	B/S	0.67	2	1.34
Bridgeway Cr	John Bruce	Shorehill	B/S	0.45	2	0.90
Bromton / Agincourt	SL Beaverhill	South End	B/S	0.16	2	0.32
Brookhaven	WL Lakewood	WL Lakewood	B/S	0.57	2	1.14
Bunton CT	Aubin Dr	North End	B/S	0.05	2	0.10
Burke Bay	Southside Dr	Southside Dr	B/S	0.37	2	0.74
Burning Bush	EL Drake	EL Drake	B/S	0.48	2	0.96
Burntwood	EL Lakewood	NL Beaverhill	B/S	0.31	2	0.62
Bursill	WL Newcombe	EL Newcombe	B/S	0.21	2	0.42
Buttonwood	WL Drake	WL Drake	B/S	0.36	2	0.72
Camirant Cr.	Island Lakes	Island Lakes	B/S	0.61	2	1.22
Canberra	SL Cottonwood	EL Autumnwood	B/S	0.34	2	0.68
Capston Road	Service Road	S/S E/Cliffwood Drive	BS	0.08	2	0.16
Captains Way	Ebb Tide Dr.	Pamela Rd.	B/S	0.30	2	0.60
Carnaby Place	EL Orchard Lane	East End	B/S	0.05	2	0.10

Carolyn	EL Ormiston Rd.	East End	B/S	0.08	2	0.16
Cascade	EL Autumnwood	EL Autumnwood	B/S	0.48	2	0.96
Cassin	EL De La Seigneurie	EL De La Seigneurie	B/S	0.54	2	1.08
Causeway Bay	Pauline Boutal Crescent	Pauline Boutal Crescent	B/S	0.20	2	0.40
Charbonneau	South of Gauvreau RD	Island Shore BLVD	B/S	0.81	2	1.62
Chatsworth	NL Parkgrove	North End	B/S	0.05	2	0.10
Chenier Bay	NL Island Lakes	NL Island Lakes	B/S	0.21	2	0.42
Cherokee	NL Comanche	NL Comanche	B/S	0.40	2	0.80
Cherrier St.	West Limit	Archibald	B/S	0.27	2	0.54
Cherry	SL Cottonwood	WL Autumnwood	B/S	0.38	2	0.76
Cherwell	NL Beaverhill	SL Bluewater	B/S	0.25	2	0.50
Chippawa	SL Comanche	SL Comanche	B/S	0.20	2	0.40
Clarendon	NL Royal Salinger	WL Pebblebeach	B/S	0.26	2	0.52
Clearwater	SL Vermillion	SL Vermillion	B/S	0.70	2	1.40
Cliffwood Dr.	SL Shamrock	North End	B/S	1.01	2	2.02
Collingwood	NL Beaverhill	NL Parkgrove	B/S	0.32	2	0.64
Conifer	SL Cottonwood	WL Autumnwood	B/S	0.59	2	1.18
Copperstone Cr	Red Willow	Blue Mountain	B/S	0.39	2	0.78
Coral	SL Cottonwood	WL Autumnwood	B/S	0.48	2	0.96
Coral Reef Cove	Ialand Lakes	Island Lakes	B/S	0.34	2	0.68
Cormorant	SL Edgewater	SL Edgewater	B/S	0.61	2	1.22
Cote St.	Evans	Archibald	B/S	0.28	2	0.56
Courtwood	WL Beaverhill	WL Beaverhill	B/S	0.06	2	0.12
Covent	EL Autumnwood	NL Crestwood	B/S	0.03	2	0.06
Coxwain Cove	Pamela Rd.	Pamela Rd.	B/S	0.08	3	0.24
Crestwood	SL Cottonwood	WL Autumnwood	B/S	0.72	2	1.44
Culloden / Bromton	Beaverhill	S End	B/S	0.16	2	0.32
Cusson St.	Evans	Archibald	B/S	0.25	2	0.50
Cypress	NL Cottonwood	NL Cottonwood	B/S	0.38	2	0.76
Cyril Place	EL Lakewood	East End	B/S	0.09	2	0.18
Dallner Bay	Shorehill Drive	Tascona Rd	B/S	0.21	2	0.42
Dayton	WL Cliffwood	EL Cliffwood	S/S	0.52	2	1.04
De La Seigneurie Bv	Service Road	W/S S/Cassin Crescent S.	B/S	0.16	2	0.32

De La Seigneurie Bv	Service Road	E/S S/Pauline Boutal Dr.	B/S	0.25	2	0.50
De La Seigneurie Bv	Service Road	W/S S/Island Lakes Drive	B/S	0.26	2	0.52
De La Seigneurie Bv	Service Road	W/S S/Cassin Crescent N.	BS	0.10	2	0.20
De La Seigneurie Bv	Service Road	W/S S/Desjardins Drive	B/S	0.03	2	0.06
De La Seigneurie Bv	Service Road	E/S S/Desjardins Drive	B/S	0.10	2	0.20
De La Seigneurie Bv	Service Road	W/S S/Langton	B/S	0.08	2	0.16
De La Seigneurie Bv	Service Road	E/S S/Langton	B/S	0.16	2	0.32
De La Seigneurie Bv	Service Road	W/S N Island Shore	B/S	0.08	2	0.16
De La Seigneurie Bv	Service Road	W/S S Island Shore	B/S	0.07	2	0.14
Debourmont Bay	SL Autumnwood	SL Autumnwood	B/S	0.42	2	0.84
DeCaigny Cove	NL Island Lakes	NL Island Lakes	B/S	0.37	2	0.74
Deniset St.	West Limit	Archibald	B/S	0.45	2	0.90
Demetrioiff	Shorehill	East End	B/S	0.15	3	0.45
Demetrioiff	Service Road	S/S E/Shorehill	N/S	0.11	2	0.22
Desjardins Drive	Service Road	S/S W/Surfside Crescent	B/S	0.08	2	0.16
Desjardins Drive	Service Road	E/S N/Island Lakes Drive	B/S	0.16	2	0.32
Desjardins Drive	Service Road	S/S W/De La Seigneurie Blvd.	B/S	0.09	2	0.18
Deswood	WL Newcombe	West End	B/S	0.05	2	0.10
Dockside Way	De La Seigneurie	W End	B/S	0.43	2	0.86
Dogwood Cove	Southbridge	West End	B/S	0.04	2	0.08
Doucet St.	West Limit	Archibald	B/S	0.24	2	0.48
D'Orsey	WL Stillwater	West End	B/S	0.11	2	0.22
Dowse St	Maginot St	North End	B/S	0.04	2	0.08
Driftwood	SL Beaverhill	SL Beaverhill	B/S	0.69	2	1.38
Dufresne Ave.	40m N. of Kavanagh	Marion	B/S	0.40	2	0.80
Dugas	WL Speers	EL Debourmont	B/S	0.60	2	1.20
Duluth	SL Cottonwood	SL Cottonwood	B/S	0.44	2	0.88
Dumoulin St.	Archibald	Maisonneuve	B/S	0.38	2	0.76
Durham	NL Crestwood	NL Crestwood	B/S	0.40	2	0.80
Earlton	Waterton	South End	B/S	0.07	2	0.14
Eastoak DR.	Shorehill DR.	River Valley DR.	B/S	0.36	2	0.72
Eastoak DR.	River Valley DR.	End	B/S	0.12	2	0.24
Ebb Tide Dr.	Pamela Rd.	Island Shore Bv	B/S	0.51	2	1.02

Echo Bay	WL Autumnwood	WL Autumnwood	B/S	0.41	2	0.82
Edenwood Place	Shorehill drive	End	B/S	0.37	2	0.74
Edgemont	SL Beaverhill	SL Beaverhill	B/S	1.01	2	2.02
Elstree Ct.	Waldport	Waldport	B/S	0.04	2	0.08
Erie Bay	WL Autumnwood	WL Autumnwood	B/S	0.42	2	0.84
Evans St.	Prosper	Guilbault	B/S	0.68	2	1.36
Evelyne Reese Bv	Island Shore	S. End	B/S	0.11	3	0.33
Evelyne Reese Bv	Service Road	W/S/ S/Island Shore	W/S	0.10	2	0.20
Evelyne Reese Bv	Service Road	E/S S/Island Shore	E/S	0.10	2	0.20
Everglade	EL Beaverhill	East End	B/S	0.08	2	0.16
Fallbrook	WL Pebblebeach	WL Pebblebeach	B/S	0.44	2	0.88
Farnham	NL Beaverhill	WL Cherwell	B/S	0.22	2	0.44
Fleury	WL Fontaine	EL Fontaine	B/S	0.21	2	0.42
Fontaine	WL Debourmont	EL Debourmont	B/S	0.72	2	1.44
Frigate By	De La Seigneurie	De La Seigneurie	B/S	0.25	2	0.50
Frontenac	NL Autumnwood	NL Autumnwood	B/S	0.55	2	1.10
Gadwall Place	WL Stillwater	West End	B/S	0.07	2	0.14
Gareau St.	Evans	Archibald	B/S	0.31	2	0.62
Garwick Cove	Capston	Capston	B/S	0.36	2	0.72
Gatineau	NL Crestwood	NL Crestwood	B/S	0.36	2	0.72
Gauvreau	EL Charbonneau	WL Island Shore	B/S	0.23	2	0.46
George Druwe Cresc.	Henry Dormer	Dockside Way	B/S	0.23	2	0.46
Giroux St.	West Limit	Archibald	B/S	0.35	2	0.70
Gleneagles	WL Pebblebeach	SL Willow Pt.	B/S	0.36	2	0.72
Goldenrod Cv	Royal Mint Dr	S. End	B/S	0.09	2	0.18
Greenmount	NL Crestwood	WL Westmount	B/S	0.24	2	0.48
Greenwich	NL Crestwood	NL Crestwood	B/S	0.38	2	0.76
Grover Hills	EL Beaverhill	SL Vermillion	B/S	0.37	2	0.74
Guilbault St.	Evans	Archibald	B/S	0.29	2	0.58
Gull Wing Bay	NL Island Lakes	NL Island Lakes	B/S	0.37	2	0.74
Gwynne	Sabourin	Scholberg	B/S	0.07	2	0.14
Haverhill Crescent	Shorehill Drive	Edenwood Place	B/S	0.27	2	0.54
Hacault Pl.	Pamela Rd.	Pamela Rd.	B/S	0.08	2	0.16

Halliday	EL Speers	EL Speers	B/S	0.31	2	0.62
Hampshire	NL Wickham	EL Drake	B/S	0.22	2	0.44
Hansford	WL Harper	SL Elizabeth	B/S	0.52	2	1.04
Harbinger By	Shorehill	Shorehill	B/S	0.26	2	0.52
Harbours End	Pauline Boutal	South End	B/S	0.12	2	0.24
Hardman	John Bruce	South End	B/S	0.10	2	0.20
Harper	Dugas	Elizabeth	B/S	0.09	2	0.18
Harper	Howden	NL Winakwa	B/S	0.68	2	1.36
Harwick	NL Edgemont	SL Beaverhill	B/S	0.26	2	0.52
Hazelnut Ln	Tallgrass Cr	Tallgrass Cr	B/S	0.11	2	0.22
Heather	NL Winakwa	EL Harper	B/S	0.69	2	1.38
Henry Dormer Dr.	Island Shore	Dockside Way	B/S	0.50	2	1.00
Hidden Valley	WL Collingwood	West End	B/S	0.04	2	0.08
Highridge Rd	Shorehill	Shorehill	B/S	0.91	2	1.82
Humber	NL Betournay	EL Howden	B/S	0.33	2	0.66
Huppe Bay	WL Island Shore	WL Island Shore	B/S	0.35	2	0.70
Ironweed Rd	Tallgrass Cr	Tallgrass Cr	B/S	0.13	2	0.26
Iroquois	NL Comanche	NL Comanche	B/S	0.34	2	0.68
Island Cove	SL Island Shore	South End	B/S	0.04	2	0.08
Island Lakes Drive	Service Road	S/S W/De Caigny Cove	B/S	0.12	2	0.24
Island Lakes Drive	Service Road	N/S W/De Caigny Cove	B/S	0.07	2	0.14
Island Shore	Service Road	E/S S/Island Lakes Dr.	B/S	0.15	2	0.30
Island Shore Bv	Service Road	W/S S/Tidal Cove	B/S	0.11	2	0.22
Island Shore Bv	Service Road	N/S E/Henry Dormer	B/S	0.07	2	0.14
Island Shore Bv	Service Road	S/S E/Henry Dormer	B/S	0.08	2	0.16
Island Shore Bv	Service Road	S/S W/Ebb Tide	B/S	0.14	2	0.28
Jade	WL Edgemont	West End	B/S	0.06	2	0.12
Jogues	NL Cottonwood	EL Speers	B/S	0.24	2	0.48
John Bruce Rd	Seine River	Wildfire	B/S	0.97	2	1.94
Jubenville	SL Betournay	SL Betournay	B/S	0.38	2	0.76
Kavanagh St.	West Limit	Archibald	B/S	0.33	2	0.66
Kenton	SL Beaverhill	South End	B/S	0.10	2	0.20
La Fleche St.	La Verendrye St.	Provencher	B/S	0.30	2	0.60

La Fleche St.	Provencher	South Limit	B/S	0.14	2	0.28
La Verendrye St.	Archibald	La Fleche	B/S	0.16	2	0.32
Lachine	NL Paterson	EL Westmount	B/S	0.28	2	0.56
Lakelawn	NL Beaverhill	WL Beaverhill	B/S	0.47	2	0.94
Lakemere	WL Clearwater	West End	B/S	0.06	2	0.12
Lakepark	SL Vermillion	SL Vermillion	B/S	0.66	2	1.32
Lands End Cv	Island Shore	S. End	B/S	0.11	2	0.22
Langton	EL Camirant Cr.	Bv De La Seigneurie	B/S	0.35	2	0.70
Lardon Ct	John Bruce	N End	B/S	0.08	2	0.16
Leeward Place	NL Desjardins	SL Myles Robinson	B/S	0.15	2	0.30
Leger Cres.	WL Island Shore	WL Island Shore	B/S	0.54	2	1.08
Leonard Shakesreare	Brunet	Brunet	B/S	0.18	2	0.36
Leveque	West Limit	Lagimodiere	B/S	0.14	2	0.28
Lighthouse Pt.	EL Island Shore	East End	B/S	0.18	2	0.36
Limetree Cove	Willowlake	North End	B/S	0.11	2	0.22
Linmar Way	Royal Mint Dr	Linmar Way	B/S	0.50	2	1.00
Lochinvar	NL Penfold	SL Paterson	B/S	0.29	2	0.58
Lochmoor	NL Penrose	SL Paterson	B/S	0.22	2	0.44
Lochmoor	NL Paterson	SL Cottonwood	B/S	0.39	2	0.78
Lone Oak Pl.	Southbridge	South End	B/S	0.05	2	0.10
Lonergan Place	Lakewood Bv	East End	B/S	0.07	2	0.14
Manbrough	NL Parkgrove	North End	B/S	0.04	2	0.08
Manring Cove	WL Cliffwood	WL Cliffwood	B/S	0.31	2	0.62
Maplehurst	SL Cottonwood	NL Monterey	B/S	0.19	2	0.38
Marina	EL Lakelawn	East End	B/S	0.03	2	0.06
Marwood	SL Edgemont	WL Edgemont	B/S	0.26	2	0.52
Maisonneuve St.	Notre Dame St.	Dumoulin St.	B/S	0.09	2	0.18
Maywood	SL Cottonwood	WL Westmount	B/S	0.29	2	0.58
McGurran Pl.	Lakewood Bv	East End	B/S	0.03	2	0.06
McKall Bay	de la Seigneurie	de la Seigneurie	B/S	0.31	2	0.62
Minaki	SL Vermillion	SL Vermillion	B/S	0.34	2	0.68
Mohawk	NL Comanche	NL Comanche	B/S	0.40	2	0.80
Monaco	SL Cottonwood	SL Cottonwood	B/S	0.46	2	0.92

Monterey	SL Cottonwood	EL Speers	B/S	0.37	2	0.74
Montvale	Southside Dr	Southside Dr	B/S	0.65	2	1.30
Morning Glory	Royal Mint Dr	Royal Mint Dr	B/S	0.34	2	0.68
Mount Laurel Cr.	SL Capston	SL Capston	B/S	0.60	2	1.20
Myles Robinson	NL Desjardins	NL Island Lakes Drive	B/S	0.46	2	0.92
Nadeau St.	Notre Dame St.	Provencher	B/S	0.20	2	0.40
Nadeau St.	Provencher	Tissot	B/S	0.09	2	0.18
Niakwa Rd. East	Fermor	North Limit	B/S	0.45	2	0.90
Niakwa Rd. East	Niakwa Rd. East	East Limit	B/S	0.92	2	1.84
Newark	NL Cottonwood	SL Westmount	B/S	0.18	2	0.36
Newcombe	NL Shamrock	South End	B/S	0.63	2	1.26
Newcroft Road	Service Road	S/S/ W/Cliffwood	B/S	0.35	2	0.70
Nipigon	NL Cottonwood	WL Northumbria	B/S	0.21	2	0.42
Norcross Cr	Shorehill	Shorehill	B/S	0.57	2	1.14
Nordstrom	de la Seigneurie	Sabourin	B/S	0.20	3	0.60
Nordstrom	Sabourin	Sabourin	B/S	0.40	3	1.20
Northport	Southside Dr	Southside Dr	B/S	0.33	2	0.66
Northumbria	NL Cottonwood	NL Cottonwood	B/S	0.47	2	0.94
Northwood	Southside Dr	East End	B/S	0.11	2	0.22
Notre Dame St.	Archibald	Maisonneuve	B/S	0.38	2	0.76
Oakmount	SL Berkshire	NL Berkshire	B/S	0.14	2	0.28
Orchard Hill Dr	Shorehill	Aubin	B/S	0.91	2	1.82
Orchard Lane	SL Shoreview	NL Shoreview	B/S	0.21	2	0.42
Ormiston	SL Elizabeth Rd.	NL Howden	B/S	0.22	2	0.44
Ospray Place	WL Stillwater	West End	B/S	0.11	2	0.22
Pambrun Pl	Wildfire	W. End	B/S	0.02	2	0.04
Pamela Rd.	Island Shore Bv	Ebb Tide Dr.	B/S	0.30	2	0.60
Park Grove	NL Beaverhill	NL Beaverhill	B/S	0.85	2	1.70
Park Terrace	WL Beaverhil	WL Beaverhill	B/S	0.36	2	0.72
Pauline Boutal	Bv De La Seigneurie	Bv de La Siegneurie	B/S	0.79	2	1.58
Pawnee	NL Comanche	NL Comanche	B/S	0.38	2	0.76
Pembroke	EL Westmount	SL Paterson	B/S	0.30	2	0.60
Penfold	SL Paterson	SL Penrose	B/S	0.86	2	1.72

Penrose	EL Penfold	WL Lochmoor	B/S	0.30	2	0.60
Penticton	SL Paterson	SL Paterson	B/S	0.52	2	1.04
Peres Oblats	EL De La Seigneurie	WL Smugglers Cove	B/S	0.50	2	1.00
Peres Oblats	Service Road	S/S E/Bv De La Seigneure	N/S	0.10	2	0.20
Peterboro	SL Paterson	SL Paterson	B/S	0.53	2	1.06
Picton Ct	Orchard Hill Dr	N End	B/S	0.02	2	0.04
Pinebluff	WL Pebblebeach	SL Niakwa	B/S	0.31	2	0.62
Pitcairn	EL Penfold	WL Lochinvar	B/S	0.14	2	0.28
Place Adgelina Gregoire	Promenade Brunet	S. End	B/S	0.75	2	1.50
Place Berube	WL Charbonneau	West End	B/S	0.19	2	0.38
Place Corbeil	SL Gauvreau Road	South End	B/S	0.14	2	0.28
Place Francis Muller	Promenade Brunet	S. End	B/S	0.75	2	1.50
Place Joyal	EL Charbonneau	East Emd	B/S	0.08	2	0.16
Place Lagace	WL Island Shore	West End	B/S	0.09	2	0.18
Place Lesard	Bv De La Seigneure	Pauline Boutal Crescent	B/S	0.11	2	0.22
Place Marcoux	SL Leger	South End	B/S	0.08	2	0.16
Place St Jean Baptiste Lavoie	Promenade Burnet	S End	B/S	0.08	2	0.16
Plinguet St	West Limit	Archibald	B/S	0.09	2	0.18
Promenade Brunet	Maginot	W End	B/S	0.87	2	1.74
Promenade Brunet	Service Road	N/S W/Drake	B/S	0.09	2	0.18
Prosper St.	West Limit	Archibald	B/S	0.31	2	0.62
Proulx Pl	Lafrance Ln	Lafrance Ln	B/S	0.13	2	0.26
Pynoo Place	NL De La Seigneurie	NL De La Seigneurie	B/S	0.22	2	0.44
Quayside	NL Pere Oblate	NL Pere Oblate	B/S	0.36	2	0.72
Quayside	SL Pere Oblate	NL Cassin	B/S	0.08	2	0.16
Queensway Cr.	EL Driftwood	NL Driftwood	B/S	0.34	2	0.68
Radburn Place	EL Beaverhill	East End	B/S	0.06	2	0.12
Rainbow Cv	Royal Mint Dr	S. End	B/S	0.05	2	0.10
Red Moon Rd	All		B/S	0.53	2	1.06
Red Willow Cr	Royal Mint Dr	Blue Mountain	B/S	0.29	2	0.58
River Valley DR.	Shorehill DR.	Eastoak DR.	B/S	0.55	2	1.09
Rockcliffe	EL Beaverhill	NL Shoreview	B/S	0.37	2	0.74
Royal Mint	Service Road	E/S N/East Mint	W/S	0.15	2	0.30

Royal Mint	Service Road	N/S E/Golden rod	S/S	0.19	2	0.38
Royal Park Cr	Royal Mint Dr	Royal Mint Dr	B/S	0.46	2	0.92
Royal Salinger	SL Niakwa	WL Pebblebeach	B/S	0.62	2	1.24
Sabourin	Nordstrom	East End	B/S	0.28	2	0.56
Scholberg	Gwynne	Nordstrom	B/S	0.15	2	0.30
Seabrook	WL Beaverhill	West End	B/S	0.04	2	0.08
Serino Place	SL Queensway	South End	B/S	0.04	2	0.08
Shamrock	EL Newcroft	WL Newcombe	B/S	0.30	2	0.60
Shamrock Drive	Service Road	S/S W/Newcroft	B/S	0.13	2	0.26
Shorehill	Service Road	E/S S Tascona Road	B/S	0.13	2	0.26
Shorehill	Service Road	W/S S/Norcross Cr	B/S	0.12	1	0.12
Shorehill	Service Road	E/S S/Wildfire	B/S	0.16	1	0.16
Shorehill	Service Road	E/S S/Dallner Bay	B/S	0.05	1	0.05
Shorehill	Service Road	W/S S/Tascona RD	B/S	0.08	1	0.08
Shorehill	Service Road	E/S N/Southside	B/S	0.11	1	0.11
Shorehill	Service Road	W/S S/ Westwater Dr North Leg	E/S	0.29	1	0.29
Shoreview	EL Beaverhill	EL Beaverhill	B/S	0.58	2	1.16
Smugglers Cove	EL Cassin	North End	B/S	0.28	2	0.56
Southbridge Dr.	NL Willowlake	NS Willowlake	B/S	1.09	2	2.18
Southmoor	WL Pebblebeach	WL Pebblebeach	B/S	0.79	2	1.58
Southside Dr	Service Road	S/S E/Shorehill	N/S	0.16	2	0.32
Southside Dr	Service Road	W/S N/Northport S Leg	B/S	0.13	2	0.26
Speers	NL Cottonwood	SL Jogues	B/S	0.15	2	0.30
Speers	NL Winakwa	SL Betournay	B/S	0.17	2	0.34
Speers	NL Maginot	North End	B/S	0.45	2	0.90
St. Catherine St.	West Limit	Archibald	B/S	0.32	2	0.64
St. Hillaire	Beaverhill	South End	B/S	0.13	2	0.26
Stillwater	NL Willowlake	SL Brookhaven	B/S	0.33	2	0.66
Stonecourt Pl	Shorehill	S. End	B/S	0.05	2	0.10
Surf Side	SL Desjardins	WL De La Seigneurie	B/S	0.51	2	1.02
Sweetwater	SL Edgewater	SL Edgewater	B/S	1.07	2	2.14
Tahoe	EL Lakewood	EL Lakewood	B/S	0.36	2	0.72
Tallgrass Cr	All		B/S	0.78	2	1.56

Tamarac	EL Lakewood	EL Lakewood	B/S	0.47	2	0.94
Tansi Ln	Red Moon Rd	Red Moon Rd	B/S	0.19	2	0.38
Tascona Road	Shorehill Drive	Dallner Bay	B/S	0.49	2	0.97
Tidal Cove	NL Island Shore	NL Island	B/S	0.45	2	0.90
Tidewater Bay	EL Island Shore	NL Lighthouse	B/S	0.25	2	0.50
Tissot St.	West Limit	Archibald	B/S	0.30	2	0.60
Treasure Cove	Pauline Boutal	South End	B/S	0.12	2	0.24
Trembley St.	West Limit	Archibald	B/S	0.44	2	0.88
Vale	WL Manring	West End	B/S	0.03	2	0.06
Vermillion	EL Beaverhill	EL Grover Hills	B/S	0.26	2	0.52
Vincent Massey	NL Betournay	NL Betournay	B/S	0.63	2	1.26
Waldport By	Shorehill	River Valley DR.	B/S	0.37	2	0.74
Watercress	SL Edgewater	EL Cormorant	B/S	0.23	2	0.46
Waterside Cove	SL Island Shore	South End	B/S	0.05	2	0.10
Waterton	Bridgetown	Bridgetown	B/S	0.30	2	0.60
Wayfarer's Haven	Island Lakes Dr.	Island Lakes Dr.	B/S	0.43	2	0.86
Weatherstone	WL Lakewood	WL Lakewood	B/S	0.64	2	1.28
Westmount	NL Cottonwood	NL Cottonwood	B/S	0.52	2	1.04
Westwater Dr	Shorehill	Shorehill	B/S	0.49	2	0.98
Wickham	EL Drake	East End	B/S	0.31	2	0.62
Wildfire Dr	Shorehill	John Bruce	B/S	0.52	2	1.04
Wilmington Dr	John Bruce	Bridgeway	B/S	0.57	2	1.14
Wiltshire	NL Wickham	NL Wickham	B/S	0.35	2	0.70
Winakwa	EL Autumnwood	WL Speers	B/S	0.43	2	0.86
Windlass Bay	SL Waterfront Road	South End	B/S	0.09	2	0.18
Wood Sage Cr	All		B/S	0.61	2	1.22
Yorkwood Dr.	Shorehill Dr.	Shorehill Dr.	B/S	0.45	2	0.89
				Total		214.31

APPENDIX "D"

Snowfall - October 1 to April 30

<u>Year</u>	<u>Centimetres</u>
1968-1969	95.20
1969-1970	159.00
1970-1971	123.40
1971-1972	106.70
1972-1973	81.00
1973-1974	130.80
1974-1975	125.20
1975-1976	136.20
1976-1977	64.40
1977-1978	73.10
1978-1979	148.60
1979-1980	108.00
1980-1981	72.50
1981-1982	77.20
1982-1983	77.40
1983-1984	56.30
1984-1985	93.20
1985-1986	124.20
1986-1987	120.20
1987-1988	65.40
1988-1989	153.60
1989-1990	96.40
1990-1991	120.50
1991-1992	133.00
1992-1993	111.60
1993-1994	82.00
1994-1995	88.60
1995-1996	202.50
1996-1997	211.40
1997-1998	104.10
1998-1999	144.70
1999-2000	71.40
2000-2001	109.70
2001-2002	105.40
2002-2003	90.90
2003-2004	149.80
2004-2005	136.60
2005-2006	151.20
2006-2007	135.60
2007-2008	111.90
2008-2009	129.20

APPENDIX "E"

EAST AREA (South)

**REGIONAL - PRIORITY I STREETS IDENTIFIED FOR DAYTIME PLOWING
(Between 09:00 and 15:30 Hours)**

NONE

APPENDIX "F"

BUS STOP LOCATIONS TO BE PUSHED - 30m

N/B St. Mary's @ Marion Near Side

S/B St. Mary's @ Marion Far Side

*S/B Main @ Bell Near Side