

632-2009 ADDENDUM 1

LOMBARD AVE. & WATERFRONT DR. LDS OUTFALL GATE CHAMBER CONSTRUCTION – CONTRACT NO. 43

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: October 2, 2009
BY: Grantley King, P.Eng.
TELEPHONE NO. (204) 272-2013

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 632-2009 Bid Submission with 632-2009 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Item A.2 (a) (1) quantity revised.
- Form B(R1): Add Items No. A.2 (a) 2 to 3 inclusive.
- Form B(R1): Item A.3 (a) unit revised.

PART E – SPECIFICATIONS

Replace: E9.3 (c) and (d) to read:

- (c) Sluice Gate located on existing chamber.
 - (i) Remove the existing sluice gate, stem extensions and operator located in the existing gate chamber.
 - (ii) Costs for the removal of the sluice gate, stem extensions, operator and capping of the openings shall be included in the gate chamber construction.
- (d) Flap Gate located on existing 900mm diameter manhole.
 - (i) Remove and dispose of the existing cast iron flap gate located in the existing Lombard Avenue Manhole.
 - (ii) Install approximately 7.5 meters of 900mm diameter concrete LDS including tie-ins, bend and nipple at the new MH and Gate Chamber as shown on drawings LD-5438 and LD-5439.
 - (iii) Cost for the removal and disposal of the cast iron flap gate and section of the existing 900mm diameter LDS to allow for the tie-ins shall be included in the gate chamber construction.
 - (iv) The Contractor is advised that a video of the existing monolithic 900mm diameter LDS and cast iron flap gate to be removed can be obtained from the office of the Contract Administrator upon request.

DRAWINGS

Replace: 632-2009 _Drawing_LD-5438-R0 with 632-2009 _Addendum_1 Drawing_LD-5438-R1

632-2009 _Drawing_LD-5439-R0 with 632-2009 _Addendum_1 Drawing_LD-5439-R1