PLANT KEY (REFER TO PLANT LIST ON C3-L-5006)

KEY	COMMON NAME/BOTANICAL NAME
DECIDUOUS TREES	
A	MANCHURIAN ASH/FRAXINUS MANDSHURICA 'MANCANA'
B	GLENLEVEN LINDEN / TILIA CORDATA 'GLENLEVEN'
C	AMERICAN ELM / ULMUS AMERICANA
ORNAMENTAL DECIDUOUS TREES	
D	AMUR MAPLE / ACER GINNALA
E	SPRING SNOW CRABAPPLE / MALUS X 'SPRING SNOW'
CONIFEROUS TREES	
F	WHITE SPRUCE/PICEA GLAUCA
G	COLORADO SPRUCE/PICEA PUNGENS
DECIDUOUS SHRUBS	
H	ARONIA MELANOCARPA / CHOKEBERRY
J	PYGMY CARAGANA / CARAGANA PYGMAEA
K	WOOD'S ROSE / ROSA WOODSII
L	THREE-LOBED SPIREA / SPIRAEA TILOBATA
M	NANNYBERRY / VIBURNUM LENTAGO
PERENNIALS AND VINES	
N	DAYLILY MIXED SPECIES/ HEMEROCALIS SP
P	CHEQUERS LAMIUM / LAMIUM MACULATUM 'CHEQUERS'
Q	NATIVE GRAPE / VITUS RIPARIA
R	BITTERSWEET / CELASTRUS SCANDENS

BELL AVE

STRADBROOK AVE

SIDEWALK RAMP WITH DETECTABLE PAVERS AS PER DETAIL 6 ON SHEET 49. (TYP.)

EXISTING TREES TO BE REMOVED IN AREA OF NEW SIDEWALK ON STRADBROOK FROM THIS TREE WEST TO DONALD (TYP)

1/64 SUPPLY AND INSTALL DECIDUOUS TREE AS PER DETAIL

2/64 SUPPLY AND INSTALL CONIFEROUS TREES IN MULCH BED AS PER DETAIL

1.8m HT. ORNAMENTAL FENCE AS PER 2/63 DETAIL (N.I.C.)

N.I.C.

EXISTING TREES TO REMAIN. PROTECT DURING CONSTRUCTION. CONSTRUCT PLANTER AS PER 3/62 DETAIL

SUPPLY AND INSTALL CONIFEROUS TREES IN MULCH BED AS PER DETAIL 2/64

1.8m HEIGHT CHAIN LINE FENCE

EXISTING TREES TO REMAIN WHERE POSSIBLE. PROTECT DURING CONSTRUCTION. IF TREES ARE REMOVED, REPLACE WITH AMUR MAPLE AS PER PLANT LIST

SUPPLY AND INSTALL LANDSCAPE ROCK AS PER DETAIL. 'GRAB DISTANCE' ACROSS ROCK AREAS TO BE NO MORE THAT 1.2m. ROCK LAYOUT TO BE CONFIRMED WITH PROJECT LANDSCAPE ARCHITECT AND CITY OF WINNIPEG PARKS PRIOR TO INSTALLATION 4/64

SUPPLY AND INSTALL NATIVE GRASSES AS PER SPECIFICATIONS.

SUPPLY AND INSTALL 1.8m HT. CHAIN LINK FENCE AND TIE INTO RETAINING WALL AT STATION

MATCH LINE D-D

MATCH LINE E-E

NORTH

X:\08-028 Southwestern BRT Corridor\dwg\2009\wkg dwg phase 1\working drawings phase 1-revised apr 14.dwg

LEGEND

- SOD
- NATIVE GRASSES
- MULCH BED
- CONCRETE SIDEWALK
- DETECTABLE PAVING IN SIDEWALK RAMP
- EXISTING TREES TO REMAIN
- PROPOSED DECIDUOUS TREE
- PROPOSED ORNAMENTAL DECIDUOUS TREE
- PROPOSED CONIFEROUS TREE
- PROPOSED SHRUBS
- PLANT KEY
- QUANTITY / PLANT KEY

LOCATION UNDERGROUND STRUCTURES — APPROVED

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. BM
ELEV. ELEV

NO.	REVISIONS	DATE	BY
1	ISSUED FOR TENDER	04/29/09	JW

DESIGNED BY SR/JW
DRAWN BY JW/OV
CHECKED BY JW/SR
APPROVED BY -
HOR. SCALE 1:250
VERTICAL
DATE 2009-04-14

McGOWAN·RUSSELL
DILLON CONSULTING

RELEASED FOR CONSTRUCTION
ORIGINAL SIGNED BY RANDY FINGAS
APRIL 29/09
DATE

LANDSCAPE ARCHITECT'S SEAL
the manitoba association of landscape architects
JACQUELINE L. WALKIE
member no. 75

CONSULTANT PROJECT NO. 08-028

Winnipeg

THE CITY OF WINNIPEG
TRANSIT DEPARTMENT

SOUTHWEST RAPID TRANSIT CORRIDOR - STAGE 1
TRANSIT WAY CONSTRUCTION, DONALD/HARKNESS RECONSTRUICTION & ASSOCIATED WORK

CITY DRAWING NUMBER P-3299 - 59
SHEET 59 OF 64

STREETSCAPE AND LANDSCAPE WORKS
STRADBROOK AVENUE 1 OF 3

CONSULTANT DRAWING NUMBER C3-L-5004-T