

1. GENERAL

1.1 References - General

.1 Refer to Section 29 05 00.

1.2 Instrument Index

.1 The following spreadsheet gives an itemized list of the instrumentation included as part of this Work.

2. PRODUCTS (NOT USED)

3. EXECUTION (NOT USED)

END OF SECTION

ADDENDUM 1

INSTRUMENT INDEX

RECORD NO.	REV. No.	TAG NAME	DESCRIPTION		MANUFACTURER	MODEL	POWER SUPPLY	CALIBRATED RANGE	MOUNTING	SUPPLIED BY	INSTALLED BY	COMMENTS	SPEC. DATA SHEET	P&ID DRAWING	INSTRUMENT LOOP DIA.	INSTALLATION DETAIL	LOCATION DWG.
			INSTRUMENT TYPE	SERVICE													
0001	0	FCV-101	Electric Acuator	Aqua Duct Valve			600V, 3Phase		Floor	City	Contractor				D-11936		D-11934
0002	0	FCV-102	Electric Acuator	Aqua Duct Valve			600V, 3Phase		Floor	City	Contractor				D-11936		D-11934
0004	0	LS-103	Float Level Switch	Valve Chamber Flood Switch			120VAC	75mm from floor	Bracket	Contractor	Contractor		I-101		D-11936		D-11934
0005	0	LS-104	Float Level Switch	Valve Chamber Flood Switch			120VAC	75mm from floor	Bracket	Contractor	Contractor		I-101		D-11936		D-11934
0006	1	PIT-105	Pressure Transmitter	Pump Station Inflow Pressure			Loop Powered	-100 to 500 kPA	Block&Bleed Manifold	Contractor	Contractor		I-105		D-11936		D-11934
0006	1	FIT-106	Flow Meter	Pump Station Inflow			120VAC	0 to 15 ML/hr	Remole Transmitter	City	Contractor				D-11936		D-11934
0007	0	ZSD-108A	Magnetic Switch	Door Contact Switch			24VDC		Door Frame	Contractor	Contractor		I-103		D-11936		D-11934
0008	0	ZSD-108B	Magnetic Switch	Door Contact Switch			24VDC		Door Frame	Contractor	Contractor		I-103		D-11936		D-11934
0009	0	HS-108	Key Switch	Security System On/Off			24VDC		Nema 12 Enclosure	Contractor	Contractor	Medeco lock set	I-104		D-11936		D-11934
0006	1	TIT-109	Temperature Transmitter	Ambient Air			Loop Powered	-10 to +40 Celsius	Wall	Contractor	Contractor		I-102		D-11936		D-11934