



SECTION D-D




SECTION A-A




PLAN VIEW

1 TREE VAULT: SIDEWALK SOIL TRENCH COVER
L-6 SCALE: 1:20




SECTION B-B




PLAN VIEW

2 TREE VAULT: SIDEWALK TREE WELL COVER
L-6 SCALE: 1:20



3 TREE VAULT: SIDEWALK SOIL TRENCH & TREE WELL COVER - BOYD BUILDING AREAWAY
L-6 SCALE: 1:20



SECTION C-C

U/G SERVICE NOTES:
1. LOCATIONS OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. ANY ENCUMBRANCES SHALL BE REPORTED TO THE CONTRACT ADMINISTRATOR IMMEDIATELY.

2	Issued for Tender	June 3, 2010
1	Released for Review	March 10, 2010
No.	Revision	Date

- AREAWAY ROOF WATERPROOFING:**
- CAREFULLY REMOVE EXISTING SIDEWALK & EXISTING FILL TO EXPOSE AREAWAY ROOF TO CLEAN BARE CONCRETE.
 - NOTIFY CONTRACT ADMINISTRATOR FOR STRUCTURAL INSPECTION.
 - REMOVE LOOSE MATERIAL TO SOUND CONCRETE. PATCH HOLES & CRACKS WITH XYPEX PATCHING COMPOUND TO PROVIDE SMOOTH SOUND SURFACE ACCEPTABLE TO MEMBRANE INSTALLATION.
 - INSTALL TORCH-ON MEMBRANE OVER ENTIRE AREAWAY AND UP BUILDING FACE.
 - INSTALL METAL FLASHING BOND BREAKER
 - SEAL GAP BETWEEN BUILDING AND CONCRETE SIDEWALK AFTER CONCRETE CURE.

- PRODUCT INFORMATION:**
- XYPEX PATCHING COMPOUND:
• XYPEX 'MAGAMIX II'
 - TORCH-ON MEMBRANE:
• THERMOFUSIBLE MODIFIED BITUMEN, FIBREGLAS REINFORCED, NOM THICKNESS 2.5mm (100 mil.) BAKOR 'TG' OR SOPREMA ELASTOPHENE FLAM (3mm) FOLLOW MANUFACTURERS INSTALLATION SPECIFICATIONS.
 - CONCRETE CRACK SEALER:
• QUICKCRETE CONCRETE CRACK SEALER (GREY)
 - TREE ROOT BARRIER:
• DEEPROOT UB-48-2 FOLLOWING MANUFACTURERS INSTALLATION SPECIFICATIONS
 - METAL FLASHING:
• BOND BREAKER STAINLESS STEEL 304 24GA

**EDMONTON STREET
WEST SIDEWALK
PORTAGE TO GRAHAM
Streetscape Redevelopment**

DETAILS



Drawn	AJH	Approved	GM
Scale	AS NOTED	Date	JUNE 3, 2010
Job	09 048	Drawing	L-6