



287-2010 ADDENDUM 1

PROVINCE OF MANITOBA / CITY OF WINNIPEG – CORYDON AVENUE
EASTBOUND – CENTENNIAL STREET TO BEAVERBROOK STREET –
MILL AND FILL, BEAVERBROOK STREET TO LANARK STREET –
PAVEMENT RECONSTRUCTION

ISSUED: April 27, 2010
BY: Roy Houston, P.Eng.
TELEPHONE NO. (204) 896-1209

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

Add: D16.1 (e) CBS Outdoors – Temporary removal of bus shelter before construction and re-installation of bus shelter after construction.

PART E – SPECIFICATIONS

Revise: E15. to read: **E15. WEIGHT RESTRICTIONS FOLLOWING ASPHALT PLANING**

ADD: **E19 BUS SHELTER**

- E19.1 CBS Outdoors will provide an electrical conduit to be cast in sidewalk concrete. CBS Outdoors will provide direction where to install the electrical conduit for the bus shelter. The Contractor shall cast the electrical conduit in the sidewalk at the location designated by CBS Outdoors.
- E19.2 The Contractor will accommodate CBS Outdoors and ensure CBS Outdoors will have access to the bus shelter for their works to temporarily remove the bus shelter and replace the bus shelter.
- E19.3 No payment will be made for the installation of the bus shelter electrical conduit and will be considered incidental to the Work for CW 3235-R7 "Renewal of Existing Miscellaneous Concrete Slabs".

DRAWINGS

Replace: 287-2010 _Drawing_3320_02-R0.PDF with 287-2010 _Addendum_1 -Drawing_3320_02-R1.PDF

287-2010 _Drawing_3320_03-R0.PDF with 287-2010 _Addendum_1 -Drawing_3320_03-R1.PDF