



BID OPPORTUNITY No. 476-2010 ADDENDUM No.2

**2010 FEEDERMAIN INSTALLATION AND ASSOCIATED WORKS ON
BISON DRIVE FROM WAVERLEY STREET TO KENASTON BOULEVARD
– CONTRACT NO. 17**

ISSUED: June 23, 2010
BY: Doug Berg, C.E.T.
TELEPHONE NO. (204) 986-4452

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: BID OPPORTUNITY No. 476-2010 Bid Submission with BID OPPORTUNITY No. 476-2010 Addendum No. 2 Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Revise C.6 a) to read: Supply and Place 50mm Crushed Sub-base Material
(Quantity shall be 1530 tonne)

Add: C.6 b): Supply and Place 20mm Crushed Base Course Material
(Quantity shall be 1020 tonne)

PART D – SUPPLEMENTAL CONDITIONS

Revise D21.3 to read: A minimum of one lane of traffic must be maintained on Cadboro Road at all times and in accordance with E19.7 a)

Revise D21.4 to read: Access to all properties on Cadboro Road must be maintained at all times and in accordance with E19.7 a)

PART E – SPECIFICATIONS

Revise E19.7 to read: Gravel Surfacing damaged as a result of construction activities will be restored to original line and grade with granular materials in accordance with CW 3150.

- a) Any temporary lanes and approaches to maintain traffic control and maintenance of access as described in D21 shall be constructed at the Contractor's expense and removed upon the completion of the project. This Work shall be considered incidental to the Work being done and no additional payment will be made for such Work.

Revise E19.7.1 to read: Gravel Surfacing work shall consist of supplying and placing the following granular materials:

- a) Minimum compacted 150mm depth of 50mm crushed sub-base limestone material over damaged areas or as determined by the Contract Administrator.

- b) Minimum compacted 100mm depth of 20mm crushed base course limestone material over areas covered with material described in E19.7.1 a).
- c) Required base preparation shall be in accordance with CW 3150, or as determined by the Contract Administrator, and shall be included with the work being done.

Revise E19.7.2 to read: Gravel Surfacing work restoration shall be measured at the contract unit price for such work as indicated in the items under Form B (R1): Prices for "Provisional Items". The contract unit price shall include all work to complete restoration including any base preparation required in accordance with CW 3150 or as determined by the Contract Administrator.