

SCALE: 1:100mm

GENERAL NOTES:

- PERFORM WORK IN ACCORDANCE WITH ALL APPLICABLE CODES AND REGULATIONS.
- REVIEW EQUIPMENT LOCATIONS WITH CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION.
- 3. DUCT ROUTING INDICATED ON DRAWINGS ARE APPROXIMATE ONLY, CONFIRM IN FIELD, REROUTE DUCTING TO ELIMINATE FIELD INTERFERENCES WITH BUILDING STRUCTURES, ELECTRICAL ETC. CONFIRM CHANGES WITH CONTRACT ADMINISTRATOR.
- 4. CONFORM TO SMACNA STANDARDS FOR SUPPLY AND INSTALLATION OF DUCTWORK.
- 5. PROVIDE ALL WALL/ROOF PENETRATIONS AND CURBS.
- 6. SEAL ALL WALL/ROOF PENETRATIONS AND DUCTWORK WATER/AIR TIGHT.
- 7. PROVIDE ACCESS DOORS FOR ALL EQUIPMENT AND DAMPERS LOCATED ABOVE DRYWALL CEILINGS.
- 8. REVISE SPRINKLER PIPING WHERE REQUIRED TO FACILITATE INSTALLATION OF NEW HVAC SYSTEM. SPRINKLER MODIFICATION TO BE DESIGNED BY A QUALIFIED SPRINKLER ENGINEER TO MEET NEPA 13.

KEY NOTES:

- CONNECT NEW DIFFUSERS TO DUCTWORK ABOVE. (SEE DRAWING M5). PROVIDE FIRE DAMPERS AND FIRE SEAL TO MAINTAIN RATED CEILING.
- PROVIDE NEW BALANCING DAMPER ON THE EXISTING RETURN DUCT.

LEGEND:

NEW EQUIPMENT OR DUCTWORK

CONTROL WIRING

THERMOSTAT

BALANCE DAMPER

1.5 HOUR FIRE DAMPER C/W ACCESS DOOR

EXISTING EQUIPMENT OR DUCTWORK

- GRILLE NO. - NECK SIZE (mm)

GRILLE SCHEDULE			
TAG	PRICE DESIGNATION	COMMENTS	
G1	350ø/RCDA/B12	ROUND CONE DIFF	USER
G2	600×600/80/F/A/B12	EGG CRATE RETUR	N
G3	750×750/80/F/A/B12	EGG CRATE RETUR	N

APEGN Certificate of Authorization KGS Group No. 245 Date: 10/01/28

CONSULTING ENGINEERS
& PROJECT MANAGERS

WINNIPEG (204) 896-1209 THUNDER BAY (807) 345-2233 **GROUP** DRAWN BY APPROVED RELEASED FOR CONSTRUCTION: HOR. SCALE: AS SHOWN 10/01/28 **K** VERTICAL: CONSULTANT DRAWING NO. 0 ISSUED FOR TENDER DATE BY DATE NO. REVISIONS DATE



P1-M04

Winnipeg PROJECT TITLE

THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT

001 FORT ROUGE LEISURE CENTRE HVAC UPGRADES — PHASE 1 COMPUTER FILE NAME 08-0107-09-P1-M04 CITY DRAWING NUMBER

MAIN FLOOR PLAN NEW HVAC