



NEW FIRE PARAMEDIC STATION NO. 27, SAGE CREEK BLVD.

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: February 1, 2011
BY: Reid Douglas
TELEPHONE NO. (204) 986-3555

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Section 02800 2.1.4 Add: Bike Rack: 1 required
Manufactured by Maglin

- Tel # 1-800-716-5506
- Fax # 1-877-260-9393

Supply and install bike rack as manufactured by Maglin - Model # MBR400 Series Bike Rack. Surface Mount installation. Refer to Architectural Site Plan A1.1 for installation location.

Section 02445 2.1.1 Revise line to read: "Black steel fencing by Iron Eagle, Model: Elegant Eagle II, 60" high sections". Contact Contract Administrator if there are irregularities in the grade that may require jogging the fence up or down in elevation.

There is one 4'-0" wide gate in this application.

Section 02445 3.1.1 Revise line to read: "Straight and true installation with 96mm spacing between pickets".

DRAWINGS

Add 966-2010 Addendum 2 Drawing M4.1A-R0

Add 966-2010 Addendum 2 Drawing M6.1A-R0

The above drawings refer to Mechanical Drawings M4.1 & M6.1.

QUESTIONS

1. Who is responsible for supplying, installing cable & terminating the voice / data system?
 - Refer to section 16741, electrical contractor shall only provide raceway as indicated, Owner's forces to install cable and terminate.
2. Who is responsible for supplying, installing cable & terminating the TV cable system?
 - Refer to section 16741, electrical contractor shall only provide raceway as indicated, Owner's forces to install cable and terminate.

3. Clarify what type & size of cabinets that are required for the voice / data system Drawing E2.2 note #7?
 - *Refer to section 16770, 2.1.4.7 – the voice / data and sound system in the same cabinet.*
4. Clarify what type or model # for the flush floor outlet that is required in room 113 lounge / day room.
 - *Refer to section 16132, 2.5 floor outlets.*
5. 200 Slab on grade is noted on drawing S1.1, but on structural detail drawing slab shows void form below. Please clarify if it is slab on void or slab on grade.
 - *Slab on void*
6. Will you require any type of waterproofing in the shower areas?
 - Yes, Kerdi waterproofing as per Addendum 2
7. Will you require the use of epoxy grout on any areas of this project?
 - *No.*
8. Are the exterior concrete roadway pavements per COW standard 3310 with a typical reinforcing mat or top and bottom steel as per the inside floor slabs?
 - *Yes, exterior concrete roadway should be reinforced per COW standard 3310.*
9. Are the exterior concrete sidewalks to be reinforced?
 - *No.*
10. Curbing is to be cast as integral or separate to the slab?
 - *Separate to the slab.*
11. How thick is the concrete in the parking lot and the concrete approach.
 - *For the concrete parking lot the following structure will be used:*
 - 200mm Reinforced Concrete*
 - 75mm Base Course*
 - 300mm Sub Base*
 - Geotextile Fabric*
 - Compacted Subgrade*
 - *For the concrete approach, use the following structure:*
 - 200mm Reinforced Concrete*
 - 75mm Base Course*
 - 375mm of 50mm limestone*
 - Geotextile*
 - Compacted Subgrade*
12. Are there details for the concrete curb
 - *Concrete curbs to be constructed as per SD-200 Curb and Gutter*