

---

**PART 1 GENERAL**

## 1.1 REFERENCE

- .1 Comply with the General Conditions of the Contract, Supplementary General Conditions and the requirements of Division 1.

## 1.2 RELATED WORK SPECIFIED ELSEWHERE

- .1 Site Engineering -1

## 1.3 SCOPE OF WORK INCLUDED

- .1 Supply and installation of Concrete Bases and Cigarette Debris Containers and Waste Receptacles.

## 1.4 SUBMITTALS

- .1 Submit shop drawings in accordance with Section 01340.
- .2 Clearly indicate fabrication details, plans, deviations, hardware and installation details.

**PART 2 PRODUCTS**

## 2.1 MATERIALS

- 1. Cigarette Debris Containers : 1 required

Manufacturer MFG ( Tel 888-672-0008 Fax 416-777-9867 )  
SuperTrashbox I c/w side Ashbox

Colour 509 BR Bright Red

- secure containers so that it can not be moved.

- container will be positioned by architect at the site

- 2. Orange Construction Fence :

Supplied and installed around entire perimeter of construction zone( including phased areas internal to the site )

Orange expanded construction fence mesh staked with iron T bars ( 8' with 3' set in ground @ 10' o.c. c/w tie wire on bottom and top cord and signed -

**NO ADMITTANCE FOR UNAUTHORIZED PERSONNEL**

**CONSTRUCTION ZONE**

Signed with tie wire at 25'- 0" around entire perimeter of project.

3. Architectural Concrete Bases

Manufactured by ArtForms - Tel # 1-905-642-3225  
- Fax # 1-905-642-3227

Supply and install formed concrete light standard base as manufactured by Artforms - Model # Kellamy 610R - ( 24" diam. ). Insure all concrete burrs are removed. 36" of concrete base to appear above finish grade. Review Site Plan Drawings - Architectural and Electrical.

**PART 3 EXECUTION**

3.1 EXAMINATION

- .1 Coordinate with Site Engineering to coordinate installation of any cast in place components or required openings.

3.2 INSTALLATION

- .1 Erect Work straight, plumb, level, and secured to prevent distortion or displacement or both.
- .2 Mechanically fasten all exterior furniture to concrete base so that they can not be removed.

END OF SECTION