
PART 1 GENERAL

1.1 REFERENCE

- .1 Comply with the General Conditions of the Contract, Supplementary General Conditions and the requirements of Division 1.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- .1 Unit Masonry Section 04200
[supply and install at wall/deck]
- .2 Aluminium Doors and Screens [install] Section 08410
- .3 Painting [install] Section 09900
- .4 Mechanical/Electrical Division 15/16
[supply and install at service penetrations]

1.3 SCOPE OF WORK INCLUDED

- .1 Supply of firestop installation where fire rated assemblies have been compromised or breached by horizontal and/or vertical penetrations at horizontal and/or vertical fire separations.

PART 2 PRODUCTS

2.1 MATERIAL - FIRE STOPPING

.1 Firestopping System I :

- .1 Fire resistant foam penetration sealant, Factory Mutual or ULC labelled; 3-6548 Silicon RTV Foam by Dow Corning Canada or Pensil 851 by Canadian Electric. Product to meet the required fire separation as shown on the floor plans or indicated in section.

PART 3 EXECUTION

3.1 INSTALLATION - FIRE STOPPING

- .1 System I : Seal gaps and holes in fire rated walls, ceilings and floor through which conduit, wire and cable, ductwork, piping and other protrusions pass as a result of all work other than that performed by Section 15 and Section 16. Install in strict accordance with silicone foam manufacturer's printed instructions.

END OF SECTION