

GENERAL NOTES

1. DO NOT SCALE DRAWINGS.

2. DRAWING WERE PREPARED BASED ON EXISTING DRAWING INFORMATION. CONTRACTOR TO REVIEW ALL SITE CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH WORK.

INSULATED AND SECURED HOARDING MUST BE CONSTRUCTED AND IN PLACE PRIOR TO BEGINNING DEMOLITION WORK.

4. COORDINATE EXACT DOOR ROUGH OPENING SIZE AND LOCATION WITH CITY OF WINNIPEG PRIOR TO

BEGINNING DEMOLITION WORK OR STEEL FABRICATION.

EXTERIOR WALL REPAIRS

1. THE INTENT OF THE EXTERIOR WALL REPAIR IS TO REMOVE EXISTING WATERPROOFING AND RESTORE THE ORIGINAL CONCRETE FINISH.

2. ALL EXISTING WATERPROOFING IS TO BE REMOVED FROM THE WALL SURFACE SUCH THAT NO DISCOLORATION REMAINS.

ALL PRECAST PANEL JOINTS ARE TO BE CLEANED OUT TO ACCEPT NEW JOINT SEALANT. 4. CONCRETE SURFACE IS TO BE SANDBLASTED TO REMOVE REMAINING CONTAMINANTS AND DELETERIOUS

SUBSTANCES AND TO APPROPRIATELY PROFILE THE SURFACE. THE PREPARED SURFACE IS TO RECEIVE 2 COATS OF 100 PERCENT SOLIDS SILANE SEALER.

6. REPAIR AREA APPROX 250'x16' (CONTRACTOR TO SITE CONFIRM)

WEATHERSTRIPPING

HOLLOW METAL DOOR


1. NEW DOOR TO BE STANDARD 3'x7' INSULATED HOLLOW METAL DOOR IN THERMALLY BROKEN FRAME. DOOR TO BE SUPPLIED PRIMED AND SITE PAINTED IN COLOUR TO BE CHOSEN BY OWNER


CONFIRM HARDWARE REQUIREMENTS WITH CITY OF WINNIPEG PRIOR TO ORDERING


4. DOOR HARDWARE LIST: HINGES 3CB 4 1/2"x4" 630 EXIT DEVICE VONDUPRIN 98E0 626 DOOR CLOSER LCN 4040 689 OVERHEAD STOP GLYN JOHNSON 100F US32D THRESHOLD KN CROWDER CT-75 W13S W50S DOOR SWEEP KN CROWDER

KN CROWDER

APEGIN Certificate of Authorization Crosier Kilgour & Partners Ltd. No. 235 Date: April 16, 2012







The General Contractor shall check & verify all dimensions and report any errors or omissions to the designers. WINNIPEG TRANSIT EXTERIOR WALL REPAIR AND NEW TANK ROOM DOOR 421 OSBORNE STREET, WINNIPEG, MANITOBA

PLANS, DETAILS AND GENERAL NOTES

JHC

S-1 HJL AS NOTED MARCH 2012 2011-0790

Sheet No.