



# BID OPPORTUNITY No. 469-2012 ADDENDUM No. 1

## 2012 RE-ROOFING OF THE BIOREACTOR BUILDING AT THE WEWPCC

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: June 15, 2012  
BY: Doug Berg, C.E.T.  
TELEPHONE NO. (204) 986-4452

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20120228

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

### **PART B – BIDDING PROCEDURES**

Add: B3.1(a) The Contract Administrator or an authorized representative will be available for a second site visit to be held at 1:30 pm on June 20, 2012 to provide Bidders access to the Site. Please meet at the WEWPCC's front Administration building.

### **PART E – SPECIFICATIONS**

Revise: E3.3 to read: The Contractor shall remove and stockpile whatever quantity identified by the Contract Administrator of the existing granular ballast material to a location on-site that is to be determined by the Treatment Plant Supervisor(s) and acceptable to the Contract Administrator.

Add: E3.3.1 Removed ballast material not selected to be stockpiled shall be hauled off site and disposed of by the Contract at his own expense.

Add: E3.4 The Contractor shall supply and install a metal pitch box at all penetrations through the roof using FillGard Pourable sealer as manufactured by Firestone, or an approved equal in accordance with B6.

Add: E3.5 All cable trays to be adequately supported by new C-ports and shall be C-port CX series rubber or an approved equal in accordance with B6.

Revise: E4.1.1 (a) to read: The Contractor shall remove and stockpile whatever quantity identified by the Contract Administrator of the existing precast paver stone material to a location on-site that is to be determined by the Treatment Plant Supervisor(s) and acceptable to the Contract Administrator.

Add: E4.1.1 (b) Removed precast paver stone material not selected to be stockpiled shall be hauled off site and disposed of by the Contract at his own expense.