



- Supply & Install New Engineered Wood Fibre Safety Surfacing
- Supply & Install New 2-Bay, 2 Baby Seat, 2 Belt Seat Swingset
- Supply & Install New 2-Tier Timber Edging w/ Pedra Cap
- Supply & Install New Crushed Limestone Pathway
- Supply & Install New Topsoil & Seed (By Others)
- Proposed New Senior Play Area +/- 186 SM Available Contains New Engineered Wood Fibre Safety Surfacing and New 2-Tier Timber Edging w/ Pedra Cap (Area May Be Reduced/Reshaped as per Design)
- Proposed Entrances into Play Areas
- Supply & Install New Multiflow Drainage Approx. 7m from Senior Play Area
- Supply & Install New Multiflow Drainage Approx. 7m from Junior Play Area
- Pick-Up & Install New Double-Sided English Park Sign
- Pick-Up & Install New Benches
- Pick-Up & Install New Sandbox
- Pick-Up & Install New Bench
- Pick-Up & Install New Accessible Picnic Table
- Supply & Install New Crushed Limestone Pad
- Proposed New Junior Play Area +/-137 SM Contains New Engineered Wood Fibre Safety Surfacing and New 2-Tier Timber Edging w/ Pedra Cap
- Supply & Install New Metal Slat W.R.

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Planning and Land Use Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	HF	CHECKED BY	
DRAWN BY	HF	APPROVED BY	
HORIZ. SCALE	1:400		
VERT. SCALE			
DATE	JAN/12		

MANAGER, PARK AND OPEN SPACES	DATE
MANAGER, PLANNING AND LAND USE DIVISION	DATE

DRAWING TITLE	DRAWING NO.
ARNOLD AVENUE PARK PLAYGROUND REDEVELOPMENT PROPOSED SITE PLAN	A.14-F
SITE ADDRESS	BID OPPORTUNITY NO.
75 Arnold Avenue	55-2012