

## DRAWING NOTES: ##

- 1. FLOAT AND THERMOSTATIC TRAP.
  PROVIDE BUCKET TRAP ON PRESSURE ABOVE 15 PSIG (100 KPA)
- 2. INSTALL SECOND TRAP ASSEMBLY WHEN INLET AIR TEMPERATURE IS BELOW 4°C.
- 3. 34" TEST VALVE C/W NIPPLE AND CAP.
- 4. 34" VACUUM BREAKER. LOCATE ON HORIZONTAL LENGTH OF PIPE.
  RUN 34" PIPE DOWN AND TERMINATE WITH OPEN END 150mm ABOVE FINISHED FLOOR.

## **SMS ENGINEERING**

**SMS Engineering Ltd.** Consulting Engineers 770 Bradford Street Winnipeg MB Canada R3H 0N3 Telephone 204.775.0291 Fax 204.772.2153 sms@smseng.com

CITY OF WINNIPEG
COOLING PLANT REPLACEMENT
151 PRINCESS STREET
BID OPPORTUNITY 887-2012

## STEAM HEATING COIL DETAIL. SINGLE BANK, 2-WAY CONTROL

Drawn By	Approved By	Reference
SMS	SMS	6088
File No.	Date	Detail Sheet
09-307-02	NOV 2012	MD-1