



496-2013 ADDENDUM 3

WAVERLEY WEST ARTERIAL ROADS PROJECT (WWARP) – PART 3 – CONTRACT 2 – ROUTE 90 TO ROUTE 165, OVERPASS (KENASTON BLVD.) AND ASSOCIATED WORKS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: September 5, 2013
BY: Coleen Groening
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20130301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Revise: E18.1 to read: The dynamic testing shall be performed by the Contractor to monitor and confirm hammer and driving system performance, assess pile installation stresses integrity, as well as to evaluate pile capacity. The Contractor shall secure the services on an independent Dynamic Testing Consultant with demonstrated experience in similar projects. Dynamic testing shall be performed on at least six (6) piles two (2) at each abutment and two (2) at the pier.
- Revise: E19.5.4 (e) to read: Type 4 Rock used for drainage material shall conform to Section 2.3 of CW 3120.
- Revise: E20.43.2 (a) to read: The Contractor shall use a mechanical screed to strike the surface of the superstructure concrete.