



Supply and Install Soil and Sod (867 SM)

Supply and Install 8' Tall, 2 Bay, 2 Belt and 2 Baby Seat Swings

Supply and Install Accessible Picnic Table

Supply and Install Granular Pathway (231 SM)

Supply and Install Engineered Wood Fibre Safety Surfacing (231 SM)

Supply and Install Subsurface Drainage and Tie Into Catch Basin (26 LM)

Supply and Install 2 Tiered Timber Edging (64 LM)

Supply and Install Composite Benches (x2)

Supply and Install Metal Slat Waste Receptacles (x2)

Supply and Install 2-12 Play Equipment & Independants

Supply and Install Double Sided Park Sign

Supply and Install Concrete Apron and Curb Cut (10 SM)

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG  
 Planning, Property and Development Department  
 Planning and Land Use Division  
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

|              |           |             |  |
|--------------|-----------|-------------|--|
| DESIGNED BY  | IL        | CHECKED BY  |  |
| DRAWN BY     | IL        | APPROVED BY |  |
| HORIZ. SCALE |           | DATE        |  |
| VERT. SCALE  | 1:400     |             |  |
| DATE         | JULY 2013 |             |  |

|  |      |
|--|------|
| MANAGER,<br>PARK AND OPEN SPACES           | DATE |
| MANAGER,<br>PLANNING AND LAND USE DIVISION | DATE |

|  |                     |
|--|---------------------|
| DRAWING TITLE  | DRAWING NO.         |
| <b>Goodridge Park<br/>PLAYGROUND REDEVELOPMENT<br/>Proposed Design</b> | <b>G.25-C</b>       |
| SITE ADDRESS   | BID OPPORTUNITY NO. |
| 34 Goodridge Crescent  | 551-2013            |