



NOTES:

1. COMPLETE AND SUBMIT RECORDS OF UNDERGROUND UTILITY LOCATES FOR INDICATED AREA, INDICATING: LOCATION PLAN OF EXISTING UTILITIES AS FOUND IN FIELD, CLEARANCE RECORD FROM UTILITY AUTHORITY, LOCATION PLAN OF RELOCATED AND ABANDONED SERVICES, AS REQUIRED. SEE SECTION 31 22 33 FOR ADDITIONAL DETAILS.
2. REMOVE OBSTRUCTIONS FROM SURFACES TO BE EXCAVATED WITHIN LIMITS INDICATED.
3. COMPLETE EXCAVATION OF PETROLEUM HYDROCARBON (PHC) IMPACTED SOILS. TOTAL IMPACTED AREA ESTIMATED TO BE 125 M2 TO DEPTHS UP TO 4 M BELOW GROUND SURFACE. TOTAL ESTIMATED VOLUME OF IMPACTED MATERIAL IS 500 M3. CONTRACT ADMINISTRATOR WILL DIRECT THE PROGRESSION OF THE EXCAVATION. SEE SECTION 31 22 33 FOR ADDITIONAL DETAILS.

DEPOSIT IN A LICENSED LANDFILL. SUBMIT TO CONSULTANT DISPOSAL PLAN FOR IMPACTED MATERIAL INCLUDING AT MINIMUM PROOF OF HAZARDOUS MATERIALS TRANSPORT LICENSE, AND LICENSED LANDFILL INFORMATION.
4. KEEP EXCAVATION FREE OF WATER WHILE WORK IS IN PROGRESS. WATER MAY BE IMPACTED WITH PHCS.

REMOVE IMPACTED WATER FROM SITE AND DEPOSIT IN A LICENSED LIQUID WASTE FACILITY. SUBMIT TO CONTRACT ADMINISTRATOR DISPOSAL PLAN FOR IMPACTED MATERIAL INCLUDING AT MINIMUM PROOF OF HAZARDOUS MATERIALS TRANSPORT LICENSE, AND LICENSED LANDFILL INFORMATION.
5. PROVIDE AND INSTALL ADEQUATE SAFETY FENCING FOR EXCAVATED AREA AT THE END OF EACH WORK DAY.
6. AT THE DIRECTION OF THE CONTRACT ADMINISTRATOR, BACKFILL THE EXCAVATION ACCORDING TO DETAILS PROVIDED IN SECTION 31 22 33.

LEGEND:

	APPROXIMATE LOCATION OF FORMER PUMP ISLAND
	ESTIMATED EXTENT OF REMEDIAL EXCAVATION
	AREA REQUIRING UTILITY CLEARANCE



SCALE: NOT TO SCALE



LONDON OTTAWA IQUALUIT
SASKATOON WINNIPEG

CLIENT NAME: CITY OF WINNIPEG
PROJECT ADDRESS: 1201 & 1215 ARCHIBALD ST, WINNIPEG, MB

PROJECT NAME: REMEDIATION: PUBLIC WORKS YARD
DRAWING TITLE: TENDER NOTES FOR REMEDIAL EXCAVATION

DESIGN: AB
DRAWN: STM
DATE: NOV/2014
FILE No: 14-5643-E

NO.	REVISION	DATE
0	ISSUED FOR TENDER	NOV 26, 2014
1		
2		

SHEET No. 1053-2014-
DRAWING_E1-R0