



# 1062-2014 ADDENDUM 1

## JEFFERSON EAST COMBINED SEWER RELIEF – CONTRACT 4 – SEMPLÉ OUTFALL

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: December 2, 2014  
BY: Paul Louden  
TELEPHONE NO. (204) 477-5381

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20131129

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

### **PART A – BID SUBMISSION**

Replace: 1062-2014 Bid Submission with 1062-2014 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Revised the following items:
- A.1 b) Revised payment terms, added E13 reference
  - A.6 a) i) Changed size (250 mm to 150 mm)
  - A.14 Revised quantity 100 to 84
  - E.1 Revised quantity
  - E.3 Revised quantity
  - E.4 Revised quantity
  - E.6 Revised quantity

### **PART D – SUPPLEMENTAL CONDITIONS**

Delete: D17.3

### **PART E – SPECIFICATIONS**

- Add: E.12.6 CSP Backfill
- a) Bedding and initial backfill shall be as per CW3110, Clause 2.2, Table 3110.2.
- Add: E13.1.2 Corrugated Steel Pipe
- a) 2200 millimetre Pipe- corrugation profile 125x25.
  - b) Pipe shall have aluminum coating as per CSA G401.
- Add: E13.2.3 a) Submit Shop Drawing for outfall section, including details of cut profile and cut treatment.

- Add E13.3 c)
- i) Isolate all galvanized accessories, railings and gratings from aluminized pipe by means of non-metallic isolation washers and hole sleeves to completely separate galvanized and aluminized surfaces.
  - ii) Isolate aluminum CSP surface from concrete connection collar by asphaltic mastic coating.
- Add: 13.4.2
- Measurement and payment for the corrugated steel outfall section shall be on a lump sum basis and shall include pipe supply, installation and bedding, concrete connection collar, hook bolts in CSP and all other items incidental to the Works.