


- Pick Up and Install Accessible Picnic Table
- Pick Up and Install Double Sided Park Sign
- Pick Up and Install Metal Slat Waste Receptacles (x2)
- Supply and Install 8' Tall, 2 Bay, 2 Belt, 2 Baby Swing Swing Set
- Supply and Install Bollards (x 38) Bollards on West Side of Property to have Chain Installed (27LM)
- Supply and Install 2 Tiered Timber Edging with Cap (53 LM)
- Supply and Install 2-5 Playstructure and Independent Components
- Supply and Install Engineered Wood Fibre Safety Surfacing (238 SM) w/ approx. 25 LM of Subsurface Drainage



CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG  
 Planning, Property and Development Department  
 Planning and Land Use Division  
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	IL	CHECKED BY	
DRAWN BY	IL	APPROVED BY	
HORIZ. SCALE		MANAGER,	DATE
VERT. SCALE	1:200	PARK AND OPEN SPACES	
DATE	JAN 2014	MANAGER,	DATE
		PLANNING AND LAND USE DIVISION	

DRAWING TITLE  
**Muriel Street Park**  
**PLAYGROUND REDEVELOPMENT**  
 Proposed Playground Design

SITE ADDRESS 692 Muriel Street

DRAWING NO.  
**M.45-D-R1**

BID OPPORTUNITY NO.  
**129-2014**