



329-2014 ADDENDUM 1

NORTH KILDONAN FEEDERMAIN REPLACEMENT

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: May 7, 2014
BY: Colin McKinnon
TELEPHONE NO. (204) 942-6391

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Revise: E21.3 (e) to read:

Polyethylene fittings: to CAN/CSA B137.1 or AWWA C901. Ductile iron backup flange to Class 150, ANSI B16.1/16.5 with stainless steel bolts and nuts, with neoprene or red rubber gasket.

Revise: E21.4 (g) to read:

Grade of pipe to be 290 MPa and to be 9.50mm thick.

Revise: E23.5 (e) to read:

The tensile strength at yield of the butt-fusion joints shall not be less than the pipe. All joints shall be logged. The log on each joint shall include the name of the certified operator, time, date, diameter, wall thickness, heating plate, temperature, fusing time and cool down time. The operator shall immediately report to the Contract Administrator any joint that fails.

Add: E22.7 (b):

Number of lugs to match the restraint retainer ring.