



473-2014 ADDENDUM 2

DEACON BULK CHEMICAL BUILDING RAIL SHED INSULATION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: July 24, 2014
BY: Lindsay Cook
TELEPHONE NO. (204) 986-3673

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Revise: E3.2.1(c) to read: Spray on foam roofing material shall be type FE 348 – 3.0 Series Roofing System as manufactured by BASF or Quik Shield ® I 125 as manufactured by SWD Urethane.
- Revise: E3.2.2(d) to read: The roofing membrane's tensile strength shall be in accordance with ASTM D-412 with a minimum strength value of 1100 psi and a minimum elongation value of between 200 and 300 percent.
- Revise: E3.2.2(e) to read: The roofing membrane shall have a flash point greater than 93.3°C (200° F) and shall be in accordance with ASTM D-56 (TCC) or shall be certified to UL 790 Class A Rating.
- Revise: E3.2.2(g) to read: Roofing membrane shall be UC – 540 Aluminum Polyurea Hybrid Roofing Elastomer as manufactured by Urecoat or Rhino Eco-Coat I Aluminized Hybrid Polyurea Coating as manufactured by Rhino Linings.
- Revise: E4.2.1(c) to read: Spray on foam insulation material shall be type WALLTITE® Eco v.3 by as manufactured by BASF or Quik Shield ® I 112 as manufactured by SWD Urethane.