

559-2014 ADDENDUM 1

CONSTRUCTION OF A COMMUNITY RESOURCE RECOVERY CENTRE(4R WINNIPEG DEPOT) AT THE BRADY ROAD RESOURCE MANAGEMENT FACILITY, INCLUDING ROADWORKS AND BUILDING

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: July 10, 2014
BY: Ash Raichura, P.Eng.
TELEPHONE NO. (204) 453-2301

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 559-2014 Bid Submission with 559-2014 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Add Item No. B.1 iv) 610 mm Diameter x 9 m Long (18 Units).
- Form B(R1): Add Item No. B.1 v) 610 mm Diameter x 11 m Long (5 Units)
- Form B(R1): Add Item No. B.2 vi) HHW Foundation.
- Form B(R1): Add Items No. C.3 i) through iii) inclusive.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: D2.1.2(b): Cast-in-Place Concrete Pile Foundations (for buildings, light standards, and miscellaneous structures).
- Add: D2.1.2(f): Structural steel framing for HHW Building.

PART E – SPECIFICATIONS

- Add: E3.2.2(f) All structural steel fabrications and connection details.
- Revise: E16.24.1 Anchor bolts and reinforcing bar dowels projecting out of cast-in-place concrete pile foundations shall be aligned with a steel template to ensure the required geometry of the projecting items is achieved. The setting template shall be rigidly secured to the anchor bolts and/or reinforcing bar dowels. Anchor bolts shall be plumb. Extreme care shall be used in this operation. Placement of cast-in anchor bolts and/or reinforcing bar dowels without the steel template will not be permitted.
- Add: E16.38(a)(iv) 610 mm Diameter by 8 m Long
- Add: E16.38(a)(v) 610 mm Diameter by 11 m Long
- Revise: E17.8.1(b)(vi) HHW Foundations (excluding Piles)

- Revise: E19.7.1 Roll-Off Bin Guide Rail Assembly will be measured on a unit basis. Handrail and Guardrail will be measured on a lump sum basis. Miscellaneous Metal will be paid for at the Contract Unit Price for "Items of Work" listed here below. The amount to be paid for will for work done in accordance with this Specification, Drawings, and accepted and measured by the Contract Administrator.
- Delete: E19.7.2(a)(ii)
- Delete: E19.7.2(a)(iii)
- Delete: E19.7.2(a)
- Delete: E19.7.2(b)
- Add: E19.7.2(a)(i) Roll-Off Bin Guide Rail Assembly
- Add: E19.7.2(a)(ii) Handrail and Guardrail
- Add: E19.7.2(b) Supply and installation of anchor bolts shall be considered incidental to the Work and no separate payment will be made.
- Add: E19.7.2(c) Supply and installation of post-installed anchors or fasteners of any type shall be considered incidental to the Work and no separate payment will be made.
- Revise: E21.1 This Specification shall cover all operations relating to the supply, fabrication, and erection of the all architectural works shown on the Drawings and as specified herein. Structural works related to buildings (excluding foundations) shall be considered incidental to the architectural works.
- Revise: E21.2.1 Refer to the Drawings and Division 01, Division 05, Division 06, Division 07, Division 08, Division 09, Division 10, for Scope of Work.
- Revise: E21.4 Refer to the Drawings and Division 01, Division 05, Division 06, Division 07, Division 08, Division 09, Division 10, for Materials and Construction Methods.
- Revise: E21.5 Supplying and installing architectural works will not be measured. This Work shall be paid for at the Contract Lump Sum Price for the "Items of Work" listed here below, which price shall be payment in full for supplying all materials and for performing all operations herein described, Division 01, Division 05, Division 06, Division 07, Division 08, Division 09, Division 10, and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator.
- Add: E21.5.3 All structural works related to the supply, fabrication and erection of buildings (exclusive of foundations) as described herein and as shown on the Drawings shall be considered incidental to the Architectural Works, and no separate measurement or payment will be made.
- Revise: E22.2.1 Refer to the Drawings and Division 01, Division 26, Division 27, Division 28, for Scope of Work.
- Revise: E22.4 Refer to the Drawings and Division 01, Division 26, Division 27, Division 28, for Materials and Construction Methods.
- Revise: E22.5 Supplying and installing electrical works will not be measured. This Work shall be paid for at the Contract Lump Sum Price for the "Items of Work" listed here below, which price shall be payment in full for supplying all materials and for performing all operations herein described, Division 01, Division 26, Division 27, Division 28, and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator.
- Revise: E23.2.1 Refer to the Drawings and Division 01, Division 21, Division 22, Division 23, Division 33, for Scope of Work.

- Revise: E23.4 Refer to the Drawings and Division 01, Division 21, Division 22, Division 23, Division 33, for Materials and Construction Methods.
- Revise: E23.5 Supplying and installing mechanical works will not be measured. This Work shall be paid for at the Contract Lump Sum Price for the "Items of Work" listed here below, which price shall be payment in full for supplying all materials and for performing all operations herein described, Division 01, Division 21, Division 22, Division 23, Division 33, and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator.
- Delete: E24.11
- Revise: E24.34 Supply and installation of barrier gates will not be measured and paid for at the Contract Lump Sum Price for "Barrier Gates", which price shall be payment in full for supplying all materials and for performing all operations herein described, and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator.
- Revise: E25.2.1 Refer to the Drawings and Division 13, for Scope of Work.
- Revise: E25.3.1 Refer to the Drawings and Division 13, for Materials and Construction Methods.
- Revise: E25.4.1 Supply and installation of prefabricated kiosk building will not be measured and paid for at the Contract Lump Sum Price for "Prefabricated Kiosk Building", which price shall be payment in full for supplying all materials and for performing all operations herein described, Division 13, and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator..
- Revise: E26 Weigh Scale
- Revise: E26.2.1 Refer to the Drawings and Division 13, for Scope of Work.
- Revise: E26.4 Refer to the Drawings and Division 13, for Materials and Construction Methods.
- Revise: E26.5 Supply and installation of weigh scale will not be measured and paid for at the Contract Lump Sum Price for "Weigh Scale", which price shall be payment in full for supplying all materials and for performing all operations herein described, Division 13, and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator.

NMS SPECIFICATIONS

Add: Section 051223

Add: Section 083612

Revise: Section 087110

2.2.2.2.2 Provide construction cylinder cores and final cores with keying to the City's MEDICO master key system.

Add: Section 233300
Section 233315
Section 233720
Section 235501
Section 238239.01

Add: Section 253002
Section 259001

Add: Section 262920

DRAWINGS

Replace: 559-2014 _Drawing_C2-R1 with 559-2014 _Addendum_1-Drawing_C2-R2

559-2014 _Drawing_A2-R1 with 559-2014 _Addendum_1-Drawing_A2-R2

559-2014 _Drawing_E1-R1 with 559-2014 _Addendum_1-Drawing_E1-R2

559-2014 _Drawing_E5-R1 with 559-2014 _Addendum_1-Drawing_E5-R2

559-2014 _Drawing_E6-R1 with 559-2014 _Addendum_1-Drawing_E6-R2

559-2014 _Drawing_E7-R2 with 559-2014 _Addendum_1-Drawing_E7-R3

Add: 559-2014 _Addendum_1-Drawing_A6-R1

559-2014 _Addendum_1-Drawing_A7-R1

559-2014 _Addendum_1-Drawing_A8-R1

559-2014 _Addendum_1-Drawing_A9-R1

559-2014 _Addendum_1-Drawing_A10-R1

559-2014 _Addendum_1-Drawing_E11-R1

559-2014 _Addendum_1-Drawing_E12-R1

559-2014 _Addendum_1-Drawing_M3-R1

559-2014 _Addendum_1-Drawing_S11-R1

559-2014 _Addendum_1-Drawing_S12-R1

559-2014 _Addendum_1-Drawing_S13-R1